

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public works DEPARTMENT

G.O. No.	2636A	Press
~~B.P. No.~~		~~Mis.~~
424-275		
Dated	29-10-	1951/873

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
29th October 1873.*

No. 474. Read the following letter from Colonel E. A. FOORD, R.E.,
Inspecting Engineer for Civil and Military Buildings, to Colonel G. W.
WALKER, R.E., Secretary to Government, Public Works Department,
dated Chepauk, 4th October 1873, No. 1,247 :—

WITH reference to G. O., No. 183, dated 29th September 1873, I have the
honour to forward, for the sanction of
Government, the plan and estimate of
Rupees 600 (now altered to Rupees 590)
for improving the cook-room chimnies of the families of the 1st Battalion, 21st
Fusiliers in Fort St. George.

2. The District Engineer, Presidency, has been requested to conform more
strictly to the course laid down in paragraphs 75 and 76, Chapter V., of the Public
Works Code.

No. 475.

ORDER THEREON, 29th October 1873, No. 2,636A

MILITARY WORKS, No. 27.

SANCTIONED and funds allotted from
the Reserve under Military.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Inspecting Engineer for Buildings.
„ District Engineer, Presidency.
„ Officiating Controller of Public Works Accounts.
„ Military Department.

Exd. S. T. Austin.
Spare Copies.

No 284 of 1872

123

Specification to accompany
an Estimate for improving the
Cook room Chimneys of the Families
of 1721 St Fusiliers in Fort Saint
George.

Amount of Estimate Rupees 600

The present old chimneys to
be demolished and large chimneys
substituted flues to be enlarged
Sheet iron blowers to be supplied
to the fire places.

Fort St George

30th Augt 1872

W. J. J. J. J.

L. H. M. R. 6

William D. District Engineer
Copied by
Chumaley Compd

224

Enclosure in a letter No. 4247 of 4th October/73
 D.O. No. 2636 A. 29-10-73
 P. W. 5450/73.
 Specification for improving
 the Cookroom Chim-
 neys of the Families
 of the 21st Fusiliers in
 Fort St. George.
 Amount of Estimate Rs. 598

Work — Improving the cookroom chimneys of the Families
 of the 21st Fusiliers in Fort Saint George as called for in Dy.
 Arch Dr. Mr. General's No. 2447 dated 5th July 1873.

Quantity	Description of work	Rate	Per	Amount	Total
	Body hire for demolishing the presents chimney & removing rubbish			10	
14	byds of excavating earth & refilling	2	byd	1	12
19	ft of cutting hard masonry	1	ft	1	3
176 1/2	Brick work in chimney	3		33	27
2.25	Sq of plastering the chimney with two coats of chunam	2	56 Sq	5	4 5
	Smiths pooly hire for making old sheet iron caps with iron uprights			2	4
17	Old sheet iron blowers in front of arch-ways to prevent smoke including fixing			12	
	Sundries			1	
	For 1 chimney			46	
	For 13 chimneys			598	
	Deduct for walls				
	Add for fractions			2	
	Total Estimate Rupees				600

Fort St. George
 30th August/73

Signed J. Goddard Lieut Col R.E.
 District Engineer Presidency

Signed D. Lissinburg Lieut
 Barrack Master

M. Ford Colonel R.E.
 Inspecting Engineer for
 Civil & Mil. Buildings

Approved, By Order
 Signed E. M. Norris Major
 Dy. Arch Dr. Mr. General's District

Pr 5450
Govt. of 1873 Madras.

PUBLIC WORKS.

To *The Inspecting Engs
for Districts*

Dated

Recd.

Encl. 3

G. O. 29th Oct. 1873, 2036.

Nos. 474 & 475

Cook Room Chimnies.

Plan & Est. for improving
the Cook Room Chimnies
of the families of the 1st
Battalion, 21st Fencibles
in Fort St George, Sanctions
& funds allotted from
the Reserve under Military.