M.R.O. 1—10,006—28-2-50.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No. 2725A	Press
B.P.—No. 1244-1248	Mis.
Dated 7.11.1873	195—

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 7th November 1873.

No. 124A. Read the following letter from Colonel E. A. FOORD, R.E., Inspecting Engineer for Civil and Military Buildings, to Colonel G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Chepauk, 27th October 1873, No. 1,353 :—

WITH reference to G. Oos., Nos. 82 and 151, dated 10th September 1872 and 23rd July 1873, respectively, I have the honour to forward, for the sanction of Government, estimates accompanied by plans and specifications for the under-mentioned works in the Bellary District:—

2 Abstract Estimates.
2 Specifications.
2 Plans.
1 Site Plan.

I.—Estimate for constructing a block of barracks for the European Infantry, Rs. 58,000.
II.—Do. do. for a band barrack for do. ,, 37,600.

2. The designs for the above buildings have been prepared in accordance with the existing blocks of barracks for the European Infantry. The verandahs are to be roofed with a light description of the ordinary terrace, instead of the Bengal sloping terrace, as most of the buildings at Bellary having the latter kind of roof are found to leak considerably. There is not much difference in the cost of the two kinds of roof.

3. The plans and estimates for the proposed buildings and the sites for the same have been approved by the local Military authorities and by His Excellency the Commander-in-Chief. The requirements of paragraphs 96 and 97, Chapter V. of the Public Works Code, have been attended to.

No. 124B. ORDER THEREON, 7th November 1873, No. 2,725A.

MILITARY WORKS, No. 1A.

HIS EXCELLENCY the Governor in Council sanctions the plans with estimates, amounting, respectively, to Rupees 58,000 and 37,600, for the provision of the barrack accommodati n required for the European Infantry Regiment at Bellary. It is observed that the designs are in accordance with the existing blocks of barracks, and properly so, as any departure from them to suit modifications introduced since the construction of those buildings would have a bad effect.

2. A sum of Rupees 10,000 is provided for the work by transfers in anticipation of the sanction of the Government of India from the grant for the Madras Telegraph Office, and the District Engineer will be expected to make proper arrangements for its utilization. In the event of an application which has been made to the Government of India proving successful, additional funds will be available if they can be expended this year.

(True Extract.)

(Signed) G. W. WALKER, Colonel, R.E.,
Secretary to Government.

To the Inspecting Engineer for Buildings.
,, District Engineer, Bellary.
,, Officiating Controller of Public Works Accounts.
,, Military Department.

Exd. E. C. Shunker.
Spare Spare

Report to accompany the Estimate for Constructing a Band Room to the European Infantry at Bellary

Amount of Estimate Rupees 40500

1. The Band Room is to be built agreeably to accompanying Plan, and is to be raised on a foundation 4 feet high with a basement 1½ high the whole to rest on a bed of concrete 12" thick.

2. The principal walls are to be 22¼ high and 2 in thickness.

3. The verandah walls to be 17½ high and 2 thick

4. The pillars are to be 9½ high and 1½ Square

5. The foundations basement and walls above are to be built with hammer dressed stone in chunam

6. Bond stones are to be placed at intervals of 6 feet in the clear.

7. The roof to the main building and Verandah rooms is to be a Pucka Terrace.

8. The Verandah roof is to be a light Pucka Terrace consisting of Brick on edge 2 Jelly and courses of flat tiles and 3 coats of plaster.

9. The whole of the wood work to be of the best

...men Teak, well seasoned and wood oiled ——

10. The flooring is to be of slabs 18 Square pointed with chunam, and stone flags to all the openings ——

11. The walls are to be plastered inside and out with 3 coats of chunam ——

Bellary
2d August 1873

Lieut Blackburn
Sub Engineer D.P.W.

Attn Engrs

From The Officer commanding
Bellary Range

To The District Engineer
Bellary

Dated 2d } Inquiry
Do } August 1873

Plan & estimate for the Barrack for a Band Room & the European Infantry at Bellary.

Report to accompany the Estimate for [illegible] of Barrack to the European Infantry at Bellary

Amount of Estimate Rs. 60,000 [illegible]

B

1. The Barrack is to be built agreeably to accompanying Plan, and is to be raised on a foundation 4 feet high, with a basement 1½ high, the whole to rest on a bed of concrete 12" thick.

2. The principal walls to be 22½ high and 2' in thickness.

3. The verandah walls to be 17½ high and 2' thick.

4. The pillars are to be 9½ high and 1½ Square.

5. The [illegible] basement [illegible] to be built with hammer dressed stone in chunam.

6. Bond stones are to be placed at intervals of 6 feet, in the clear.

7. The roof to the main building and Verandah rooms is to be a Puchah Terrace.

8. The Verandah roof is to be a light Puchah Terrace, consisting of Brick on edge, 2 Jelly — 2 courses of flat tiles and 3 coats of plaster.

9. The whole of the wood work to be of the best Nonlmein Teak, well seasoned, and well oiled. —— —

flooring is to be of slabs 18 square, pointed with chunam, and stone flags to all the openings.

11. The walls are to be plastered inside and out with 3 coats of chunam.

Ballarat
22nd July 1873

Sub Engineer D.S.P.W

OFFICE OF THE INSPECTING ENGINEER
FOR CIVIL AND MILITARY BUILDINGS,

Bellary District.

Enclosure in a Letter
No. 1353 dated 27 Aug 73

40 Rs. 2725 4-7-11-73

P.W. 5862/73
5

Specification Report to accompany Estimate for Constructing a New Block of Barrack for the European Inf.y at Bellary.

Dep.t No 5725

Estimate Rs. 58,000.

flooring is to be used.

Bellary District.

Enclosure in a Letter
No. 1353 dated 27 Oct. 73

L.B. No: 2725-A-7-11-73

P.W. 5862/73
3/11

Specification Report
to accompany Estimate
for Constructing a Band
Room for the European
Infantry at Bellary.
Lg. 18225

Estimate Rs. 37,600.

OFFICE OF THE INSPECTING ENGINEER
FOR CIVIL AND MILITARY BUILDINGS,
Chepauk, 27 October 1873.

No. 1353

From

THE INSPECTING ENGINEER
FOR CIVIL AND MILITARY BUILDINGS,

To

The Secretary to Government
Public Works Department

SIR,

Enclosures 7-
1 abstract
estimates
specifications
Plans
site plan

With reference to G.O. Nos. 82 and 151, dated 10th September 1872 and 23rd July 1873 respectively, I have the honor to forward for the sanction of Government estimates accompanied by plans and specifications for the undermentioned works in the Bellary District.

i. Estimate for constructing a block of Barracks for the European Infantry ——— Rs. 58,000

ii. —D:— —D:— for a Band Barrack for —D:— ——— 37,600

2. The designs for the above buildings have been prepared in accordance with the

the existing blocks of Barracks for the European Infantry. The verandahs are to be roofed with a light description of the ordinary terrace, instead of the Bengal sloping terrace, as most of the buildings at Bellary having the latter kind of roof are found to leak considerably. There is not much difference in the cost of the two kinds of roof.

3. The plans and estimates for the proposed buildings and the sites for the same have been approved by the local Military authorities and by His Excellency the Commander in Chief.

The requirements of paragraphs 96 and 97, Chapter V of the Public Works Code have been attended to.

I have the honor to be
Sir
Your Most Obedient Servant
E.V. Ford Colonel R.E.
Inspecting Engineer for
Civil & Military Buildings

successful additional funds will be available if they can be expended this year.

Copies

J.C. for Rec
& E. Bellary
Contr. P. Wks
Mily Departt

J.C. sent 21/11/73

A — B.
No. 124 - 124

P. W. 1873 Departt.
No. 5862.
No. 1353

From

The Inspecting Engineer
for Buildings,

To

The Secretary
to Government Mad.

3 Plans sent up with the
for C.D. 364 377 -
Encl. 4 65.1.77

Dated 28 October 1873.
Recd. 29 X5

Forwards for
sanction 2 estimates
for constructing a
block of Barracks
& a Band Barrack
for the European Infty
at Bellary.

Faithfully

A

No. 1725 A

His Excellency the Governor in Council
sanctions the plans with estimates a-
mounting respectively to Rs 58,000 and 37,600
for the provision of the Barrack accommo-
dation required for the European Infantry
Regt at Bellary. It is observed that the
designs are in accordance with the
existing blocks of Barracks, and, properly
so, no departures from them
exist modifications introduced since the
construction of those Buildings would
have a bad effect.

A sum of Rs 10,000 is provided
for the work by transfers in anticipation
of the sanction of the Govt of India from the
grant for the Madras Telegraph Office and the
District Engineer will be expected to make
proper arrangements for its utilization.
In the event of any application which has been
made to the Govt of India proving

Ch. 582

27254

7-11-1873

Govt. of {1873} Madras.

PUBLIC WORKS.

To The Executive Engr
for Buildings

Dated

Recd. Encl. 5

G. O. No. W. - 1873.

Nos. 12 & 12A to 12

Barracks. Estimates

For providing barrack accommodation for the European Infantry Regt at Bellary, sanctioned.