M.R.O. 1—10,006—28-2-50.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public Works. DEPARTMENT

G.O. No.	2814	Press
~~B.P. No.~~ 292-293		~~Mis.~~
Dated	20-11-1873	~~195~~ .

Not to be folded or roughly handled

No. 292. Read the following endorsement of the Inspecting Engineer for Civil and Military Buildings, dated Coonoor, 22nd October 1873, No. 1,350 :—

From G. S. SAGE, Esq., District Engineer, Cuddapah, to Colonel E. A. FOORD, R.E., Inspecting Engineer for Civil and Military Buildings, dated Cuddapah, 8th October 1873, No. 1,343.

With reference to G. O., No. 2,042, of 27th August 1872, I have the honour to forward a plan of the Pullumpett Cutcherry, also an estimate for Rupees 980 for repairing the building, and to observe as follows.

2. The building is not a good piece of work, the principal defects being :—

1st.—That the foundations have not been carried down to depth shown in original estimate, but as shown in the accompanying plan, where it will be observed no depths are given, but if scaled various depths will be measured and so it has been built. I propose to protect the foundations by a wall all round building at a distance of 6 feet from main walls, the space contained by it to be covered with 4 inches of concrete plastered to prevent water from roof getting to foundations.

2nd.—The roof is said to leak, I think, simply from absorption as lime and plastering is bad. I purpose to remedy this by a thick coat of hot coal tar, to be covered with sharp coarse sand, which will form a kind of asphalte, and which I have found very effective elsewhere.

3rd.—The floor of entrance passage three sides of verandah, Tahsildar's room, Cutcherry room, and central court was originally chunamed, but it is now quite broken up owing to the traffic. I propose these portions should be asphalted.

4th.—The other items of estimate require no remark, being ordinary repairs.

3. I have the honour also to report that the work is in hand, and that a further allotment of funds for repairs to building is required in my district as the Budget grant is already exceeded.

4. The value of the building is Rupees 9,208 ; it was erected in 1867-68, since when Rupees 277 have been spent on it in repairs.

The District Engineer having explained, in person, the state of the building and the repairs to be made, the plan and estimate received with this letter are forwarded for the orders of Government, with reference to G. O., No. 2,042, dated 27th August 1872.

1 Plan.
1 Estimate.
1 Specification.

(Signed) E. A. FOORD, Colonel, R.E.,
Inspecting Engineer for Civil and Military Buildings.

No. 293. Order thereon, 20th November 1873, No. 2,814.

CIVIL WORKS, No. 18.

It is presumed that the Inspecting Engineer for Buildings has satisfied himself as to the adequacy of the remedies proposed by the District Engineer of Cuddapah for the alleged insecu-

rity of the foundations of the Pullumpett Taluq Cutcherry. The estimate now submitted appears to provide for new work or improvements to the extent of Rupees 630 out of Rupees 980, for concrete round the foundations and asphalting of floors, which sum is accordingly provided from the Reserve under Provincial, leaving the balance of Rupees 350 for repairs to be provided by a future adjustment of the Provincial Repair allotments of all districts.

(True Extract.)

No. 2814 Read
Pro. of the Madras Govt.
Read the following

From the Inspecting Engr for Bldgs No. 1350 of 22 Oct 73
Buildings

It is presumed that the Inspecting Engineer for Buildings has satisfied himself as to the adequacy of the remedies proposed by the District Engineer of Cuddapah for the alleged insecurity of the foundations of the Pullumpett Taluk Cutcherry. The Estimate now submitted appears to provide for new work or improvements to the extent of Rs. 630 out

of Rs 980. for 30 Concrete
round the foundations
& asphalting of floors
which sum is accordingly
provided from the Reserve
under Provincial, leaving
the balance of Rs 350.
for repairs to be provided
by a future adjustment
of the Provincial Repair
allotments of all Districts.

Cmtd.

32

To Mr Engineer Jambusar
" Dr Engineer Ankleshwar
" Cmtr

No 292-93.
Signed Sdh. Collector
Dated 24/11/93

of Rs 980. for 35 Cubic
round the foundations
& asphalting of floor
which sum is accordingly
provided from the Reserve
under Provincial, leaving
the balance of Rs 350.
for repairs to the provin
by a future adjustme
of the Provincial Repair
allotments of all Distri

Cl 5859

Govt. of {1873} Madras.

PUBLIC WORKS.

To the Inspecting Engr
for Buildings

Dated

Recd. Encl. 3.

G. O. 20th Nov. No. 2814.

Nos. 292 & 293

Taluq Cutcherry at Pul-
lampett, Cuddapah Dt:
Papers orders on letter
from the Inspg. Engr. for
Buildings submitting an
Est. for the repairs to the
Cutcherry.

To the Inspecting Engr for Buildings
& Engr Cuddapah
& Collr
No. 292-93. Copies of the Order
Dated 24/11/73