M.R.O. 1—10,006—28-2-50.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public works DEPARTMENT

G.O. No. 3055		Press
~~B.P. No.~~ 323-324		~~Mis.~~
Dated 19-12-1873		~~195~~ .

Not to be folded or roughly handled

No. 323. Read the following endorsement of the Chief Engineer for Irrigation, dated Ellore Canal, 22nd November 1873, No. 51 :—

From J. H. LATHAM, Esq., Chief Engineer and Manager of the Madras Irrigation and Canal Company, to Lieutenant-Colonel J. MULLINS, R.E., Chief Engineer for Irrigation and Joint Secretary to Government, Public Works Department, dated Kurnool, 8th November 1873, No. 164.

29th mile Repairs on Capital Account. Soonkesala Head Sluice Screws.

I HAVE the honour to enclose a supplemental estimate for the face wall built this year in the 29th mile of Main Canal, amounting to Rupees 400,* and to request you to lay it before Government for sanction.

	Rs.
* Sanctioned, G. O., No. 1,427, of 26th May last	5,145
Supplement overspent	400
Total ...	5,545

2. The excess seems only due to the contractor having excavated the foundations for carrying the face wall five or six yards farther into the existing puddle slope than I had intended this season. I let him build the wall accordingly, not thinking that the estimate would be exceeded. The wall costs about Rupees 75 a yard run, at least, at that end.

2. I also enclose for sanction an indent for completing the raising screws of Soonkesala head sluice (including one spare one). I think a very efficient apparatus may be fixed at Rupees 160 per sluice, in which the square threaded screws will have half an inch pitch, and the turning parts work on brass. The whole cost of screws will be included in the estimates for 1873-74 now preparing.

SUBMITTED to Government, with a recommendation that the supplemental sanction required for the face wall in the 29th mile be granted.

2. The indent has been disposed of in this office.

(Signed) J. MULLINS, Lieut.-Colonel, R.E.,
Chief Engineer for Irrigation.

No. 324. ORDER THEREON, 19th December 1873, No. 3,055.

IRRIGATION, No. 19.

RUPEES 400, in addition to the sum of Rupees 5,145 passed in Government Order No. 1,427 of the 26th May 1873, are sanctioned for the new face wall in the 29th mile of the Madras Irrigation and Canal Company's Main Canal.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Chief Engineer for Irrigation.
" Chief Engineer and Manager of the Madras Irrigation and Canal Company.
" Examiner of the Madras Irrigation and Canal Company's Accounts.
Exd. S. T. Austin.
Spare Copies

No 57.

Submitted to Government with a recommendation that the supplemental sanction required for the face wall in the 29th mile be granted.

2. The indent has been disposed of in this office.

Office of the Chief Engr for Irrigation Ellore Canal 22. Novr 1873

Lieut-Colonel
Chief Engineer for Irrigation

To The Secretary to Govt PWD

P. W. 1873 Departm

No. 6461

From The Chief Eng

for Misa

To The Secretary

Wa

No. 57.

Dated 22nd
Recd. 28th } Nov

Encls: 3.

Submits for a
tion supplementar
timate for Face
wall built in
29th mile of the
I H Co's Canal

with an Order

3255

Letter to Engineer Dept. Ottawa
Contract No. 5145 for extra work on Lachine
Canal Contract No. 1427 of the 25th May 1873 and
wall in the 29th mile of the Canada Colonization

Chief Engineer for Superintendence
Chief Engineer & Manager M. & L. R. R. Co.
Examined & the M. & L. R. Co's Accounts

Chief Engineer & Manager M. & L. R. R. Co.

Dec 20/12/73

W.H. 24/11/73

h: 323-24

Dir 2 Dec 73

Ch 6466

Govt. of {1873} Madras.

PUBLIC WORKS.

To The Chief Engr. for Irrigation

Dated

Recd.

Encl.

G. O. 19 Dec 1873. 3055

Nos. 323 & 324

Re. Estimate Canal. Rep.

Supplemental Estg. No: 400 for the new face wall on the 29th Mile of the Canal, sanctioned.