M.R.O. 1—10,006—28-2-50.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____ .

MADRAS RECORD OFFICE

Government of Madras

Public works DEPARTMENT

G.O. No.	3069 D	Press
~~B.P. No.~~		~~Mis.~~
427G. 427H 427I		
Dated	27-12-1873	~~195~~ .

Not to be folded or roughly handled

Read the following papers :—

No. 427G. From Colonel E. A. FOORD, R.E., Inspecting Engineer for Civil and Military Buildings, to Colonel G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Chepauk, 18th September 1873, No. 1,135.

I HAVE the honour to submit, for the sanction of Government, three revised estimates, in the form of comparative statements, for completing the undermentioned Subsidiary Jails in the district of South Arcot :—

3 Comparative Statements.
1 Estimate.

I.—Sub-Jail at Thittagoody.
II.—Do. at Virdachellum.
III.—Do. at Porto Novo.

2. In G. O., No. 1,999, dated 12th August 1873, a sum of Rupees 1,445 is granted for the first, and Rupees 1,100 for the second work, and Rupees 700 allotted in the current year's Budget for the Sub-Jail at Porto Novo.

3. The revised estimates exceed the original estimates by Rupees 536, Rupees 814, and Rupees 202, respectively. The balances now requiring sanction in addition to the grants for the current year are as follow :—

	Rs.
Sub-Jail at Thittagoody	249
Do. at Virdachellum	186
Do. at Porto Novo	210

4. The excess in the case of the Porto Novo Sub-Jail is owing to the work having been suspended for a long time, and portions of the roofing left in an unfinished state have needed repair. There was also some extra work authorized to the hospital shed. The estimates of the Thittagoody and Virdachellum Sub-Jails have been exceeded, partly owing to the Coimbatore plan of latrine having been adopted, and partly to loss of materials from stoppage of the work. The greate loss was sustained at Virdachellum, the fixed station of the range. Mr. Hawksworth's name is mentioned in the statement, but Mr. Norfor, the present District Engineer, was Range Officer in 1869.

No. 427H. Endorsement of the Inspecting Engineer for Civil and Military Buildings, dated Chepauk, 12th December 1873, No. 1,655.

From R. E. NORFOR, Esq., District Engineer, South Arcot, to Colonel E. A. FOORD, R.E., Inspecting Engineer for Civil and Military Buildings, dated Cuddalore, 5th December 1873, No. 177.

WITH reference to your endorsement, No. 1,231, of the 1st October, and G. O., No. 2,367, of the 25th November 1873, I have the honour to submit a statement showing the state of the hospital sheds attached to the several Subsidiary Jails in this district, the expenditure incurred thereon, and the sums still required for their completion.

2. In my letter of the 3rd instant, No. 173, I have already reported that the Magistrate is of opinion that the hospital sheds be completed with a view of their being converted into cook-rooms, and the cook-rooms being used as store-rooms.

I do not, therefore, anticipate any savings on the estimates for the Subsidiary Jails, and I beg to re-submit the comparative statements returned with your endorsement.

3. The statement of hospital sheds does not include those which have been already completed.

FORWARDED to the Chief Engineer, Department Public Works, with reference to his memorandum, No. 362, dated 25th September 1873. The undersigned approves of the completion of the hospital sheds for utilization as cook-rooms, and the cook-rooms being used as store-rooms, as proposed by the Magistrate.

3 Comparative Statements.
1 Estimate.
1 Statement.

(Signed) E. A. FOORD, Colonel, R.E.,
Inspecting Engr. for Civil and Military Buildings.

No. 427I. ORDER THEREON, 27th December 1873, No. 3,079D.

CIVIL WORKS, No. 31.

HIS Excellency the Governor in Council sees no reason why an additional outlay of Rupees 454-8-6 and Rupees 408, respectively, should be incurred on completion of the imperfect hospital sheds at Thittagoody and Virdachellum in order that they may eventually be utilized as cook-rooms and the cook-rooms originally provided be converted into store-rooms, the necessity for which has not hitherto been recognized as regards Sub-Magistrates' Cutcherries and Subsidiary Jails in general, or proved as regards those at Thittagoody and Virdachellum in particular.

2. The sanction for completion of these buildings will accordingly stand at—

	Rs.
Thittagoody	1,240
Virdachellum	878
Porto Novo	910

the balance of allotments, viz., Rupees 217, being credited to the Reserve. The District Engineer will take steps to ensure these buildings being completed within the current official year without fail, the materials of the unfinished hospital sheds being utilized and corresponding savings made as far as possible.

(True Extract.)

(Signed) G. W. WALKER, Colonel, R.E.,
Secretary to Government.

To the District Engineer, South Arcot.
" Judicial Department.
" Officiating Controller of Public Works Account's.

Exd. S. T. Austin.
Spare Copies

Office of the Inspecting Engineer for Civil & Military Buildings
No 1135
Chepauk 18 September 1873.

From,
Colonel E. A. Foord, R.E.
Inspecting Engineer for Civil & Military Buildings

To,
Colonel G. W. Walker R.E.
Secretary to Government P.W.D.

Sir,

Enclosures 4
3 Comparative Statements
1 Estimate

I have the honor to submit for the sanction of Government three revised estimates in the form of comparative statements for completing the undermentioned Subsidiary Jails in the District of South Arcot.

i Sub Jail at Tittagudy
ii " " Virdachellum
iii " " Porto Novo

2 In my No. 1999, dated 12th August 1873, in sum of Rs. 1745 is granted for the 1st and Rs. 1100 for the 2nd work; and Rs. 700 allotted in the current year's Budget for the Sub jail at Porto Novo.

3.

Civil & Mily. Buildings

Novo and Construction of
Out Offices to the Same

fixed station of the range. Mr Hawksworth's name is mentioned in the statement, but Mr Norfor the present District Engineer was Range Officer in 1869.

I have the honor to be
Sir
Your Most Obedient Servant
E A Ford Colonel R.E.
Inspecting Engineer for
Civil & Military Buildings

3. The revised estimate exceeds the original estimates by Rs 536, Rs 814 and Rs 202 respectively. The balance remains quiring execution in addition to the grants for the current years are as follows.

Sub Jail at Shittagunde Rs 249.

—D:— Vidarshallum —:— 186

—D:— Porto Novo —:— 210

4. The cases in the case of the Porto Novo Sub Jail is owing to the work having been suspended for a long time, and portions of the roofing left in an unfinished state have needed repair since was also some extra work authorized to the hospital shed. The estimates of the Shittagunde and Vidarshallum Sub Jails have been exceeded, chiefly owing to the Commissariat plan of latrines & cesspools adopted, and liability to loss of materials from stoppage of the work in the greatest loss was sustained at Vidarshallum, this

Pub. W. 1873 Depart.
Prdw. No. 5556.

The Inspecting Engineer
for Buildings
To
The Secretary
Govt. P.W.D.

No. 1135
Dated 18
Recd 19
20 } Sept. 1873

Encl: 1.

Submits for sanction
three estimates in the
form of comparative
statements for com-
pleting the Subsidiary
Jails at Chittagudi,
Verdachellum &
Porto Novo in the
South Arcot Distt.

No. 1427
Cir 20 Sept. 73 R. Govt. 174.
Sanctioned Order 22 Sept. 73

No. 3079 D. 27 Oct. 73

Encl + Mdy: Sundries

South Arcot District

Encls: in a letter No 1135
dated 18 Septbr 73

G.O no: 3079 d. 27-12-73

675
P.W 5166/73.

Comparative Statement
showing the work done and
that remains yet to be done
for alterations and addi-
tions to the Sub Magis-
trate's Cutcherry at Porto

South Arcot District

Extract from a Statement shewing the present state of Hospital Sheds attached to Subsidiary Jails in the South Arcot District, the amounts expended thereon and those still required for their completion.

Names of places where the Hospitals are built	Original Estimate	Approved Estimate	Amount expended up to 31st March 1873	Amount required to complete current year	Total Estimate	Amount required for completion	Remarks.
Porto Novo	600	715	535	107 1/2	642 1/2	72 15	Completed except thoney comb work at a cost of 50 Rupees and some other trifling items.
Cuddalore	180	194 6	179 6		179 6	15	
Tatnee	320	399	279		279	81	
Chittagoody	600	700 11 6	245 7 6		245 7 6	~~434 8 6~~	This is the cost of materials deteriorated and on hand, work not commenced.
Cuddalore	180	222 13 6	92 3 9		92 3 9	130 9 9	
Tatnee	320	585 4 3	145 4 3		145 4 3	440	
Virdachellum	600	1007 11 10	599 11 10		599 11 10	408	To be roofed in Honey comb work and asphalting to be done - part of materials ready.
Cuddalore	180	180	180				
Tatnee	320	689 - 9	249 - 9		249 - 9	369 - 0	

Dist. Engineer's Office S. Arcot
Cuddalore 5 December 1873

[Signed] R. E. Norton
District Engineer.

[True extract]
E. W. Nicholl Lieut. R.E.
Asst. Engineer in charge Buildings

1145 -
1100
700
321,5
30 2 0
2 1 3

1209-15-0 Tindivanam
870-0-0 Villupuram
90-0-0 Porto Novo
3:24:0

Sheriff's Office—South Side Dist.
County of Washington

Sheriff's Office, Salem, Or. Oct. 31st 1873.

Hon. Wm. Lair Adams,
Circuit Judge, Presiding.

Dear Sir:

I have the honor to transmit herewith, Statement of Prisoners confined in the County Jail of Washington County, Oregon, for the month of October 1873, and the amount of Jail fees due each.

Respectfully,
Your obedient servant,
[illegible]
Sheriff.

Statement of Prisoners confined in the County Jail of Washington County, Oregon, for the month of October 1873.

2 3/30	Wm. Pfaff	Burglary	Oct. 1st		2	Days	$1	00	$2 30
	Sentenced to confinement in the Penitentiary for the term of two years and to pay a fine of one hundred dollars and costs of prosecution.								
2 4/5	Wm. Pfaff	Larceny	Oct. 3rd		6	"	Agt		12 45
	Sentenced to confinement in the County Jail for the term of sixty days and to pay a fine of one hundred dollars and costs of prosecution.								
1 10/30	Wm. Pfaff	Larceny	Oct. 3rd		20	"	do	40	40 00
	Sentenced to confinement in the County Jail for the term of thirty days and to pay a fine of one hundred dollars and costs of prosecution.								
12 4/8	Wm. Pfaff	Larceny	Oct. 3rd		10	"	do	80	16 80
	Sentenced to confinement in the County Jail for the term of ninety days and to pay a fine of one hundred dollars and costs of prosecution.								
3	Wm. Pfaff	Larceny	Oct. 3rd		2	"	do	80	5 60
	Sentenced to confinement in the County Jail for the term of thirty days and to pay a fine of one hundred dollars and costs of prosecution.								
19 3/5	Wm. Pfaff	Larceny	Oct. 3rd		4	"	do	80	30 40
	Sentenced to confinement in the County Jail for the term of ninety days and to pay a fine of one hundred dollars and costs of prosecution.								
12	Wm. Pfaff	Larceny	Oct. 3rd		6	"	do	1	6 00
	Sentenced to confinement in the County Jail for the term of ninety days and to pay a fine of one hundred dollars and costs of prosecution.								
4 12/30	Wm. Pfaff	Larceny	Oct. 3rd		15	"	Agt	70	32 77 50
	Sentenced to confinement in the County Jail for the term of fifteen days and to pay a fine of one hundred dollars and costs of prosecution.								
	Total								18 51 420 00
	Sentenced to confinement in the County Jail for the term of [illegible] days and to pay a fine of [illegible] dollars and costs of prosecution.								20 00

Total amount of fees allowed by Court for boarding prisoners confined in the County Jail for the month of October 1873 $438 51

State of Oregon, County of Washington, ss.

I, Wm. Pfaff, Sheriff of Washington County, Oregon, do solemnly swear that the foregoing account is correct and just, and that the prisoners therein named were confined in the County Jail of said County for the time therein stated, and that the charges therein made are reasonable and just.

Wm. Pfaff
Sheriff.

Subscribed and sworn to before me this 31st day of October 1873.

Jno. Hall
County Clerk.

—South Side District—

[illegible]

[illegible]

[illegible]

Taken from a statement showing the present state of Hospital Fees allowed to Circuit Judges in the South Side District the amount suspended, & those still required for their completion.

C. 20 Jan 173 Dec 9 Jan 174

North Arcot District

Enclos: in my letter No 1135
dated 18 Septr 73
G.O. Cons: 2979 & 2712-73
6/5/73
P.W. 516 6/73.

Abstract Estimate for
Constructing Jail & Lat-
rines for the Subsidiary
Jails at Cuddalore,
Tindavanellum and
Chittagooty.

Amount of Estimate Rs 2,[illegible]

No III Range. South Arcot District. Viridachellam Taluq.

Comparative Statement showing the work done and that remains yet to be done for Alterations and additions to the Subsidiary Jail at Viridachellam and Construction of Out Offices to the Same.

Description of work.	Quantities	Original Estimate to June 1869. Rates	Amounts	Work done up to June 1869. Quantities	Rates	Amounts	Work remains yet to be done Quantities	Rates	Amounts	Amount of deterioration during the last 4 years. Quantities	Rates	Amounts	Revised Estimate or Total of Columns of 3, 4 & 5. Quantities	Rates	Amounts	Increase Quantities	Amounts	Decrease Quantities	Amounts	Excess over the Original Estimate.	Remarks.
1		2		3			4			5			6			7		8		9	10
Alterations to the Subsidiary Jail																					
Brick in Chunam including plastering	Cft	7143/4	" 2	92 156	518¾	" 2	64 136	225	" 2	482						92 156					
Terracing with joints 3 Courses of flat tiles &c	Sqre	1 3/16	22	28 97				1 3/16	22	28 97						28 97					
Pucka work of 1½ brick work	Cft	459	" 6	14 56	218	" 6	6 13	241	" 6	286						14 56					
Iron doors with frames &c (3×6¾) Complete	No	4	65	260																	
do gratings do (5×2)	do	2	128	25																	
do do do (3×1½)	do	7	10	70																	
Weather Boards large	do	2	15	30			385			150						535					
do small	do	8	10	80																	
Sky lights with frames & glass	do	2	35	70																	
Terracing with asphalte 1" thick	Sqre	7½	20	145				7½	20	145						145					
Excavating foundation Scaffolding & Sundries				34 15			34 15			14						48 15		14			
Clearing deepening and repairing the well				50			53 153									53 153		3 153			
				900			544 112			373 41						917 153		17 153			
Additions Building																					
Brick in Chunam including plastering	Cft	2520	" 2	315	2520	" 2	315									315					
Flooring with Brick jelly in Chunam 3" thick	Sqre	3/10	3	949	3/10	3	949									949					
Paving with asphalte 1" thick	Sqre	2¼	20	45				2¼	20	45						45					
Terracing with joists 3 courses of flat tiles	do	1	22	22	1	22	22									22					
Roofing with Palmyrah rafters, reepers, flat and pan tiles &c	Sqre	57/8	20	1178	57/8	21	1178									1178					
Teak wood wrought and put up	Cft	21 15/16	4	87 12	21 15/16	4	87 12									87 12					
Iron door with frames Complete (3½×6)	No	2	65	130			131									130					
Ventilators do do (5×2)	do	4	12 8	51			50									50					
Weather Boards	do	4	15	60			60									60					
Rain pipes	do	4	2	8			8									8					
Excavating foundation				20			20									20					
Scaffolding and Sundries				45 73			45 73			19 111						65 32		19 111			
				910			865			644 111						929 111		19 111			
Hospital shed				600			599 110			78			330	01		1037 110		407 110*			
Cook House				181			180			440						180					
Latrine				320			249 9			518			330			689 9		369 9*			
				1100			812 7			856			330	0		1876 127		776 127			
Total				2910			2438 79									3724 79		814 79			
Deduct the Amount of Expenditure up to July 1869																2438 79					
Amount required for Completing the work to																1286					

* Sanctioned in G.O. No 1354 of the 26 April 1869.

** The Roofs of the Hospital shed and Jail Latrine have fallen down & the old materials sold in auction. Therefore the Cost of Re-roofing & repairing the Hospital Shed and of a new Latrine is included in the Revised Estimate hence the excess.

× This includes the sums of Rs 40—— for Honey Comb Work in the Hospital shed. Vide G.O. No 18 of 3 Feb: 1873.

×× This provides for Constructing the Latrines of Coimbatore pattern.

District Engineer's Office S. Arcot. Cuddalore 5 July 1873.

Edward Colonel, R.E. Inspecting Engineer for Civil & Mily. Buildings.

Offg: District Engineer.

South Arcot District.

Enclo: in a letter Rc 1135
dated 18 Septr 73

G.O. 2079 R - 27-12-73

675
P. W. 1156/73.

Comparative statement
Showing the work done and that
remain yet to be done for Altera-
tions and additions to the Civil
Living jail at Verdachellum
and Construction of Out Offices
to the same.

Vide Chellam Salup.

Southern Arcot District

No. III Range.

Comparative Statement showing the work done and that remaining yet to be done for alterations and additions to the Sub Magistrate's Cutcherry at Thittagoody and Construction of out offices to the same.

Description of work.		Original Estimate			Work done up to July 1869.			Work remaining to be done			Amount of deterioration during the last 4 years	Revised Estimate for the remainder of Columns 3, 4 & 5			Increase			Decrease			Excess over the original Estimate.	Remarks.
		Quantities	Rates	Amount	Quantities	Rates	Amount	Quantities	Rates	Amount	Amount	Quantities	Rates	Amount	Quantities	Rates	Amount	Quantities	Rates	Amount		
1			2			3			4				5			6		7			8	9	10
Brick in Chunam including plastering	Cft.	3135	2	3914	2023 7/16	2	2523	1111 19/24	2	1388			676			4594		676				
Flooring with brick jelly in Chunam 3" thick	Sq.ft.	44 13/16	3	147				4 13/16	3	147						147						
Paving with asphalte 1" thick	do	6½	20	130				6½	20	130						130						
Roofing with palmyrah rafters, reepers, flat & pantiles ½ Complete	Sq.ft.	123/4	20	255	7 43/128	20	148	5 53/128	21	106			39			294		39				
Teakwood wrought and put up	Cft.	3 7/9	4	15	8 10	2	4	1 8/9	4	7	8					15 8	10					
Iron doors with frames 3'x6' Complete	No.	4	65	240			240									240						
Ventilators 5'x2'	do	2	15	30			30									30						
Batten doors 3'x6' Complete	do	2	20	40						40						40						
Ventilators 3'x1½'	do	2	10	20						20						20						
Pain pipes	do	3	2	6				3	2							6						
Weathers Boards Large	do	2	15	30	2	15	30									30						
do Small	do	8	10	80				8	10	80						80						
Excavating foundation				10						10						10						
Scaffolding and Sundries				6722			18			70 10						88 10		2148				
				1330			727 2/11			624 19			106 6			1457 11		1271 8				
Deduct the value of 2 Batten doors	40									70												
do Ventilators	21			70						554 19						70						
do Old roof	10			1260			727 2/11			x 3948 6			1066			1387 10		1271 8				
Hospital Shed				600			245 7/6			1071 23			601 16			700 16		100 16				
Coote house				180			92 39			19* 119			221 36			222 136		42 136				
Jail Latrine				320			145 43			8			35 149			375 49		55 149				
Well of 4½ ft diameter				80			72									80						
Total				2440			1282 25			1259 23			2251 39			2767 25		327 25				327 25

Sanctioned G.O. No. 1354 of the 26 April 1869.

Deduct the amount of Expenditure up to July 1869 1282 25

Amount required for completing the work 1485

District Engineer's Office S. Arcot.
Cuddalore 5 July 1873

Lt. Colonel R.E.
Inspecting Engineer for Civil & Mily. Buildings

1694-8-6
454-8-6
1239-13-0

District Engineer S. Arcot.

* This includes a sum of 1240 for Honey Comb work in the Hospital shed. Vide No. 13 of 3rd February

* This provides for carriage of tiles & pattern.

District Engineer's Office,
South Arcot.

No 1172.

Cuddalore 5th December 1873.

From

The District Engineer
South Arcot.

To

The Superintending Engineer
for Civil & Military Buildings
for Circle.

Sir,

With reference to your endorsement
No 1231, of the 12th October, on D.O. No 2367,
of the 25th September 1873, I have the honor
to submit the statement showing the
works attached
to the State of the Hospitals which fell in this
division during the current
year, the amount of the expenditure incurred
by the Public Works Department, and the
amount still required
to complete the same.

For this complete statement of the 3 Hospitals,
In my letter of the 3rd instant,
I have already requested that
No 1173, I have also applied for
the Magistrate's office to be completed,
the Hospital sheds being pronounced
unfit for use after the Cool Season
with a view of their being removed into Cool rooms, and the Cool rooms being

South Arcot District.

Encl: in a letter No. 1135
dated 18 Septr/73

G.O No: 3079 b-27-12-73

6/5
3
P.W 5766/73.

Comparative Statement
showing the work done and
that remains yet to be
done for alterations and
additions to the Sub Ma-
gistrate's Cutcherry at
godly and construction of
Offices to the same.

being used as store rooms. I do not therefore anticipate any savings on the estimates for the Subsidiary Jails, and I beg to resubmit the Comparative Statements returned with your endorsement.

3. The statement of Hospital Sheds does not include those which have been already completed.

I have &c.

(Signed) R.E. Norfor
District Engineer.

No 1655

Forwarded to the Chief Engineer D.P.W. with reference to his Memo No 362, dated 25th September 1873. The undersigned approves of the completion of the Hospital Sheds for utilization as Cook rooms, and the Cook rooms being used as stores rooms as proposed by the Magistrate.

Enclosures 5
3 Comparative Statements
1 Estimate
1 Statement

Offices of the Inspg Engrs for Civil & Military Buildings
Chepauk 12 Decr 1873

E A Dod Capt R.E.
Inspecting Engineer for Civil & Military Buildings

To
Colonel G.W. Walker R.E.
Chief Engineer D.P.W.

P.W.D. Works 1873 Despatch
Opn. of Govt for Decr
No 6757
From
The Supdg Engineer
for Civil & Mily Buildgs
To,
The Chief Engineer
P.W. Deptt
No 1655
Dated 12
Recd 13 } Decr 1873
Recd 15
Cuddr: 5
No 3079 D - 27th Decr 1873
Forwards copy of the Supdg Engrs
letter from the Dist Engrs
Ss Acot submitting a
Statt shewing the State
of the Hospital Sheds
attached to the Sub
Jails in the Distt of
Ss Acot & States that
the approval of the completion
of the Hospital Sheds for
utilization as cook rooms
Does as proposed by the Magistrate.

No 4274

No 3079 of S.P.D.

Pro: of the Madras Govt.

Read the following

From,

The Supdg Engr for Bgs: (N. E. Do 1135 of 18th Septr 73)

Do Do - (" " " 1655 " 12th Decr 73)

No 3278

His Excellency the
Governor in Council sees
no reason why an addi-
tional outlay of Rs 454-8-0
and Rs 408 respectively
should be incurred on
completion of the imperfect
Hospital sheds at Thittagoody
and Virdachellum in order
that they may eventually
be utilized as Cook Rooms
and the Cook Rooms origin-
ally provided be converted
into

into Store Rooms, the neces-
sity for which has not
hitherto been recognized
as regards Sub Magistrates'
Cutcherries and subsidiary
Jails in general, or pressed
as regards those at Thitta-
goody and Virdachellum
in particular.

The sanction for com-
pletion of these buildings
will accordingly stand at
Thittagoody Rs. 1240. ✓
Virdachellum — " — 878.
Portonovo — " — 910.
The balance of allotments
viz: Rs. 217 being credited
to the Revenue. The District
Engineer will take steps
to ensure these buildings
being completed within
the

the current official year
without Jail; The mate-
rials of the muni-
cipal Hospital
Sheds being uti-
lized and co-
operation in
using needle as
far as possible
Lyttle

38

D.C. South Arcot — by S. despatch to Chgt 27/12/75.
Judl. Dept. Ref. — D.C despatch 17/1/76.
Controller Ref.

No 5156 & 6757

Govt. of 1874 Madras.

PUBLIC WORKS.

To The District Engr
South Arcot

Dated

Recd. Encl. 5

G. O. 27 Dec 1873. No 3079

Nos. 4274-4274.

Sub Jails in the South Arcot Dist.

Passing orders on letters from the Inspecting for Buildings submitting Estimates for Completing certain Jails, disapproving of the proposal of the completion of Hospital Sheds attached to the Jails for use as work rooms.