

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public works

DEPARTMENT

G.O. No.	690	Press
B.P. No.		Mis.
42-43		
Dated	4-3	18-13

Not to be folded or roughly handled

*Proceedings of the Madras Government; Public Works Department,
4th March 1873.*

No. 72. Read the following letter from the District Engineer, Bangalore, to the Chief Engineer, Public Works Department, dated Bangalore, 15th February 1873, No. 956 :—

I HAVE the honour to forward for sanction an estimate of Rupees 155, with specification, for constructing urinals in rear of the Cavalry Stables, Race-course.

2. The work has been called for by the Military authorities, and approved of by the Major-General Commanding the Division, in order to prevent the men committing nuisance against the side walls of the stables, and in rear of the forage compound for want of urinals close to the stables.

No. 73. ORDER THEREON, 4th March 1873, No. 690.

MILITARY WORKS, No. 4.

SANCTIONED.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the District Engineer, Presidency.
,, Controller of Public Works Accounts.
,, Military Department.

Exd. T. O'Connor.

3
X

Abstract Estimate for constructing
 Drains in rear of the Cavalry Stables on the Race Course
 prepared agreeably to the requisitions received from the
 Assistant Quarter Master General Mysore Division etc.
 23 of 17th January 1873.

Measurements	Particulars	Rate Per amount	Total
2 0 0 2	2 cts of Drains corrug. rated down	70 " " 6	140 " "
2 6 ² . 7854 . 5654	Sqrs of stone pavement 6' thick	15 " " 8 6 4	148 6 4

Sundries 6 98

Total Estimate Rupees 155

Dist^l Engrs Office
 Bangalore
 3rd February 1873.

Henry M. M. M.
 Captain R.E.
 District Engineer.
 Bangalore

Proven
M. M. M. M.
Order

P. No. 1065/73.
M. L. - 1065/73 B. 8-72.


Specification for foregoing Estimate
Amount of Estimate Rs. 155-00

Sides to Drains

will be corrugated iron which will stand on a base of flat stone 6" ^{thick} in these stones will be inserted bat holes with clamps fixing the bottom of iron sheeting, all joints will be thoroughly riveted with 2" overlap.

Roof

The roof will be conical 2 1/2 riv. eaves projecting 6" over sides, roof will be attached to sides with strong iron clamps. Height of Sides to be 6 1/4 feet.



Entrance will be as per margin.
All materials and workmanship to be of the best description obtainable subject to the inspection of District Engineer who may pass or reject the whole or any part thereof.

District Engineer's Office
Bangalore
3rd February 1873.

Henry M. B. }
Captain R. E.
District Engineer
Bangalore

District Engineers office
Bangalore 15 February 1893.

No 956

From

The District Engineer
Bangalore.

To

The Chief Engineer
Public Works Department
Madras.

Sir,

I have the honor to forward for
sanction an Estimate of Papers 155 with
Specification for constructing animals in
rear of the Cavalry Stables Race Course.

The work has been called for
by the Military authorities and approved
of by the Major General Commanding the
Division, in order to prevent the nuisance
caused by animals against the side walls
of the Stables and in rear of the Forage
Compound for want of animals close to the
Stables.

I have the honor to be
Sir

Your most obedient servant

Henry Stuart
Capt. R.
District Engineer Bangalore

From

The District Engineer
Bangalore

To the Chief Engineer
P.W.D.

Re Estimate
No 155 of 15th Feb 1893

Estimate for
constructing animals
in rear of the Cavalry
Stables on the P.W.
Compd.

Amounting to
Rs 155/-

P. No 1065/93.
P.W.D. No 1363/892

P. M. 1873 Michael

of son

No 1065

The South American

& Foreign

The Chief Engineer

J. W. Mackay

Dated 15th July 1873

Received 17th do

Sum 2.

For according to

directions an estimate

of 13155 with built


specification for

Constructing Mural

in rear of Camp Wall

to be done

with an order



Sanctioned
No 690
M. F. M.

Bangalore

J. R. Singh
on 12/10/73
order 9/3/73

11/12/73

19-11-1873

No 1065

Gobt. of 1873 Madras.

PUBLIC WORKS.

To *The District Engineer*
Quendruy

Dated

Recd.

Encl. 2

G. O. 4th March 1873, 690th

Nos. 72473.

Urinals. Res. for con-

structing Urinals in
rear of ~~the~~ Cavalry
Stables on the Race
Course at Bangalore,
Sanctioned.