

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No.	1551	Press
B.P. No.		Mis.
Dated	12. 6.	195 1874

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
12th June 1874.*

No. 222. Read the following letter from Colonel E. A. FOORD, R.E., Inspecting Engineer for Civil and Military Buildings, to Colonel G.W. WALKER, R.E., Secretary to Government, Public Works Department, dated Coonoor, 14th May 1874; No. 668:—

2 Plans.
2 Estimates.
2 Specifications.

I HAVE the honour to forward, for the sanction of Government, the under-mentioned estimates for completing the office accommodation required by the District Engineer, Neilgherries:—

Constructing a verandah in front of the Engineer's Office at Wellington. 225
Do. a Store-room and office at the 2nd milestone on the Coonoor
old ghaut for the use of the Local Fund Overseer 1,020

2. The Cantonment Overseer has a convenient office and Store-room, but a verandah is required in front of the office in the place of the present dilapidated thatched verandah. The Local Fund Overseer has no office. His stores, which consist of tools, blasting powder, fuze, etc., are at present kept in a thatched hut on the Coonoor ghaut. The estimate now forwarded is for a small office and Store-room which have been designed to fit a suitable site on the Coonoor ghaut.

3. No other offices or stores are required.

No. 223. ORDER THEREON, 12th June 1874, No. 1,551.

CIVIL WORKS, No. 17.

THE substitution of a permanent verandah for the present unsightly chuppar in front of the Engineer's office

at Wellington at a cost of Rupees 225 is sanctioned, and funds provided from the Provincial Reserve.

2. The District Engineer will submit his proposal to provide the Local Fund Maistry with an office and Store-room to the Local Fund Board.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the District Engineer, Neilgherries.
,, Officiating Controller of Public Works Accounts.
,, Financial Department.

Exd. T. O'Connor.
Spare Copies

2.

Love,

7-1

sure

— J. K.

est

est

Abstract Estimate No 25 of 1873/74

Nilgerry District
Work Constructing a Verandah to Front of
Engineers office at Wellington

Quantities	Particulars of Work	Rate	Amount	Total
106	cubic ft. Brick in Chumam	40	42 6 5	
117	Square ft. Flooring with 1 ft. Sp. Bricks	25	29 4	
19	cubic ft. Teakwood wrought & put up	24	46	
10	8 ft. Sheets corrugated, iron	5	50	
4	18" Iron Bolts & Nuts	8	2	
8	8" do do	4	2	
20	6" do do	3	3 12 5	203 6 5
	Supdt. & Sundries		19 9 7	
	Total Estimate Rupees		225	

For Amount Capt. R.L.

District Engineer

EA Mord. at N. C.
Respecting Engineer

Potacamund
Distt Engrs Office
4th August 1873

Nilgerry District
District Engineer

106 cubic ft. Brick in Chumam

117 Square ft. Flooring with 1 ft. Sp. Bricks

19 cubic ft. Teakwood wrought & put up

10 8 ft. Sheets corrugated, iron

4 18" Iron Bolts & Nuts

8 8" do do

20 6" do do

Supdt. & Sundries

Total Estimate Rupees 225

Specification

Amount of Estimate Rs. One thousand and Twenty

Foundation—To be excavated $2\frac{1}{4}$ ft. wide & 2 ft. deep and filled in with rubble stone in Chumau

Basement—To be of Brick in mortar $1\frac{1}{4}$ ft. wide and $\frac{3}{4}$ ft. high

Superstructure—To be of Brick in clay $1\frac{1}{4}$ ft. wide, except enough below roof and around Doors & Windows to be of Brick in Mortar, pointed with Chumau internally and, optionally—Walls to be 8 ft. to Wall plate or top of tie beam

Flooring—To be of good binding clay well watered and panned

Roof—To be of anti-peepers nailed to Rafters, bamboo mats and Pann Jalis & Chumau borders

Woodwork—To be of Neugi—Tie beams to have a scantling of $6\frac{1}{2} \times 3\frac{1}{2}$ —Principals $4\frac{1}{2} \times 3\frac{1}{2}$ —Rising Posts $4\frac{1}{2} \times 6$ —Pillars $4 \times 3\frac{1}{2}$ —Purlins $5 \times 3\frac{1}{2}$ —Ridge Pole $6 \times 2\frac{1}{2}$ —Rafters $4 \times 2\frac{1}{2}$ —The store to be fitted with 3 shelves $12 \times 1\frac{1}{4}$ and Office with 1 shelf $5 \times 1\frac{1}{4}$ —Door frames to have a scantling of $1\frac{1}{2} \times 3\frac{1}{2}$ —Window 4×3 with Cross rail & Bars, the latter $1\frac{1}{2} \times 1\frac{1}{2}$ —Doors & Window shutters to be $1\frac{1}{2}$ thick and to be supplied with Hinges, bolts & Padlocks to former

District Engineers Office
Milgherries
Cotacumund 4th August 1873.
Mr Pope.

Geo Horant.
Capt R.E.
District Engineer.

Exchange with City
 No. 46. Standard No.
 1574
 Robert Detmold
 Sheep River
 No. 25 ip 1873/74.
 Constructing a road
 to front of the business
 Office at Wellington.
 No. 37 12 th June/74
 No. 18 18 th June/74
 No. 22 5 th June/74
No. 32 20 th June/74
 2

Abstract Estimate No 24 of 1873/74

Nilgerry District

Work - Constructing a Store Room and Office at the 2nd Mile
Stone in the Coonoor Rd. Grant for the use of Local Fund Range

Particulars of Works. Rate. Amount Total.

488 1/4	Cubic ft. Rough Stone in Chunnam	12 ..	58 95
433 3/4	do Bricks in Mortar	10 ..	173 8
705	do Bricks in Clay	20 ..	141 ..
1967	Square ft. Pointing with Chunnam	6 ..	118 11
1967	do White & Col. Washing	" 4 ..	148
396	do Plastering	18 ..	515
858	do Roofing with split reeds, reeds, Nails, bamboo mats, Pan Diles & Chunnam borders	20 ..	171 97
114	Cubic ft. Neuge Wood for rafters & posts	28 ..	285 ..
18	Cubic yds Earth work	" 4 ..	48
11	Lbs of Iron	" 1 ..	2 ..
2	Padlocks	" 8 ..	4 ..
8	6" Bolts	" 12 ..	3 ..
4	9" do		975 9

Supdt. & Sundries 447

Total Estimate Rs. 1020 ..

District Engineer's Office
Nilgerry
Coonoor 4th August 1873
M. R. P.

per order
District Engineer
Capt. R. E.

El. and Cal. N. E.
Superintending Engineer for
Civil & Military Buildings

Nilgerry District
Work done in a
No. 1195 at 11
No. 1074
No. 1228
No. 1512
No. 3200/74
5-1/74
Estimate No 1020
Work done in a
No. 1195 at 11
No. 1074
No. 1228
No. 1512
No. 3200/74
5-1/74
Estimate No 1020

No. 118

OFFICE OF THE INSPECTING ENGINEER
FOR CIVIL AND MILITARY BUILDINGS,
Cantonment May 1874

From

THE INSPECTING ENGINEER
FOR CIVIL AND MILITARY BUILDINGS,

To

The Secretary to Government
Public Works Department.

SIR,

Enclosures 6.
2 Plans.
2 Estimates
2 Specifications

I have the honor to forward
for the sanction of Government the
undimentioned estimates for
completing the office accommodation
required by the District Engineer
Neilgherry.

Constructing a verandah in front of
the Engineer's Office at Wellington Rs. 225
Constructing a store room and office
at the 2nd mile stone on the Coonoor
old ghaut for the use of the Local
Fund Overseer Rs. 1020.

The Cantonment Overseer
has a convenient office and store
room, but a verandah is required
in front of the office in the place
of the present dilapidated thatched
verandah. The Local Fund
Overseer has no office. His stores,
which consist of tools, blasting
powder, &c. are at present
kept

Wellington District

Indicative in a letter
of 6th instant May
1874.

Abstract Estimate
of Specifications.
No. 2471873/24

Constructing a stone
Barrack Office at the
2nd mile stone on the
Coonoor old Ghaut
for the use of Local
Fund Range Machinery.
Rs. 272 Rs. 1020/24
No. 1020/24

Mrs. 3200/24
6-1794

Kept in a thatched hut on the
Coonoo ghant. The estimate now
forwarded is for a small office
and store room which have been
designed to fit a suitable site on
the Coonoo ghant.

No other offices or stores
are required.

I have the honor to be,

Sir,

Your most Obed. Servt.

E A and Colonel A. B.,
Inspecting Engineer for
Civil & milly. Buildings

P. W. 1874-Refutation
Principal of the same

No. 168.

543200

From

The Inspecting Engineer
for Buildings.

To

The Secretary to Govt.
2nd Dept.

Cell. No: 1551. 126-74

Dated

11/7

May 1874

Recd. 29/5

Forwarded for
Sanction & estimate
for completing
the office accommoda-
-tion required
by the District
Engineer. Nedgherries.

Ok 22/5

P. W. D. *Amal*
Rs. of the Madras Government
Read the following

From the P. E. for Buildings (H. E. No 668 of 14 May 74)

The substitution of a
permanent Verandah for
the present unsightly Chuppar
in front of the Engineer's
Office at Wellington at a
cost of Rs. 225 is sanctioned
and funds provided from the
Provincial Reserve.

The District Engineer
will submit his proposal
to provide the Local Fund
maintaining with an Office and
Dining Room to the Local Fund
Board. L. W. W.

23/5

To D. E. Fitzpatrick
" Controller
" Financial Officer
S. Copies despatched 19/6/74.

P. W. D.

Proceedings of the Madras Government,

Under date the

187

Read the following:—

*From the Insp. Engineer } (N.E. No. 668 of 14 May 1874)
for Buildings*

*I don't see the need for a
verandah at all - at
least it is not explained*

*His Excellency the
Governor in Council sanc-
tions the undermentioned
estimates submitted with
this letter.*

*With a Store Office for 27.
Overseer he permanently need -
on the old Plant - 2 - 1000
why spend Rs. 1000?
21/5/74 M.B.*

*For constg. a verandah to the } Rs.
Engineer's Office at Wellington } 225
do - a Store room and Office }
on the Coimoor old plant } 1020*

*The question of funds
will be taken into considera-
tion when the demands from
the Reserve come under re-
view - Amn*

*Sd/- S. L. Seligman's
S. L. for Buildings
Cmbr. of P. W. D.*

222-223.

22/5/74

23/5/74

3200



Govt. of 1874 Madras.
PUBLIC WORKS.

To
The De-Super
Highways

Dated

Recd.

Encl. 6.

G. O. N. June 1551

No. 222-223.

Engineer's Office at Willingdon

The substitution of a permanent
Verandah for the present im-
sufficiently Chopper in front of
the office at a cost of Rs
225, sanctioned -

Proposals to provide the
Local Fund Mainly with
an Office & Store room to be
submitted to the Local Fund
Board -