

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No.	2688	Press
B.P. No.		Mis. _____
Dated	21-9-	24 195

Not to be folded or roughly handled

19
*Proceedings of the Madras Government, Public Works Department,
21st September 1874.*

No. 466. Read the following letter from Major J. N. HUNTER, R.E., District Engineer, Salem, to Colonel G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Yercaud, 4th September 1874, No. 108:—

WITH reference to paragraph 3 of the Proceedings of Government, under date 16th December 1873, No. 3,025, I
1 Estimate. have the honor to forward, for sanction and for an assignment of funds, an estimate of Rupees 120 for building honey-comb work between the posts of the verandah in front of the Subsidiary Jail at Ahtoor.

No. 467. ORDER THEREON, 21st September 1874, No. 2,688.

CIVIL WORKS, No. 35.

SANCTIONED and funds made available by transfer from the grant at the District Engineer's disposal under "Repairs, Civil Buildings, Provincial."

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the District Engineer, Salem.
,, Officiating Controller of Public Works Accounts.
,, Judicial Department.

Exd. T. O'Connor.
Spare Copies

Detail Estimate No. 8 of 1874-75
 Particulars of Work. ^{Measurement in feet} ^{Quantity} ^{Unit}

Honey Comb or open Brick Work.

Covered with 2 Coats of Plaster.

Between the openings of posts
 in Verandah of the first two

Male ward. $4 \times 8 \frac{1}{2}$ 9 300

Between the openings of a
 portion of 3rd Male ward and in

front of the two female wards $4 \times 8 \frac{1}{2}$ 9 300

Total Sq. feet of Honey Comb work. 600

or Squared. 600

Specification.

Specification report to accompany the
 Estimate of Rs. 120. for building honey &
 Comb brick work between the posts of the
 Verandah in front of the Subordinate Jail
 at Alwar.

2. Authority. H. A. No. 3025 dated 16th
 December 1873.

3. The westerly rain and sun beating
 into the wards of the Sub. Jail, causes great
 inconvenience, and necessitates the submission
 of this Estimate for providing honey Comb
 brick work, all along the front verandah
 in front of the doors, and between the wooden
 posts.

4. The open brick work shall be 1.3"
 wide and carried up to the height of the brass
 windows. It shall be built with wall brick
 of Government size, sound and well burnt.
 The joints shall be cemented together with
 mortar consisting of one part of fresh and
 newly burnt slake lime slaked on the work
 incorporated with $1 \frac{1}{2}$ parts of clean, coarse
 river sand. The mortar shall be ground
 under a mill.

The bricks shall be plastered with 2.
 Coats of Chiman. The first Coat, consisting
 of one part of lime to $1 \frac{1}{2}$ of
 river sand; and the second Coat consisting
 of three parts of lime to one of finely
 sifted white river sand.

The openings in the brick work shall

have

No. 108. District Engineer's Office,
Yercaud ^{14th} September 1893.

From
The District Engineer
of Salem.

To
The Secretary to Government,
Public Works Department.

Sir,
With reference to paragraph 3
of the Proceedings of Government
under date 16th December 1893, No. 3025,
I have the honour to forward for sanction
and for an assignment of funds an
estimate of Rs. 120 for building
honey-comb work between the posts
of the Verandah in front of the
Subsidiary Jail at Ethan.

I have the honor to be,
Sir,

Your most Obedt. Servant.

J. A. K. K. Major R. E.
District Engineer, Salem

15/5618
 GOVT. OF MICHIGAN
 PUBLIC WORKS.

M. St. Jacques
 Salen

21 Sept 1874
 Nos. 466-467

Stores and Work

Contract of No. 120
 for building stores and
~~the~~ brick work between
 the ports of Tenacosta
 in front of the Submarine
 Jail at Salen in the
 Salen St. Jacques,
 funds provided by
 certain transfer

P. No. 1874 Salen
 No. 5618.

The District Engineer

Salen

The Secretary of the

D. St. Jacques

Date 21 Sept 1874

2688

of understanding for
 construction and for an
 assignment of funds
 estimate of No. 120
 for building stores
 construction between
 the ports of the water
 side in front of the
 Submarine Jail at Salen
 M. St. Jacques

Sanctioned and funds made available
 by transfer from the grant at the District
 Engineer's disposal under No. 120, and No. 121
 M. St. Jacques
 No. 5618
 15/5618
 466-467