

*Proceedings of the Madras Government, Public Works Department,
21st September 1874.*

No. 480. Read the following letter from Colonel E. A. FOORD, R.E., Inspecting Engineer for Civil and Military Buildings, to Colonel G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Chepauk, 8th June 1874, No. 811 :—

With reference to the Order of Government of the 3rd March 1874, No. 29,

1 Plan.
1 Abstract Estimate.

I have the honor to forward a revised plan for a dead-house, with an estimate for the same, amounting to Rupees 565.

2. The plan and estimate which I forwarded to the Surgeon-General, Indian Medical Department, and which were returned to me with his approval, only differed from these in there being no ventilator in the former and the walls being of brick-in-clay. In this estimate the walls are of brick-in-chunam, and in the plan openings under the eaves have been substituted for the wall ventilators.

No. 481. ORDER THEREON, 21st September 1874, No. 2,694.

CIVIL WORKS, No. 37.

His Excellency the Governor in Council is pleased to adopt the plan and estimate submitted with this letter modified so as to allow of the roof being tiled instead of thatched, and desires that the plan be lithographed and adopted as a standard plan.

(True Extract.)

(Signed) G. W. WALKER, Colonel, R.E.,
Secretary to Government.]

To District Engineers.

To the Executive Engineer, Wynaad.

„ Surgeon-General, Indian Medical Department.

„ Judicial Department.

Exd. E. C. Shunker.

Spare Copies

Estimate No. 4.
B.

Revised Estimate for Dead House

Standard Plan, (walls only 12 feet high.)

Walls of Brick in Chunam pointed and Whitewashed.

Roof Thatched, with Eave ventilators

Quantity	Particulars	Rate	Per	Amount	Total
1429	lft of Brick in Chunam	2	5	lft 215 13 5	
61½	" of archwork in Chunam	3	3	" 12 7 1	
15	Sq of Pointing & whitewashing	2	"	Sq 16 14 "	
2.16	" of Asphalt flooring ½" thick	14	13	" 31 15 11	
8.64	" of Roofing with Bamboo rafters Purlins, keepers, including country wood couples with 2 collar pieces &c complete	15	"	Sq 129 9 7	
23	lft of Country wood wall plates Struts and Braces	2	"	lft 46 - "	
8.75	Sq of Tarring 2 coats to wood work	11	6	Sq 6 4 8	
1	Door pannelled & glazed complete	34	4	Each 34 4 "	
3	Windows glazed complete	13	10	" 40 14 "	
2	Sq of wood oil to Doors & windows	12	6	Sq 1 9 "	
25	lft of excavating the foundation and filling the Basement	2	"	lft 3 2 "	
Total				538 13 8	
Sundries at 5 percent				26 2 4	
Total Estimate Rupees					565

Office of Insp. Eng. for C.B.
M. Buildings. Chhapauk
8th June 1874.

Edmd Colonel R.E.
Insp. Eng. for Buildings.

No. 811

OFFICE OF THE INSPECTING ENGINEER
FOR CIVIL AND MILITARY BUILDINGS,
Chepauk, 8th June 1874.

From

**THE INSPECTING ENGINEER
FOR CIVIL AND MILITARY BUILDINGS,**

To

The Secretary to Government
Public Works Department

SIR,

With reference to the Order of
Government of the 3rd March 1874
No. 29, I have the honor to forward
a revised plan for a Dead house with
an Estimate for the same amounting
to Rupees 565.

2 The plan and estimate which I forwarded to the Surgeon General Indian Medical Department, and which were returned to me with his approval only differed from these in there being no ventilator in the former and the walls being of brick in clay. In this estimate the walls are of brick in chunam.

Enclosures-2

1 Plan
1 Abstract
Estimate

Only in a letter
to 811 of 8th June 1874

Mr. 3490/44.

25. 321 Sept 17/4
Lm 13 Oct 1880

Florida Colonies

For a dead horse
will pass unhurt

Adams

Adina 18 1855

main and, and in the plan, openings
under the eaves have been substituted
for the wall ventilators.

I have the honor to be.

Sir

Your most Obedt Servt

E. A. Smith Colonel R. E.

Inspr. Engineer Genl.

Civil & Mily. Buildings

Memorandum.

The accompanying revised Plan and Estimate for a dead house, to serve as a standard for future Construction in the Presidency is forwarded for approval.

2. The plan is the same as that forwarded to Government by the Inspecting Engineer for Buildings with his letter of the 3rd March 1874, except that a tiled has been substituted for a thatched roof in accordance with the order of Govt.

3. The Estimate is framed on the rates usual in the Presidency.

Asst.

P. M. 1874 Sept.
No. 811
No: 3490

From

The Inspecting Engineer
for Buildings,

To

The Secy. to Govt.
P. M. Sept.

Encls: 2

Dated 8 June 1874.
Recd. 9/10

Forwards for approval
a revised plan and
estimate of Rs 565
for a Dead house.

Ob. No: 2694. 21.9.74.

Ob. 480

Order to P. M. 10 June 74 P. S. 1. 1.

[illegible]

This architectural drawing shows a small building with a gabled roof. The roof is supported by a series of vertical posts. The front facade features a central arched window with a grid pattern. The building is shown in a cross-section view, revealing the internal structure and the roof's slope. Dimensions are indicated with numbers and lines.

PLAN.

Architectural plan of a rectangular building. The central hall is labeled 18×12 . Surrounding the hall are several rooms and corridors, some of which are shaded. Dimensions for these areas are provided: 5×5 (top center), 5×8 (bottom center), 5×5 (top left), and 5×5 (top right). A vertical corridor on the right side is labeled 5×5 . The plan is oriented with a north arrow pointing towards the top right. The drawing is labeled 'PLAN.' at the top and 'A' at the bottom.

Revised Abstract Estimate for a Dead House.

Quantities	Particulars	Per Sq. Ft.	Per Lineal	Total
15 1/2	Cubic yards. Excavating foundation			
8 1/2	Cu. yds. Filling			
16 23	Cubic feet. Bulk in Chumam			
6 1/2	Do. Arch-work Do			
5 1/4	Square feet. Planking & waste wadding			
5 75	Do. Roofing with Teakwood.			
	Freezers, Sails, Kib and pan			
	Tiles Chumam borders &c. Complete			
70	Cubic feet. Teakwood for Cupboards, Rackets,			
	Stops & Wall plates			
2 1/2	Square feet. Asphalt's flooring 1/2 inch			
1	Door Panelled & glazed. Complete			
3	Windows glazed Do			
2	Squares of Wood Oil to Door and Windows			
42	Square feet. Granite for Steps			
4	Planking feet 1/2 inch. Lead piling for sink			
16	lbs Sheet lead for Sink			
	Sundries at 55% int.			
	Total Estimate			

Adele Scott.

Walter R. R.

Under Secretary to the President P. K. D.

*Proceedings of the Madras Government, Public Works Department,
18th Jul, 1874.*

No. 348. Read the following letter from Colonel E. A. FOORD, R.E., Inspecting Engineer for Civil and Military Buildings, to Colonel G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Chepauk, 8th June 1874, No. 811:—

With reference to the Order of Government of the 3rd March 1874, No. 29, I have the honor to forward a revised plan for a dead-house with an estimate for the same amounting to Rupees 565.

2. The plan and estimate, which I forwarded to the Surgeon-General, Indian Medical Department, and which were returned to me with his approval, only differed from these in there being no ventilator in the former and the walls being of brick-in-clay. In this estimate the walls are of brick-in-chunam, and in the plan openings under the eaves have been substituted for the wall ventilators.

ESTIMATE No. 4.—B.

REVISED ESTIMATE FOR DEAD-HOUSE.

Standard Plan—(walls only 12 feet high).

Walls—of brick-in-chunam, pointed and whitewashed.

Roof—thatched, with eave ventilators.

Quantity.	Particulars.	Rate.	Per.	Amount.	Total.
		RS. A. P.		RS. A. P.	RS. A. P.
1,429	Cubic feet of brick-in-chunam ...	0 2 5	C. foot.	215 13 5	...
61½	Do. of archwork-in-chunam.	0 3 3	"	12 7 1	...
15	Squares of pointing and whitewashing	1 2 0	Square.	16 14 0	...
2-16	Squares of asphalte flooring, half inch thick	14 13 0	"	31 15 11	...
8-64	Squares of roofing with bamboo rafters, purlins, reepers, including country-wood couples, with two collar pieces, etc., complete.	15 0 0	"	129 9 7	...
23	Cubic feet of country-wood, wall-plates, struts, and bressummers...	2 0 0	C. foot.	46 0 0	...
8-75	Squares of tarring, two coats to woodwork	0 11 6	Square.	6 4 8	...
1	Door panelled and glazed, complete	34 4 0	Each.	34 4 0	...
3	Windows glazed, complete	13 10 0	"	40 14 0	...
2	Squares of wood-oil to doors and windows	0 12 6	Square.	1 9 0	...
25	Cubic yards of excavating the foundation and filling the basement	0 2 0	C. yard.	3 2 0	...
	Total...	...	...	538 13 8	...
	Sundries at 5 per cent...	...	...	26 2 4	...
	Total Estimate...	...	...	...	565 0 0

CHEPAUK,
8th June 1874.

(Signed) E. A. FOORD, Colonel, R.E.,
Inspecting Engineer for Buildings.

Proceedings of the Madras Government, Public Works Department,
18th July 1874.

No. 349. ORDER THEREON, 18th July 1874, No. 1,932.

CIVIL WORKS, No. 29.

His Excellency the Governor in Council sanctions the plan and estimate submitted with this letter as standards for the construction of dead-houses.

2. The plan will be lithographed for distribution and the estimate printed.

(True Extract.)

Amrutha Colonel, R.E.,
Secretary to Government.

To District Engineers *Garyain*
To the Executive Engineer, Wynaad.
To the Surgeon-General, Indian Medical Department.
,, Judicial Department.

Exd. E. C. Shunker.

3 Spare Copies will follow from Madras

Public Works Dept
Proceedings of the Madras Government
19 Read the following
1932
Now
The Inspr Engr
for Buildings (To Cols 811-878 June 1874)

His Excellency the Governor in Council sanctions the plan and estimate submitted with this letter as standards for the construction of dead houses.

The plan will be lithographed for distribution and the estimate printed.

MD 24/7
7/26
District Engineers
Ex Engr Wynaad
Surgeon Genl. Ind. Med. Dept.
Judicial Dept.

(3 copies sent to the
Govt. Secy to Govt.)

AMM

Public Works Department

Letter from the Inspecting Engineer
for Buildings No. 811, dated 8th June 1874.

For Order.

Submitted for
order.

Mr
19/6
No dear details etc
but I have no more further

C. M. Walker Esq. R.E.
Secretary to Government
S.W.C.

11

Received
by
the
Secretary
to
Government
on
the
11th July 1874

A.S. July 17th
Per 2/1/14 Rtd 6/7/74

*Proposed to be
erected at the
corner of the main
road to the*

3470

*Proposed to be
erected at the
corner of the main
road to the*

*Proposed to be
erected at the
corner of the main
road to the*

*2. 8. 174
Civ 19/6/74*

2694 S.H.B. 17

Proceedings of the Madras Board
Read the following

From
The Inspectors } (H.E. No 81178 June 174)
for Civil & Military Buildings

His Excellency
the Governor in
Council is pleased
to adopt a modifi-
cation of the Plan
and Estimate sub-
mitted with this
letter, ~~which~~ ^{modified} allow
of the roof being
tiled instead of thatched
and desires that the
plan be lithographed
and adopted as a
Standard

174

Standard Plans.
Comm

Public Works Department
Letter from District Engineer
Cuddalore, No. 608, dated 1st July 1874.

For orders.

Resubmitted with
printed copy of L.O. No. 1932
dated 18th July 1874, ap-
proving of a standard
Plan for Dead Manceo.
Orders are requested
as to whether the order
(which has not yet
been issued) should
go in its present form
providing for a
thatched roof, or be altered.

where letter has
been sent. M.
3/5.

C. M. Nether C. M. R.
Secy. Board P.W.D.

To District Engineer
& Engineer Mysore
Surgeon Gt. Indian Med. Dept
+ J. D. P. O.
(50 Plans & 50 L.O.)
S. Copies & Plans despatched
to all 28/9/74.

480-481.

5/9/74 Rtd 11/9/74

3490^{not sent to press.}
Govt. of 1874 Madras.

PUBLIC WORKS.

To, *Superintendent*
Public Works
Madras
Robert Ingers

ated

ated

Exd. 2

Very
G. O. 21 Sept. 1874, No. 2694

120

Hos. 480-687.

Dead-houses

The modified Plan
submitted for the con-
sideration of — sanctioned.
The Plan ordered to
be lithographed & x-
copied as a
Standard Plan —