

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No.	2728	Press
B.P. No.		Mis.
Dated	28-7	1954

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
28th September 1874.*

No. 550. Read the following letter from Captain J. L. L. MORANT, R.E., District Engineer, Neilgherries, to Colonel G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Ootacamund, 17th September 1874, No. 294 :—

I HAVE the honor to submit an estimate, amounting to Rupees 309, for putting in proper repair the road from Hannington tope, skirting the Honorable J. D. Sim's Park, at Coonoor, up to where it enters private property.

No. 551. ORDER THEREON, 28th September 1874, No. 2,728.

CIVIL WORKS, No. 46.

SANCTIONED for immediate execution, specific allotment of funds being made hereafter from expected savings.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the District Engineer, Neilgherries.

.. Officiating Controller of Public Works Accounts.

— Kilgherry District —

Wor^{to} Estimate of the probable Cost of placing in proper repair the existing road from Bannington Top Skirting the Honorable J. W. Sims Park & other private property.

Measurement

to L^d W. Carbutt Particulars of Work.

Earth Work

80	12	4	240	} From the road to woodhouse to Drain No 1	
8	5	9	360		} this Cutting
100	12	12	1800		
200	12	3/8	900	} From Drain No 1 to Drain No 2	
250	12	3/8	1125		
425	12	3/8	1912 1/2		
8	5 1/2	15	660	} Mouth of old Drain	
125	12	3/8	562 1/2		
125	12	3/8	562 1/2		
125	2	10 1/2	2625	} From Drain No 2 to Drain No 3	
250	12	3/8	1125		
200	12	3/8	900		
240	12	3/8	1215	} From Drain No 3 to Drain No 4	
240	12	3/8	1215		
260	12	3/8	1170		
6	4	8	192	} to junction of Quinto road	
200	12	3/8	900		
2855	2	1 1/2	8565		

2607 1/2
964 Cubic Yards Earth Work

Parapets

12	2	2	48	} on 3 old Cross drains
12	2	2	48	
12	2	2	48	
<u>144</u>				Cubic yards Rough stone Parapets
<u>5</u>				

Blasting and removing rocks
 4 3 3 36
 3 2 1 2 9
 3 2 2 12
 6 3 4 72
 8 4 2 64
 24 2 2 120
 6 3 2 36
 4 2 1 10
 4 2 1 8
 5 1 1 7 1/2
 3 2 1 6

380 1/2

14 Cubic yards Blasting & removing rocks.

Estimate of 500 of 1874 & 5.

Nikheny District

Work Estimate of the probable cost of placing in
 proper repair the existing road from Hamiltons Cove
 Skirting the Honorable J. D. Sims Park up to Private
 property.

Quantity Description of Work Rate Per unit Total

964 Cubic yards Earth Work
 5 — W. — W. stone Parapets
 14 — W. — W. Blasting & removing rocks
 3 Old drains to be lengthened & packed
 9 New stone drains @ 1 1/2 x 2 x 2 1/2

2944.

Superintendent & Sundry 11 12

Total Estimate Rupees 309.

Amount of Estimate Rupees Three hundred
and nine only.

J. H. Munn
 Captain R. C.

Dist Engineer office District Engineer
 Ootacamund
 16th September 1874

Amount not successful (amount) for amount
of the same for

Amount not successful

Mr 59318/74.
No. 28 2728-289-74
P. 4. 27 28 Sept 74
L. 18. 1:550.

No. 294

Potacumund
District Engineer's Office
17 September 1874

From

The District Engineer
Stilgheries.

To

The Chief Engineer and
Secretary to Government
Potacumund
Sir.

I have the honor to
submit an estimate amounting
to Rs 309.00 for putting in proper
repair the road from Hannington
Tops skirting the Honorable A. D.
Sind's Park at Coonoor up to
where it enters private property.

I have the honor to be
Sir

Your most obedt Servt

Jas. Morant Captain R.E.

District Engineer.

Dear

No: 5931A.

The Rectified

Still Mining

Wm Lloyd Garrison

Secretary to Govt
D. W. W.

Sept 1872.

St. Michael and St. George

Shirley and Robert

of Alsatians & the word
of Alsatians & the word

Writing the Monographs
J. D. Davis and the others

Records

Col. of 1574. 30 miles.

PUBLIC WORKS.

To _____
 Date _____
 Recd. _____
 Enc. _____

Date _____
By _____

Encl. /

C. O. 28 *Delph* 1874, No. 2728

556-557-
F105.

1000 from Spaulding Co

the amount the double

5 kinds / each at 1000

210 3/10 for
Columbo

Amorim Luis & C. = 2018

conclusions for the investigation.

reaction, ~~Stages and~~

~~Handwritten signature~~