M.R.O. 1—10,006—28-2-50.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE

Government of Madras

public works DEPARTMENT

G.O. No. 3220 Press

~~B.P. No.~~ ~~Mis.~~

227-28

Dated 16-11-1928 ~~195~~ .

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
14th November 1874.

No. 227. Read the following letter from Major J. O. HASTED, R.E., Superintending Engineer, 1st Division, Kistna, to Colonel G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Masulipatam, 6th October 1874, No. 77 :—

AGREEABLY to G. O., No. 2,694, dated 21st ultimo, I have the honor to forward, herewith, two estimates* for constructing dead-houses at Guntoor and Masulipatam, amounting to Rupees 1,000 and 880, respectively, and to request that they may be sanctioned in lieu of those sanctioned in G. Os., Nos. 2,335 and 2,336, dated 17th July 1869.

* According to revised Standard Plan.

2. The revised estimates have been included in ensuing year's Budget, as the dead-houses are reqired for Police *post mortem* examinations.

No. 228. ORDER THEREON, 14th November 1874, No. 3,220.

CIVIL WORKS, No. 19.

THE estimates, amounting to Rupees 1,000 and Rupees 880, respectively, for the construction of dead-houses at Guntoor and Masulipatam are sanctioned in lieu of those* approved in G. O., Nos. 2,335 and 2,336, dated 17th July 1869. But the works being below Rupees 2,500 cannot be budgetted for, and will have to be carried out from allotments which will, if practicable, be made from the Reserve of next year.

	RS.
* Guntoor	1,260
Masulipatam	925

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the Superintending Engineer, Kistna.
" Officiating Controller of Public Works Accounts.
" Judicial Department.

Exd. S. T. Austin.
Spare Copies

Kistna

Abstract Estimate &c of 1874-75.

District Kistna Taluq Bunder

Revised – Constructing a Dead House for Hospital at Masulipatam as per standard plan sanctioned in G.O. No. 2694 of 21st September 1874.

1522 ft

Quantity	Description of Work	Rate	Amount Total
15 1/4	Cyds of Ry Coursing foundation per Cyd	" 13	1 31
8 1/2	do of Filling do	" 13	" 10 8
60 1/9	do of Brick in Chunam do	5 8	330 9 10
2 5/15	do of Arch work do do	6 8	14 12 11
16 7/50	Lgths of pointing & whitewashing per Sqr	2 4	36 5 1
5 3/4	do of Roofing with Teakwood rafters, laths, flat & pantiles Chunam borders &c Complete do	15 "	86 4 "
78	Cft of Teakwood Couplis, raftis, steps & wall plates. per Cft	2 8	195 " "
2 8/50	Lgths of Phosphatte flooring 1/2" thick under which 4" of Concrete with a substratum of broken stone of 3" thick Complete per Lgth	184 "	396 9
1	Door 3/4 Panelled & 1/4 Glazed Complete 5'x8'	45 " "	45 " "
3	Windows glazed do do 3'x5'	20 " "	60 " "
2	Sqrs of wood sill to door & window openings	24 "	4 8 "
1 5/9	Cyds of Cutstone work per Cyd	8 " "	12 7 1
4	Dgs ft of 1/2 inch lead piping per Cft	" 8 "	2 " "
16	lbs of Cleat lead for Cisk	" 6 "	6 " "
	Sundries & Contingencies at about 5 per Ct		45 12 7
	Total Estimate Rupees		880 " "

Supg Engr's office 1st Cir N.
Masulipatam 6th October 1874

Lt actual Major R.E.
Supg Engr 1st Cir Kistna

Abstract Estimate &c. of 1874-75.

District Krishna Subg Gudivada

Revised Constructing a Cadjan Shed for Hospital at Gudivada &c per Standard Plan sanctioned in G.O. No. 2694 of 21st Septr 1874

Quantity	Description of work	Rate	Amount	Total
15 1/4	Cyds of Excavating formed above per Cyd	" 1 3	1 31	
8 1/2	do — of Filling — do —	" 1 3	" 10 8	
60 1/9	do — of Brick in Chunam — do —	5 8	330 9 10	
2 5/18	do — of Plaster work — do — do —	6 8	14 12 11	
16 7/50	Lyrs of Whiting & white washing per Sq	3 "	48 69	
5 3/4	do — of Roofing with Teak wood rafters bails, flat & pantiles Chunam borders &c complete — per do	17 "	97 12 "	
78	Cft of Teak wood for Angles, Ridging Hips & wall plates — per Cft	34	253 8 "	
2 8/50	Lyrs of Asphatte flooring 1/2" thick under which 4" of Concrete with a Substratum of broken Stone of 3" thick Complete per Lyrs	188 "	39 154	
1	Door Panelled & glazed Complete 5'x8'	55 "	55 "	
3	Windows glazed — do — 3'x5'	25 "	75 "	
2	Lyrs of wooden Shelves per Lyrs	1 8 "	3 "	
1 5/9	Cyds of Ash Stone for Steps — per Cyd	12 "	18 10 8	
4	Rft of 1/2" Iron Piping for Sink	" 8 "	2 "	
16	Nos of Shut Irons for Sink	" 6 "	6 "	
	Sundries & Contingencies at about 5 per Ct		53 69	
	Total Estimate Rupees			1000 " "

Supdg Engrs Office 1st Dn
Masulipatam 6th October 1874

Jon actud Major RE
Supdg Engr 1st Dn
Krishna

Enclosure in a letter No 37 dated 6 October 1874 from the Supdg Engineer Vellore to the Secretary to Govt G.O. Dl Dept

Revised

Abstract Estimate for Constructing a Head House for Workmen at Gantur for Rs. 1000-

WW. 6501/2/74.

Rg. 714 Nov 74
In Bk. 227

the dead Horses and required for Police

Post-Mortem examinations.

I have the honour to be,
Sir,
Your most obedient Servant

J. H. Stead Major R.E.

Superintending Engineer 2nd Div. Kistna

P. W. Office, Dowlaishweram
the 26th August 1869.

Received 6th September 1869
8.P.C.

Proceedings of the Madras Govt.

Read the following:-

From the Supg Engineer
Kistna } (R. P. No. 773 6th Oct. 1869.)

3220

The estimates amounting to Rs 1001 and Rs 880, respectively, for the construction of dead Houses at Guntoor and Masulipatam are sanctioned in lieu of those approved in G. O. Nos. 2335 and 2336, dated 17th July 1869 - But the works being below Rs 2,500 cannot be budgetted for, and will have to be carried out from

Rs 1001
Rs 880
Rs 1881

+ Guntoor Rs 1260
Masulipatam " 925

Rs 2185

Rs 2185
Rs 2000
Rs 185

Rs 2000
Rs 185

Rs 2000
Rs 185

from allotments which will, if practicable, be made from the Reserve of next year.

Govt

Am[t] of Stores issued to the Troops

98

Surplus of Victuals
Contr[s] for Rec[d] &c.
Ind[e] Debts
Copies dispd 20/11/74.

227-228.

Rec[d] 21/10/74 Rep[d] 31/10/74

6501

Govt. of [1874] Madras.

PUBLIC WORKS.

To

Re Supp: Supr:
Kistna

Dated

Recd. Encl. 2

G. O. 12 Nov 1874. No. 3223

Nos. 227-228.

Dead Hoses at Guntoor and Masulipatam - Kistna Dt.

Estimates amounting to Rs 1070 & Rs 880, respectively for the construction Nine Dead Hoses, sanctioned in lieu of those approved in G O Nos 2335 & 2336 dt 17 July 69 and the works to be carried out from allotments which will, if practicable, be made from the Reserve of next Year —