Proceedings of the Madras Government, Public Works Department, 10th December 1874.

No. 201. Read the following letter from Major J. BEATTY, R.E., District Engineer, Godavery District, to Colonel G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Dowlaishweram, 30th October 1874, No. 2,428 :—

I HAVE the honor to forward herewith an estimate, amounting to Rupees 1,920, for repairing sea punt No. 1, which work has already been put in hand, as stated in this office letter No. 2,176 of 9th October 1874, from the sum of Rupees 2,700 allotted in G. O., No. 2,271, of 17th August 1874, and to request you will be good enough to obtain sanction of Government for the same.

2. It is proposed to undertake the repairs of two more punts if sufficient funds are available. The detailed estimates for the repairs of these punts cannot be framed till they have been docked and examined.

No. 202. ORDER THEREON, 10th December 1874, No. 3,471.

ACCOUNT, No. 14.

THE estimate for repairing a sea punt belonging to the Cocanada harbour plant, referred to by the District Engineer, Godavery, is sanctioned. It is observed that it amounts to Rupees 1,920. Funds will be allotted for carrying out similar work to other boats as estimates are received.

2. It seems desirable that a schedule of rates for work carried on in the Dowlaishweram Workshops should be periodically furnished by the District Engineer for check and comparison with those prevailing at other building yards. Such will hereafter be forwarded on the 1st April in each year.

(True Extract.)

Colonel, R.E.,
Secretary to Government.

To the District Engineer Godavery.
,, Officiating Controller of Public Works Accounts.

Exd. S. T. Austin.
Spare Copies

Detailed Estimate No. 98 of 1874-75

Government workshop. "Repairing Tools & Plant"

Work - Repairing No. 1 Sea Punt. 31

Particulars of work	Number	Measurement: Length	Measurement: Breadth	Measurement: Height	Square or Running feet	lbs per foot	Cubic Contents
1	2	3	4	5	6	7	8
Iron work							
Sheet Iron for bottom	18	11. 3	2-6	0-1/4	506 1/4		
Do for both ends	2	8-3	2-6	0-1/4	41 1/4		
Cover plates under ribs	17	1-2	0-8	0-1/4	13 1/4		
Patches to hull	2	3-3	2-6	0-1/4	16 1/4		
					577	10	5770
Bilge plates	2	52	0-8	0-3/8	69 1/3		
Sheet Iron for 1 Iron head	1	5	2.6	0-3/8	12 1/2		
					81 5/6	15	1227 1/2
L Iron for fitting Safe plank	1	72	2" x 2"	0-1/4	72	4 1/2	324
Round Iron for bolts Do Do	36	1'	1/2"	diar.	36	3/4	27
Do for cross pieces to Iron bars	4	1'6"	1"	diar.	6	2 1/2	15
Do Do for Rivets	4400	0-3	5/8"	diar.	1100	1/16	1168 3/4
					Total Wrought Iron lbs		8532 1/4
Wood work							
Deck planking. (only half part)	1	50	6-3	0-2			52-1-0
Beading pieces	4	6-0	0-6	0-2			2-0-0
Safe plank (only one side)	1	60	0-9	0-2			7-6-0
Trough							
Planks	2	34-0	1-4	0-2 1/2			18-10-8
Do	2	9	1-4	0-2 1/2			5-0-0
					Total Teak wood eft		85-5-8

Caulking	Rft	1100
Painting out side	Sqrs.	8½
Larring in side	"	8½
Docking & Launching	"	"

No 98.

Abstract

Quantity	Description of Work	Rate	Amount	Total
1	2	3	4	5
8532¼	lbs Wrought Iron	@ 2 6	1333 2 7	
85 5⅔	Qft Teak wood wrought and put up	2 " "	170 15 1	
1100	Rft Caulking — Hundred ft	3 " "	33 " "	
8½	Sqrs. Painting out side	3 8 "	29 12 "	
8½	" Larring in side	1 8 "	12 12 "	
	Docking & Launching	" " "	20 " "	1599 9 8
	Centage	20 " "	%	320 6 4
	Total Rupees			1920 " "

Govt. Workshop
Dowlaishweram
13th October 1874

Signed R. R. C. Brockman Captain R.E.
Executive Engineer in charge
Government Workshop.

/ True Copy /
R. Beatty. Major R.E.
District Engineer Godavery

DISTRICT ENGINEER'S OFFICE, GODAVERY.

No. 2428 DOWLAISHWARUM, 30th October 1874.

From.

Major J. Beatty R.E.

District Engineer

Godavery District

To.

Colonel G. W. Walker R.E.

Secretary to Government D. P. W.

MADRAS

Sir,

Enclosure 1 one

I have the honor to forward herewith an Estimate amounting to Rupees 1,920 for repairing Sea Punt No. 1 which work has already been put in hand, as stated in this Office letter No. 2176 of 9th October 1874, from the sum of Rupees 2,700. allotted in G.O. No. 2271 of 17th August 1874, and to request you will be good enough to obtain Sanction of Government for the same.

2. It is proposed to undertake the repairs of 2 more punts if sufficient funds are available. The detailed estimates for the repairs of these punts cannot be framed till they have been docked and examined.

S.P.W. 1951/74

Enclosure in a letter No. 2428 dated 30th Oct 74 from the District Engineer Godavery to the Secretary to Government P.W.D. Madras

Rly. Dte. Dec. 1/74

Ltr. R.S. No. 207.

I have the honor to be

Sir

Your Most Obedient Servt.

L. Beatty Major R.E.

District Engineer Godavery.

Ead

P. W. 1874. Dept.
No. 6931.

From

The District Engineer,

Godavery District.

To

The Secretary to Government

Department Public Works

MADRAS

Dated. 30 October
Received. 6 Nov. } 1874

NO. 2428

Enclo. 1

Subject.

Submitting detailed Estimate of Special repairs to No. 1 Sea Punt.

A. No 3241- 10 Dec 1874

A 207

~~Cir 12-12-74~~
Cir 26-11-74

Common
~~Rec'd to be Reg~~ 6 Nov 74

P. W. D.

Proceedings of the Madras Government,

Under date the 187 .

Read the following:—

From

The District Engineer, Godavery } (8471 / C.R. No. 2428 d/30 Oct/74)

The Estimate for repairing a Sea Punt belonging to the Nerasapoor Harbour Plant, referred to by the District Engineer Godavery is sanctioned. It is observed that it amounts to Rs 1,920- Funds will be allotted for carrying out similar work to other boats as Estimates are received.

2. It seems desirable that

If Hall the Funds Voted for such Charges on the Debtor, may always be reduced W.

that a Schedule of rates for work carried on in the Vowlaicheveram Workshops should be periodically furnished by the District Engineer for check and comparison with those prevailing at other building yards - such will hereafter be forwarded on the 1st April in each year.

Govt

207-202

Govt. of 1874 Madras.

951

PUBLIC WORKS.

To

The Dist. Engr.
Godavery

Dated

Rec'd. Encl. 1

G. O. 10 Decr 1874. No. 3471

Nos. 201-202.

Punt sanctioning an Estimate for repairing a ferry punt belonging to the Cocanada harbour plant & intimating that funds will be allotted for carrying out similar work to other boats as estimates are received -

E
L
F

Govt 26-11-74