M.R O. 1—10,006—23-2-50.

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No. / B.P. No. ~~—~~ 1313	Press / ~~Mis.~~
Dated 8 — 5 —	1875 / ~~—195—~~.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department, 8th May 1875.

No 185. Read the following letter from R SMITH, Esq, District Engineer, Nellore, to Colonel G W. WALKER, R E, Secretary to Government, Public Works Department, dated Camp at Kavali, 8th March 1875, No. 118 —

I HAVE the honor to submit a comparative statement and a revised estimate, amounting to Rupees 32,300, for the first-class Taluq Cutcherry now under construction at Atmakur in this district

2. The excess, to the extent of Rupees 5,365, is, you will observe, owing to the alterations in, and the additions to, the standard design, ordered by Government, subsequent to the preparation and submission of the original estimate, of Rupees 22,700, for this cutcherry and out-houses The details of this excess are annexed —

	RS
Additional verandahs	605
Iron gratings for three doorways in Treasury	135
Iron railing between Treasury and Cashier's room	520
Compound wall and gate	2,730
Ryot's shed	300
Cook-house	150
Branch roads	520
Latrine for establishment	190
Latrine for prisoners	40
Steps	175
Total	5,365

3 With reference to the extra sum of Rupees 725, entered in the revised estimate on account of "Loss sustained by the sudden stoppage of the work in 1870" I beg to explain that a considerable quantity of teak was purchased in that year in excess of the scantlings required for the present design, and that I now find I cannot realize the full price paid for it A loss has also been experienced in altering some of the wood-work to suit the revised design, and provision has to be made to cover the cost of the extra windows made in 1870, until they can be utilized elsewhere

---

No 186 ORDER THEREON, 8th May 1875, No 1,313

CIVIL WORKS, No 14

THE amount of the estimate sanctioned in G O, No 2,190, of the 9th July 1868, was Rupees 22,700, and in the comparative statement now forwarded by the District Engineer the cost of the cutcherry and its accessories is estimated at Rupees 32,300 The net excess to be provided for is therefore Rupees 9,600

2 The total excesses under various heads amount to Rupees 11,342, and the savings to Rupees 1,742, and an analysis of the former shows that they are referrable, firstly, to alterations in the designs sanctioned by Government or to additions made and presumed to be made on the same authority, secondly, to under-estimation in the rates and quantities, and, thirdly, to omissions of details subsequently found to be necessary To the first category belong items aggregating Rupees 6,629, to the second other items amounting to Rupees 4,339, and those of the third are limited to a sum of Rupees 374

3 The District Engineer has included in his revised estimate, as one of the alterations sanctioned by Government, a masonry compound wall, but there is no general authority for such a work; and in view of the urgent requirements in other localities for buildings to be provided for out of the Provincial grant, it may be dispensed with. The estimate will be accordingly reduced by Rupees 3,360.

4 The excesses on account of rates or quantities under-estimated occur principally in the item of stone masonry substituted for brick work and in teak wrought and put up, in wood oiling for the trusses, and in superintendence and sundries They are somewhat greater than would probably have occurred had more consideration been brought to bear on the framing of the original estimate, and a better approximation should be made in the case of similar work in future

5 The amount now sanctioned for the revised estimate, with reference to the correction made in paragraph 3, is Rupees 6,240, but the question of the provision of the necessary allotment to complete the work must be reserved for further consideration, pending which the District Engineer will be called upon to account for his omission to enter the building in his budget list for the current year in the usual manner. Funds would then have been made available, instead of which they have been already allotted to the full extent of the budget grant

(True Extract)

Lieut -Colonel, R.E.,

Officiating Secretary to Government.

To the District Engineer, Nellore
„ Judicial Department
„ Controller of Public Works Accounts

Exd. S T Austin

Spare Copies

No 118

Executive Engineer's Office

Camp Rajmahal

8th March 1875

From

R. Smith Esquire

Executive Engineer Sahebgunge

To

Colonel G. H. Walker R.E.

Secretary to Government

Public Works Department

Fort William

Sir

Executive Engineer

2.

I have the honour to submit

a Comparative Statement and

a Revised Estimate, amounting

to Rs 32,300, for the first Class

Sahebgunge Cutcherry now under

Construction at Atmakur, in

this District.

2 The excess, to the extent of Rs 5,365,

as you will observe, owing to the

alterations in, and the additions

to the Standard design, ordered

by

No 5

Rs 1,000

No 6

No 7

Rs 1,000

No 8

Rs 1,000

No 9

Rs 1,000

No 10

Rs 1,000

No 11

Rs 1,000

No 12

Rs 1,000

No 13

Rs 1,000

No 14

Rs 1,000

No 15

Rs 1,000

No 16

Rs 1,000

No

by Government subsequent to the preparation and submission of the original estimate, of Rs 22700, for the Cutcherry and out houses. The details of the excess are annexed

	Rs
Additional Verandahs	605
Iron Gratings for three doorways in Treasury	135
Iron Railing between Treasury and Cashier's room	520
Compound Wall and Gate	2730
Ryots Shed	300
Cook house	150
Branch Roads	520
Latrine for Establishment	190
Latrine for Prisoners	40
Steps	175
Total	5365

3. With reference to the extra sum of Rs. 725, entered in the revised Estimate, on account of Loss sustained by the land slip stoppage of the work in 1870, I beg to explain that a considerable quantity of Teak was purchased in that year, in excess of the scantlings required for the present design, and that I now find I cannot realize the full price paid for it. A loss has also been experienced in altering some of the wood work to suit the revised design, and provision has to be made to cover the cost of the extra Windows, made in 1870, until they can be utilized elsewhere.

I have the honor to be
Sir
Your most Obedient Servant.

District Engineer

Encl.

by Government subsequent to the preparation and submission of the original estimate, of Rs 22700, for this Catchery and out houses. The details of this excess are annexed

	Rs.
Additional Verandahs	605
Iron Gratings for three doorways in Treasury	135
Iron Railing between Treasury and Cashier's room	520
Compound Wall and Gates	2730
Kyd's Shed	300
Cook house	150
Branch Roads	520
Latrine for Establishment	190.
Latrine for Prisoners	40.
Steps	175
Total	5365

3. With reference to the extra sum of Rs. 725, entered in the revised Estimate, on account of Loss sustained by the said Inundation of the work in 1870, I beg to explain that a considerable quantity of Teak was purchased in that year, in excess of the scantlings required for the present design, and that I now find I cannot realize the full price for it. A lower has also been experienced in altering some of the wood work to suit the revised design, and provision has to be made to cover the cost of the extra Windows, made in 1870, until they can be utilized elsewhere.

I have the honor to be
Sir
Your most Obedient Servant.
[signature]
District Engineer

Encl.

P. W. 1875 Dept.

From No: 1671

The District Engineer
of Nellore

To

The Secretary to
Government
P. D. P. W.
Fort Saint George
Madras.

Dated 8th March 875
Despd 11 Do
Received 15th —

No 118
Encls 2

Submits for sanction
a revised Estimate and
Comparative Statement
for the 1st Class Tahg
Cutcherry now under
construction at Atmakur
in the Nellore District
amounting to Rupees 32300

G.O. No: 1319. dt 5-7-75.

G.O. July 68 No 222-223.
" 29 Augt " 557-558.
" 1st March 69 46-47.
" 17 Octr 73 269-270.
Mat. prepared in the Letter Dept.

No 785

C-1-5-75 R-3-5-75

Comparative Statement of the Cost of Constructing a 1st Class Salt Catchery at Atmakur. Sanctioned by Government in G.O. No 2539 dated 17th October 1873.

Description of work	As per original Estimate			As per revised Estimate.			Increase		Decrease		Remarks
	Quantity	Rate	Amount	Quantity	Rate	Amount	Quantity	Amount	Quantity	Amount	
Scaffolding			200			280		80			
Excavating foundations and filling in basement etc Complete			150			150					
Strong iron case for Treasure 6x5x4 internal dimensions			100						100		Not required as Treasury to be railed in
Iron Railings for Cashier's room including Cartage						520		520			Agreeably to G.O. No 1288 dated 13th May 1874
Loss sustained by the alteration of wall built in front of the Tahsildar's Court house.						93		93			This work was removed on the receipt of the order directing additional verandahs
Superintendence and Sundries			943 6 6			1362		418 12 3			
			1470			1940		8411		3571	20
Cook Room											
Concrete in Chunam Cft			936			306		306			The revised estimate is for a Cook house according to the revised design sanctioned in G.O. No 1014 dated 20th April 1874
Brick in Chunam do	20½	4 2	84 90				20½	84 90			
Cut Rough stone in Chunam do			33 4 20	136	2		33	136 2			
Teak wood wrought and put up Cft	15¾	3 4 0	5 1 5 0	9	4	36			6¾	15 5 0	

diagonally over 3" of broken brick rubbish including pointing the floor with Chunam complete	32	8	256	44 10	440	12	184			Excess in quantity owing to the flooring in the additional verandahs. Difference in rate is owing to the difficulty of getting suitable Bricks
Squares of flooring with 3/4 thick Asphalte with 4" Concrete in Chunam and with a Substratum of brick rubbish 3" thick Complete	7.56	31 8	238	2 3 7.56	31 8	238 2	3			
Roofing with flat and pan tiles and Chunam borders Complete Squares	86.35	10	863	8	99 70	990	12.65	12 6 8		The excess is the roofing for the additional verandahs ordered in G.O. No 795 dated 23d November 1874
Flooring with 1" Teak wood planking including varnishing the Ceiling Complete Square	5.5	27	148	8	5.5 45	247 8		99		It is proposed to use 1 1/4 inch planking instead of 1" which will cost Rs 45 per Square at the current rates. Experience has proved that at an out-of-the-way place like Atmakur Teak wrought and put up cannot be done for less than the sum given in the revised Estimate
Teak wood wrought and put up for trusses of 18' Span				46 4	184	46	184			

Teak wood wrought and put up for trusses of 15 span				25½	4	102	
Teak wood including wastage etc cft	996	3	4	3237		1003-4	4012
Do for reepers	130	3	6	438	12	148½ 4	594
Loss sustained by altering the Teak wood collected in previous years to suit the revised design						106 3 2	331 4
Plastering with 1 coat of Chunam Square	144	1	12	252			

							Experience has proved that, at an out of the way place like Attakur, Teak wrought and put up cannot be done for less than the sum given in the revised estimate
				25½	7	702	
							Experience has proved that at an out of the way place like Attakur Teak wrought and put up cannot be done for less than the sum given in the revised estimate. The excess in quantity is for the additional verandahs
							Do Do Do Do
							A large quantity of Teak was collected for this cutcherry in 1870 that would not suit the Scantlings of the present design. This item is to cover wastage and the difference between the dimensions of the old and present Scantlings
				144	252		

Plastering with 2 coats of Chuliana Squares	36				144	5	12	396	Two coats of Plastering are allowed instead of one.
Colour wash Squares	144	4	36		144	4	36		
Pointing Squares	95	2 4	213	12	95	2 4	213	12	
Dental Cornice work Rft	379	4	94	12	379	4	94	12	
Wooden frame work including nails etc Complete Sqft	94	6	35	4	94	7	41	2	
Pairs of Doors 1/3 Panelled and 2/3 Venetianed with hinges, bolts etc Complete according to the standard design 4-4×8-5	24	54	1296		24	54	1296		
Iron barred windows for record room including Venetian shutters and Teak wood frames hinges bolts circular glazed heads etc complete 2-3×5-6	10	34	340		6	52	312		4 28 — the windows made in 1870 had to be altered to suit the revised design
~~Do Do 2-3×4-1½~~	1	25	8	25	8	0	140	40	14 8
Glazed circular heads 2-3×1-1½	7		7		5	7	35		4 28 According to revised design
Door Iron barred inside and batten outside according to the standard design 4×7½ ft with pad locks Complete	6	75	450		6	75	450		

Iron Railings for sides and rear of Cashier's Room					3	45	135	3	135	Ordered in G.O. No 1288 dated 15th May 1874.
Iron barred Ventilators for prison wards 4×2'	6	11	66	6	11	66				
Teak wood venetians including Corner uprights & iron Bolts of 5' long each with nuts, washers and paintings etc Complete. Square feet	110	112	12328	120	2	240	10	47 8		
Roofing turret with Teak wood planks of 3/4 including Corner uprights and painting etc Complete Square feet	105	1	105	110	1 4	137 8				
Chunam moulding to large arch of Sheristar's Court house, Small arches of Clerk's Rooms Public and records rooms etc in and out Rg ft.	380	2	47 8	380	3	714		23 12		
Painting both sides of doors and the exposed surfaces of wood work										

| | | |

Iron King rods, nuts, straps, bolts, and fittings &c Complete	2	6	8	13			2 13	
Iron work for trusses of 15ft Span including iron King rods, nuts, straps, bolts and fittings etc Complete	1	6	12	4 8	140	2	28	
Stone bed plates for trusses	18	12	13	8	18 3	54	40 8	Fine granite slabs were used instead of ordinary dressed stone
Do Do for Posts	14	8	7				14 7	
Teak wood Ornamental board in front of the Public including iron work etc complete	1		10	1	20	20	10	Original rate too low for the style of work desirable
Ornamental wrought iron finial fitting etc Complete	1	15	15	1	40	40	25	Do Do
Stair case with Teak wood steps etc complete	1	50	50	1	86	86	36	Do Do
Lbs zinc sheet to lay in the valleys of Roof including fitting etc	600	4	150		600	4 0 150		

Iron King rods, nuts, straps, bolts, and fittings &c Complete	2	6	8	13				2 13	
Iron work for trusses of 15 ft span including iron King rods, nuts, straps, bolts and fittings etc Complete	2	6	12	4	8	140		2 28	
Stone bed plates for trusses	18	12	13	8	18	3	54	40 8	Fine granite slabs were used instead of ordinary dressed stone
Do Do for Posts	14	8	7					14 7	
Teak wood Ornamental board in front of the Public including iron work etc Complete	1		10		1	20	20	10	Original rate too low for the style of work desirable
Ornamental wrought iron finial fitting etc Complete	1	15		15	1	40	40	25	Do Do
Stair Case with Teak wood steps etc complete	1	50		50	1	86	86	36	Do Do
Lbs Zinc Sheet to lay in the valleys of Roof including fitting etc	600	4		150			4	150	

Scaffolding			200		280			80	
Excavating foundations and filling in basement etc Complete			150		150				
Strong iron case for Treasure 6×5×4 internal dimensions			100					100	Not required as Treasury is to be railed in
Iron Railings for Cashier's room including Cartage					520			520	Agreeably to G. O. No 1288 dated 13th May 1874
Loss sustained by the alteration of wall built in front of the Tahsildar's Court house					93			93	This work was removed on the receipt of the order directing additional verandahs
Superintendence and Sundries			943	6 6	362		9	418	12 3
			1470		1954			8411	2 3571 20
Cook Room									
Concrete in Chunam Do						9	3	6 306	
Brick in Chunam do			20½	4 2	84	90			
Cut Rough Stone in Chunam Do								20½ 84	90 The revised estimate is for a Cook house according to the revised design sanctioned in G. O. No 1014 dated 20th April 1874
						33	4	20 136 2	33 136 2
Teak wood wrought and put up Cft			15¾	3 4	0 5	1	5	0 9 4 36	6¾ 15 50

Roofing with Palmyrah rafters, reepers, rafter and reeper nails, flat and pan tiles &c Complete Square	4	25	100	4 3/4	30	1428		3/4	4 1/2	8 4					The revised Estimate provides for first class Ceylon Palmyrahs
Flooring with 8" Square flooring bricks including pointing with Chunam and a levelling Courses of Brick in clay Complete Squares	472	8	13	12	22 1/5	10	22		0.48	8	3 10				
Plastering with 1 Coat of Chunam	6.25	1	12	10	15	11 1/3	2 12	31 2		8	5 1/12	2 0	3 8		
White washing	6.25		39	1	7.5	11 1/3	39	2 10		6	5 1/12	1	8 7		
Excavating foundations and filling in basement			3 0				3								
Superintendence and Sundries			14	15	5 1/2	21 0	2 12			10		11	3 5		
			280				430					249	14	99	14

Ryots Shed

Concrete Cy.	5.33	3	15	15	10	15 1/3	3 6 0	51 12			10	35	122		The revised estimate is for the
Brick in Chunam do	15.1	4	20	62	47							15.1	624	7	revised design sanctioned
Cut stone in Chunam do						40 1/2	20 165					40	165		in G O No 1014 dated 20th
Honey comb work Squares						1 1/2	5 8 0	84			1 1/2	8	4 0		April 1874.
Flooring with 8" Square flooring bricks set diagonally															

over three inches of broken brick rubbish including pointing the floor with Chunam — Squares	6.65	8		53	32	5¾	10		57	8		4 4 10 0.9
Roofing with Palmyrah Couples, Rafters, reepers nails, flat and pantiles, Chunam borders etc Complete — Squares	11 25 — 275			11	30	—	330					5 5 —
Teak wood work including wastage — Cft.	26.25	3	40	85	5	0	32	4	—	128	5¾	4 2 11 0
Plastering with 1 Coat of Chunam — Squares	1.5	1	120	2	10		11¾	2	12	0	32 5	10¼ 2 9 11
White washing —							11¾	3	9	2	12	11¾ 2 12 0
Country Teak wood Spoots 12' long each —	12	5	—	60	—							12 60 0
Excavating foundations and filling in —					6					6		
Loss sustained by altering the work done as per Old design —										58		58
Superintendence & Sundries				19	9	5				407		20 13 7
										580		422 47 1224

The revised Estimate provides for first class Ceylon Palmyrahs

Latrine for Establishment

12 Seats

Concrete — Cft					18	36	60	12	18	60	120		The revised Estimate is for the revised design sanctioned in G.O. No 1014 dated 20th April 1914. When the foundation was dug it was discovered that a bed of Concrete was necessary to insure the stability of the building
Brick in Chunam — Do		56	4/27	436	236	40					56 4/27	236 40	Hammer dressed stone was substituted for Bricks
Cut Rough stone in Chunam — Do					37	4	36	1581	37	156	16		
Honey Comb work — Squares	1	5	80	5	8	0	6 4/5	5 80	37 6				
Teak wood wrought and put up — Cft	38 1/2	3	40	125	20	28	40	112			10 1/2	132 0	
Roofing with Palmyrah & rafters, reepers, nails, flat and span tiles and chunam borders etc complete — Squares	9 4/5	25	00	195	00	9 1/2	30	285	17/10	90			The revised Estimate provides for first class Ceylon Palmyrahs
Asphalte work 3/4 thick — Squares	2	27	00	54	00	4 1/2	27	121	2 1/2	67	80		
Plastering with 1 coat of Chunam — Squares	20	1	120	35	00	14	2120	38		3	80	6	
Stone work — Cft	3 3/4	3	0	0	11	3	1					3 3/4 113	
White washing								39	3 6	14	3	46	
Teak Doors						2	10	20		2	29	00	
Zinc Buckets							2	28	5	2	5	00	

Excavating foundations and filling in basement				10			10						
Superintendence and Sundries				286	9		307				2010		
				690	00		81				440	13	250 13
Latrine for Prisoners 8 seats													
Concrete — Cft						13	360	43	14		13	43	140
Brick in Chunam — do	1½	4	36	194	10								46 194 10
Rough stone in Chunam do						26	436	109	11		26	109	11 0
Honey Comb work — Squares	1/5	5	80	4	6	5	4/5	5	80	2	36		3 2/20 18 15 7
Teak wood wrought and put up — Cft							29/8	340	94	106	19	4	76
Roofing with Palmyrah rafters, reepers, nails, flat and pan tiles and Chunam borders etc complete — Squares		6	25	0	150	6	30	180					30
Plastering with 1 coat of Chunam — Squares		15	112	0	26	4	0	10½	212	0	2	8	14
White washing — Squares								10½	39	27	4	10½	2 7 4
Asphalte floor ¾ thick — Squares		1½	27	0	40	8	0	2½	27	0	67	8	1 27
Stone work — Cft		2½	3		76								2½ 76
Trap Door						1	10	10					1 10
Zinc Bucket						1	28	28					1 28

The revised estimate is for the revised design sanctioned in G. O. No 1014 dated 20th April 1874.

The revised estimate provides for first class Ceylon Palmyrahs

Excavating foundations and filling in			8		8	
Superintendence & Sundries			21	107	27	11
			540		580	
Probable amount for Constructing a masonry well			150		1	
Constructing Compound wall all round 1400 running feet			700		x 100	
Masonry Compound wall as per Sanctioned design in G.O. No 1014 dated 20th April 1874						
Foundation Cft				5	2	10
Concrete do				1½	36	54
Cut Stone in Chunam do				3	54	162
Plastering Squares				5	1/16	1 120	1 14
White washing do				1/10	39	4
Superintendence and Sundries						6
					Total for 100 ft	24
					For 1400 24 per 100 ft	3360
Compensation for land Sanctioned in G.O. No 2738 of 26th August 1868.			500		500	

					8	11
					253	30	213	30

Gate			70	1	70		
Constructing Road from Atmakur Branch Road leading from the main building to the 4 out houses							
Earth work Cy.	437	1 3 3		437	34 23		Branch roads to Cutcherry
Broken Stone do	334	12 2		334	250 8		and to out houses vide G.O
Red gravel do	167	8 8		167	83 8		No 3480 dated 11th December 74
Drains			30		30		
One Road Tunnel			100		100		
Sundries			21 13	9	21 13 9		
			524		520		
Add amount of loss sustained by sudden stoppage of work			3770		725		The excess included under this head is to cover the cost incurred in altering some of the wood work prepared in 1870 according to the old design, and to cover the loss that will be sustained by selling the surplus Teak collected in 1870
Add amount paid to G. Vardaiah Chetty agreeably to G.O No 2334 dated 5th October 1872			775		775		
General Sundries			15		20	5	
Grand Total			22700		32300	14456 8 10	4856 8 10

District Engineer's Office
Camp Kavali
8th March 1875

RK.

J G Smith
District Engineer

Enclosure in a letter
No 118 dated 8th March
1875 from the District
Engineer of Chittagong to the
Secretary to Government
of B.T. Madras.

Recd

No. 1671/2/75.

GO- 8 May/75
no B No 185

Comparative statement
of the cost of Constructing a
first class Salvey Cutcherry
at Akyab as sanctioned
by Government in G. Lett

Thick Coir Sailing Catcherry at Allinagur — Nellore District.

Excess.

Allowances additions ordered by Government.	Ration Quantities in original Estimate.	Omissions in original Estimate.	Total.	Remarks.
3631 4 -	60 2 6	106 8 3		G.O. No 795 - 23rd March
443 5 -	64 - -	213 - -		— do — do —
120 - -	99 - -	- - -		— do — do —
126 8 -	184 - -	- - -		— do — do —
28 - -	102 - -	- - -		— do — do —
74 - -	747 - -	- - -		— do — do —
396 - -	81 4 -	- - -		
28 - -	331 4 -	- - -		G.O. No 1571 - 13th July 1874
135 - -	5 14 -	- - -		G.O. No 1288 - 13th June
19 4 -	14 8 -	- - -		G.O No 795 - 23rd March
40 8 -	47 8 -	- - -		[illegible]
520 - -	32 8 -	- - -		G.O No 1288 - 13th June
93 - -	23 12 -	- - -		G.O No 795 - 23rd March
- - -	11 4 -	- - -		
- - -	35 - -	- - -		
- - -	28 - -	- - -		
- - -	10 - -	- - -		
- - -	25 - -	- - -		
- - -	36 - -	- - -		
- - -	80 - -	- - -		
- - -	418 12 3	- - -	8411 2 -	
30 6 -	42 8 -	- - -		G.O. No 1014 - 28 April
136 2 -	8 3 10	- - -		
- - -	20 3 8	- - -		
- - -	1 3 1	- - -		
- - -	11 3 5	- - -	249 14 -	
165 - -	35 12 2	8 1 -		do
58 - -	4 4 10	2 12 -		
- - -	55 - -	- - -		
- - -	42 11 -	- - -		
- - -	29 11 -	- - -		
- - -	20 13 7	- - -	422 4 7	— do — do — do —
156 1 6	60 12 -	3 4 6		
- - -	31 14 5	20 - -		
- - -	90 - -	6 - -		
- - -	67 8 -	- - -		
- - -	3 8 -	- - -		
- - -	2 - 10	- - -	440 13 -	
109 11 -	43 14 -	2 7 4		— do — do — do —
- - -	18 15 7	10 - -		
- - -	30 - -	2 8 -		
- - -	2 10 -	- - -		
- - -	27 - -	- - -		
- - -	6 11 -	- - -	253 3 -	
3 3360 - -	- - -	- - -	3360 - -	— do — do — do —
70 - -	- - -	- - -	70 - -	— do — do — do —
620 - -	- - -	- - -	620 - -	G.O. No 3450 - 11th Dec 1874
- - -	725 - -	- - -		
- - -	5 - -	- - -	730 - -	
10260. 1. 6 - 3822. 11. 3 - 873. 12. 1			14456 8 10	
			4836 8 10	
Total Excess Rs			9620 - -	

Govt. Litho Department.
Fort St. George. ——
Madras. 5th April 1876.

Major R.E.
Under Secy. to Govt. P.W.D.

No. II.—PARTICULARS FROM ESTIMATES.

Main Budget Head to which chargeable	Provincial.
Title and purpose of the work as given by District Engineer.	Taluq Cutcherry at Attanakur, Shellore.
Original sanction for the preparation of the detailed estimate (Date and number in both sanctioning and Public Works Department)	G.O No 2190 of 9 July 1868.
Amount of original detailed estimate	Rs 22700
Number and date of sanction and endorsement in Public Works Department	by O No 2539 of 17 Oct/73.
Amount of revised estimate	32 300
Do. of original do	22700
Excess over do. do	9600

* Classification / Exception
1st ... Estimate

Budget Head to which the work is chargeable, in detail
Civil Buildings

Amount of current year's allotment .	6458
Do. expended in previous years	16242
Total .	22,700
Balance to be provided	9600

Left Cuy / and wall

Funds can be made available during the current year ... O
(Yes or no, and state how in former case)
Next year ?

Brought forward as urgent
(Yes or no, and if so state by who)

G.O 8 May/75.
mBk No 185

1873

1671

DOCUMENTS IN FILE.

From District Engineer— Nellore

1 Covering letter No 118, date 8 March/75.
Taking Cutcherry at Atmakur, Nellore.

~~1 Letter from Range Officer, No —, date~~

~~1 Detailed Estimate~~

1 Abstract do.
1 Comparative Statement

~~1 Plan~~

~~1 Specification Report~~

From Office—
1 Standard Plan of 1871
2 — Do — of 1874
3 — Do — of 1872.
Original sanction, No 2190 date 9 July 1868.
for detailed estimate preparation

Orders and Proceedings	No	Date	Under P W D G O No	Under P W D G O Date
P W Department	664	1/3/69		
	2794	15/5/71		
	2334	6/10/72		
~~Do do~~	2559	17/10/72		
	798	23/3/74		
~~Revenue do~~	1814	26/4/74		
	1268	13/5/74		
	1871	12/7/74		
~~Financial do~~	3490	11/12/74		
	2652	24/12/73		
	1340	23/6/74		
Judl ~~Military~~ do	1059	3/7/68	2190	9/7/68
	1257	12/8/68	2738	26/8/68
Rev. — do —	590	11/4/72.	232	23/4/72.

GO 8 May/75
in B No 185

P. W. Dept

Proceedings of the Madras Government

Read the following:-

From the Divisional Engineer, Nellore } (D.E. No. 118 dated 8 Mar/75)
G.O. No. 1313 of 8th May/75.

The amount of the Estimate sanctioned in G.O. No. 2190 of the 9th July 1868 was Rs 22700, and in the Comparative Statement now forwarded by the Divisional Engineer the cost of the Cutcherry and its accessories is estimated at Rs 32300. The net excess he provided for is therefore Rs 9600.

2. The total excess under various heads amounts to Rs 11342 and the savings to Rs 1742 and an analysis of the former

brought to bear in the framing of the original Estimate and whether application should be made in the case of similar work in future.

6. The amount now sanctioned for the revised Estimate with reference to the Correction made in Para 3 is Rs 6240; but the question of the provision of the necessary allotment to complete the work must be reserved for further consideration, pending which the District Engineer will be called upon to account for his neglect ~~and not~~ having the building in his budget list for the current year in the usual manner. Funds would otherwise have been made available instead of which they have been already

allotted to the full extent of the budget grant.

Adg S

AMW

Dr Lt Col Kellner
Jud Dept
Capt Mc Masters Revd Ab. Estt

S-C-dated 20-5-95

1877

Govt. of {1875} Madras.

PUBLIC WORKS.

To

The Dr. Engr.,
Kellore

Dated

Read Ansd

G O, Engrs No. 1313

Nos. 185-86

No 185/6.