M R O. 1—10,006—23-2-50

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No.	3305	Press
~~B.P.~~ No.		~~Mis.~~
Dated	19-11-	1875 —195 .

Not to be folded or roughly handled

~~Specification and Estimate for repairing the Roof of the~~
~~Verandah Roof of the Dwelling House~~
~~of Messrs Watson & Scott~~

The above Estimate provides,

1st For removing a broken Rafter and a Half Rafter destroyed by white ants of the Verandah roof, and for putting up new ones of Bannatoo wood in their place with 2 new Jack Rafters of the greatest length using the old ones for the shorter ones in the event of any of them being found to be unsafe and being removed—

2d " For repairing thereof which had been previously destroyed by white ants by removing the flat Tiles which are unnecessarily heavy, and by putting up the roof again, using 1/2 of new rafters, iron Nails & 1/8 of new Battles & setting the ridge tiles with Chunam—

3 For replacing with Laterite pellew clay the floor of the rear Verandah which is damaged, for replacing the broken glasses of the Door & Window Shutters, for supplying a window Shutter which has been wanting, and for whitewashing the whole building with 2 coats of Chunam—

4 Also also proposed to

remove

remove the timber & standing in the Mauri room as they occupy the whole space of the room - No allowance has however been made for the items in the Estimate as they are liable to be cut & made use of & the Cattle is likely to be sent from the premises under instructions of Superintendence -

Portlock Range Office
South Canara
Currimbetta 6 Aug 1875

Range Officer

Ass. Divisional Engineer

9-11-75

Exd. in Book
11-8-75

Work

Abstract Estimate No. 13 of 1875-76.

South Canara District.

Repairs to the old Choultry at Portlock.

Quantities	Description of work.	Rates			Amount		Total		
		Per	Rs	A P	Rs	A P	Rs	A P	
25.	Replacing the broken glasses including the cost & fixing @	each	0	3 0	4	8 0			
1.	New 2/3 panelled & 2/3 glazed Window shutter with a pair of brass hinges & hook complete				4	0 0			
10 41/48	Cft. Jungle wood wrought & put up @	Cft.	1	12 0	18	15 8			
3822	Sqrft. shifting tiles & removing the flat tiles & putting up the roof again with ridge & 1/3 of new Pantiles and Channam ridges @	Sqre	10	0 0	382	3 2			
618	Repairing the floors of the verandah with laterite & Jelligue @	Sq.	1	8 0	6	11 4			
6098 2/3	Sqrft. Whitewashing the whole building	Sq.	0	6 0	23	6 0			
	Sundries & Superintendence	Total	7	8 0	31	6 5			
					Total of Estimate Rs				475 0 0

Portlock Range Office,
Currimbetta 6th Aug 1875

Range Officer

Ass. Divisional Engineer

Estd in Lr dtd 11-8-75

Detailed Estimate No. 13 of 1875-76.

South Canara District

5

Work. Repairs to the old Place of Travellers Bungalow

Detail of Work.	Number.	Measurements in feet. Length: Each	Length: Total	Length: Total Length	Breadth or Thickness	Height or depth	Contents	Total quantity of each description of Work
Glass Panes for windows & shutters	14	9"	-	9"		1ft.		
Do Do for Door shutters	11	9"	-	9"		1ft.		
Replacing the broken glass & including the cost and fixing								28.
New 3 panelled and 3 glazed Single shutter with a fan of Wood complete	1	5ft.		5ft.	2	5ft.		
New rafter for Wood Verandah roof	1	18	-	18	3	5½	2-9.	
New hip rafter for a cover of Do	1	24	-	24	4	5½	4-36	
New jack Rafters for Do Do	2	18	-	36.	3	5½	4-18.	
Jungle wood wrought & fixed complete						Cubic feet		10-44/48.

Detail of Work.	Number.	Measurements in feet. Lenth. Each.	Total	Total Length	Breadth or Thickness.	Height or Depth.	Contents.	Total quantity of each description of work.

South Canara Dy Engr Office

No 57. Mangalore 9 November 1875

From

R.C. Lawford Esqr.

Dy Engr South Canara

To

Major Genl Cleveland RE.

Secretary to Government

Dpkw

Sir.

I have the honor to submit for the sanction of Govt. an Estimate amounting to £75. for putting in repair the old Police Arms at Portion lately used as a Police Station House.

2. The value of the building being within the limits as reported in my letter No 27 of 21 July 1875 forwarded with Co. No 2216 of 30 Idem, I am unable to sanction the accompanying Estimate under the existing rules.

3. The work Estimated for is absolutely necessary as it is reported that a rafter has been broken and a few rafters and about half the eaves have been destroyed by white ants

4. As it is improbable that any additional or separate allotment can be obtained this year from Govt. from Provincial

P. Wks 1875 Dpkw

No 42 44

From

The District Engineer

S. Canara

To

The Secretary to Government

G.P.W. Bombay

Rate Rs 2½ Rupees 1875

Page 13½ No 57

Budget (3) 1

Re Abt Repairs to Police Arms at Portion lately used as a Police Station House

Submitting for sanction a Prot. an Estimate & Drg amounting to Rs 75 for putting in repairs

Rs 330 S

19th Nov 75

Abstract accompanying Estimate for Repairing the old Police Arms at Portion

Camp Office at Mangalore the 9th November 1875

R.C. Lawford

Dy Engr

Sanctioned

Rs 330 S

19th Nov 75

Chief Engr

Dy Secy

Copy forwarded to Dy Engr South Canara

Chief Engr Office 19th Nov 75

Copy forwarded to Secy to Govt

Chief Engr

Ex 4335 dt 16-11-75

funds, I shall endeavour to spare about
£50 or as much as I can ~~spare~~ from the
balance of repair allotment at my dis-
-posal for appropriation as the estimate
being sanctioned in order to commence
& finish this official year and to ensure
its completion before the month of May
next. The balance will be appropriated
during the next official year.

At present the building is occupied
by the D.A Board as a school at £10 per
month and the Pootoon Range Officers
offers the same rent if let to them as
a dwelling house, on its vacation by the
Board. I crept that it might always be
useful as a dwelling house for a Range
Officer, I do not know any other use that
it could be put to, but I believe that
Pootoon is to be the Baluy headquarters
when it may prove serviceable if not.
Required for the above purpose I think
the money may be advantageously laid
out in its repair.

I have &c

W. of A. C. Crawford
Orderly Officer

Ch. 7274

3305

£ 10-0-0

To 3305.

The return of the
Opening the old Police Station
Should it be provided as
the building been to cease
it is proposed, that the
with a new Quarters with
the Building of Pootoon
Lt. Crawford
Cutchery

7274

Govt. of {1875} Madras.

PUBLIC WORKS.

To [redacted] Fuel Dept

Dated 23-11-1875

Issued

Recd 27 Jan

Fwd

G O 19 Nov 1875. No 3305

Nos. 438-439

Rd Military Barracks at Trichinopoly South Camp

Estimate amounting to Rs 475 for repairing the Cookhouse with terrace