

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public Works

DEPARTMENT

G.O. No.	3380	Press
B.P. No.		Mis.
Dated	26-11	1875
		195

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
26th November 1875.*

No. 593. Read the following endorsement of the Chief Engineer for Irrigation, dated Danaincheroovoo, 16th November 1875, No. 1,358:—

From J. D. GRANT, Esq., Officiating District Engineer, Tinnevely, to Lieutenant-Colonel J. MULLINS, R.E., Chief Engineer for Irrigation, dated Camp at Ambasanudram, 6th November 1875, No. 99.

I HAVE the honor to forward, for sanction, an estimate of Rupees 170 for constructing an apron to the surplus weir of Marathony Periakulam Tank in Sunkerninarcovil Taluq. More than one year's revenue having been spent on the tank in the last five years, this estimate cannot be sanctioned locally.

1 Estimate.
1 Plan.

2. From the plan it will be seen that the scour through the vents has dangerously scooped out the soft rock in rear of the weir and that protection is necessary.

3. The estimate provides for filling in the hollow with earth and rough stone, and laying over that a rough stone apron 1 foot 6 inches thick with a rear retaining wall.

SUBMITTED to Government.

2. The filling in under the aprons should consist of small stone or clean gravel rather than earth. The outer apron had better extend to the ends of the rear wing returns, unless the rock on which the latter is founded be harder than that which has been washed away.

3. No provision appears to have been made in the estimate for the rough (dry) stone apron beyond the retaining wall. Its width is $7\frac{1}{2}$ feet and the length about $67\frac{1}{2}$, say 22 yards. The cost will be $23 \times 22\frac{1}{2} \times \frac{1}{2}$ at $1\frac{1}{2}$ Rupees, say, with sundries, 50 Rupees, making the total 220 Rupees.

(Signed) JOHN MULLINS, Lieut.-Colonel, R.E.,
Chief Engineer for Irrigation.

No. 594. ORDER THEREON, 26th November 1875, No. 3,380.

IRRIGATION, No. 56.

Account.

The estimate of Rupees 220 for repairing the escape of the Marathony large tank is sanctioned.

(True Extract.)

Major-General, R.E.,
Secretary to Government.

To the District Engineer, Tinnevely.
.. Controller of Public Works Accounts.
.. Chief Engineer for Irrigation.
.. Collector of Tinnevely.
.. Revenue Department.

Exd. S. T. Austin.

Spare Copies

No 1358

clause 3.

Submitted to Government.

The filling in under the aprons should consist of small stones or clean gravel rather than earth. The outer apron had better extend to the ends of the rear wing returns unless the rock on which the latter is founded be harder than that which has been washed away.

No provision appears to have been made in the estimate for the rough (dry) stone apron beyond the retaining wall. Its width is $7\frac{1}{2}$ feet and the length about $67\frac{1}{2}$ say 22 yards. The cost will be $22 \times 2\frac{1}{2} \times 2$ at 12 Rupees, say with sundries, 50 Rupees making the total 220 Rupees.

imp. at
amethur
November 1875

Colonel Sir L. L. L.
Chief Engr. for Irrigation

To,
The Secretary to Government
P. W. D.

P. W. 1895 Dept.
No: 7465

From

The Chief Engr.
for Irrigation.

Dated 16 Nov. 1895.
Recd 22nd Nov 1895.

No: 1358.

Submitting letter
of the St. Engr. Tim-
mally forwarding an order
of Rs. 220 for repairing
the escape of the Mara-
thony large tank.

No: 593

G.O. No 3380. 26. 11. 75.

No 3380

Pro: of the Madras Govt.
Under date the 26 Nov 1895.

Read the following:-

From

The Chief Engineer
for Irrigation

(H. E. 18958 of 16 Nov 1895)

The estimate of Rs. 220 for repairing the escape of the Marathony large tank is sanctioned.

16/11

[Signature]

54/6

To The District Engineer
Controller of P.W. Accounts
Chief Engr. for Irrigation
Collector of Timmally
Rev. Secy.

with 3 Enclosures

Despd- 2-12-75

H. E. Lacey

13/1/1974

3322

Box 573-574

Marathon, Long Creek.
Mineral District. The
estimate of P. 226 for
repairing the escape of
the ~~main~~, constructed.

55373/94

Ch. 27 - 25