

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE

Government of Madras

Public Works

DEPARTMENT

G.O. No.	3565	Press
B.P. No.		Mis.
Dated	20-12-	1875-195-

original

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
20th December 1875.*

Read the following papers :—

No. 333. From Lieutenant-Colonel J. F. FISCHER, R.E., District Engineer of Madura, to Colonel G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Madura, 14th July 1875, No. 1,423.

I HAVE the honor to submit, for the sanction of Government, the accompanying plan and estimate of Rupees 375 for enlarging and improving the Sub-Registrar's office at Tiroomungalum.

1 Estimate of Rupees 375.
1 Plan.

2. The plan and estimate have been countersigned by the Registrar of Madura and Registrar-General at Madras in token of their approval.

3. Out of the Budget allotment of Rupees 400 for Minor New Works (Civil Buildings, Provincial,) there remains an unappropriated balance of but Rupees 80, but funds for the above service can be met from the provision in the Budget of Rs. 555 for record racks in the Dindigul Range, which is not required for the same, as the Sub-Collector, Madura, has stated in his letter No. 311, dated 4th August 1874, that the record racks B to G would provide ample accommodation for taluq records for many years to come, and that he would therefore recommend that the big record rack A might be delayed until it might be really required.

No. 333-A. From District Engineer, Madura, dated 7th December 1875, No. 3,616.

No. 334. ORDER THEREON, 20th December 1875, No. 3,565.

CIVIL WORKS, No. 19.

THE estimate is sanctioned, and funds have been provided in G.O., No. 3,378, of 26th November 1875. The amount of the estimate for record racks, sanctioned in G.O., No. 658, of 29th May 1874, is reduced from Rupees 730 to Rupees 430.

(True Extract.)

Major-General, R.E.,
Secretary to Government.

To the District Engineer, Madura, with Plans.
„ Controller of Public Works Accounts.
„ Financial Department.

Exd. S. T. Austin.
Spare Copies

No 3618

District Engineer's office
Madurai 7th December 1875.

From,

Lieut: Coll: J. F. Fischer R.E.

To,

District Engineer, Madurai.

Major: General: G. W. Walker R.E.

Secretary to Government

P. W. D.,

Madras.

Sir,

With reference to your Memo
No 726 under date the 17th ultimo, I have
the honor to return herewith the sanctioned
Plan and estimate of Rs 730 for construc-
-ing and improving the Record Rocks
in the Lalug Cutcherry at Diindigul.

I have the honor to be

Sir

Your most obedt servt

W. F. Fischer R.E.

District Engineer

Encls: Vug 4
1. detailed and
Abstract Est.
2. specification
3. sheets of Plans.

DOCUMENTS IN FILE.

from District Engineer *Madura*

1 Covering letter No. *112* date *16/2/11*

~~1 Letter from Range Officer, No. , date~~

~~1 Detailed Estimate~~

~~1 Abstract, No. , date~~

~~1 Plan~~

~~1 Specification Report~~

~~From Office~~

Original sanction, No. , date
for detailed estimate preparation.

Orders and Proceedings.	No.	Date.	Under P. W. D. . G. O.	
			No.	Date.
P. W. Department	...			
Public do.	...			
Revenue do.	...			
Financial do.	...			
Military do.	...			

P. W. 1875 28/6/11
From No 7882
The District Engineer
Madura
To
The Secretary to Govt.
P. W. D.
G.O. No 3665. 20.12.10
Dated 3rd December/10
Recd 16/1
No 5 x No: 2616.
Deputy's Secretary
of the Second Rank
of the District Engineer
Madura
1 plan 1 Red 5th
1 sanction 3 28/11

Chgo { 7882
4630

~~2008/2009~~

10/11/19

[illegible]

The estimate is sometimes
funds may be appropriated
from the anticipated
savings referred to by the
D.C.

Adel

Adel

Adel

Adel

Adel

Adel

Adel

Adel

Adel

Adel

Adel

Adel

Adel

Proceedings of the Madras Government
Under date the 1875
Read the following

Yours

The D.C. Madura - (H.C. No. 1423 of 14th July 1879)

The Estimate is sanctioned; and funds may be appropriated from the anticipated saving referred to by the District Engineer.

Handwritten: The B.C.M. Club

11/20/20

- *Phyllanthus* *sp.* *sp.*
 - *Phyllanthus* *sp.* *sp.*

1950

11-59:

Case 7882
14/12

New Works

M. 7882/3/75 Civil

Detailed Estimate No. for 1873-74

Works

Dindigul Talooq Madura District

Preparing Research Pocks for use in the Talooq Kutcherry at Dindigul.

Particulars	No.	Measurements of feet			Contents
		L	B	D	
<u>Rack A</u>					
Principal Posts	8	17	7/2	7/2	3 1/2
Cross braces	28	1	7/3	7/3	12 2/3
Longitudinal braces	42	7/3	7/3	7/3	31 2/3
Total Cft. of wood					80 2/3
Planks for shelving	7	2 1/2	4	7/8	7 1/2
Total Cft. of Planking					7 1/2
8 (1 foot dia x 6") cut granite rest stones	8				
Iron nails 7" long	Total No. 72 doz.				140
<u>Rack B</u>					
Principal Posts	7	11	7/3	7/3	8 5/9
Cross braces	18	2 1/2	7/4	7/4	2 7/16
Longitudinal braces	12	6	7/4	7/4	4 1/2
Do	6	3 1/4	7/4	7/4	1 7/32
Total Cft. of wood					17 25/32
Planks for shelving	6	9 1/4	2 1/2	7/8	17 1/32
Total Cft. of Planking					17 3/32
Cut granite rest stones No. 7	7 (1 ft. dia x 6")				
Iron nails 5" long, Total No. 7 doz.	84				
<u>Rack C</u>					
Principal Posts	6	11	7/3	7/3	7 1/3
Cross braces	18	2 1/2	7/4	7/4	2 7/16
Longitudinal braces	24	5	7/4	7/4	7 1/2
Total Cft. wood					17 1/8

Planks for shelving	6	10	2 1/2	1/8	18 3/4
Total Cft. Planking					18 3/4
Cut Granite rest stones No. 6	6	(1 ft. dia x 6")			
Iron nails 5" long No. 7 doz	84				
<u>Rack D</u>					
Principal Posts	12	11	1/3	1/3	11 2/3
Cross braces	12	2 1/2	1/4	1/4	6 7/16
Longitudinal braces	6	6	1/4	1/4	2 1/4
D:	6	3 1/2	1/4	1/4	1 5/16
D:	2 1/2	1 1/2	1/4	1/4	6 3/4
D:	6	3 1/2	1/4	1/4	1 5/16
D:	4	1	1/4	1/4	3/8
Total Cft. wood					33 1/8
Planks for shelving	6	18 1/2	2 1/2	1/8	34 7/16
Total Cft. Planking					34 7/16
Cut stone rest	12	(1 ft. dia x 6")			
No. doz 15 Iron nails 5" long	180				
<u>Racks E & F</u>					
Principal Posts	8	11	1/3	1/3	9 1/9
Cross braces	24	2 1/2	1/4	1/4	3 3/4
Longitudinal braces	24	8	1/4	1/4	12
Total Cft. Wood					25 3/8
Planks for shelving	12	8	2 1/2	1/8	30
Total Cft. Planking					30
Cut Granite rest stones	8				
No. 8 doz Iron nails 5"	96				
<u>Rack E</u>					
Principal Posts	6	11	1/3	1/3	7 1/3
Cross braces	12	2 1/2	1/4	1/4	1 7/8
Longitudinal braces	6	3 1/2	1/4	1/4	1 5/16
D:	6	3 1/4	1/4	1/4	1 1/32
Total Cft. wood					11 7/8
Planks for shelving	6	4 1/4	2 1/2	1/8	7 3/8
Total Planking					7 3/8
Cut Granite rest stone No	6				
5 1/2 doz Iron nail 5" long					66

M. 7882/75

Abstract Estimate for Record Racks for use in
 P. B. Salong Lutcherry at Dindigul
 Valuation Rs 10,000 - Date of last repairs July 1869/70

Quantity	Particulars	Rate	Per	Amount	Total
<u>Rack A</u>					
80 2/3	lft. of wood	2	..	lft. 161 5 1/4	
77	Planking	1	12	..	134 12
8	Cut Granite rest stones inclusive of fixing	..	6	each 3	..
12	Dozens of Iron nails 7" long	..	5	Doz 3 12	302 13 1/4
<u>Rack B</u>					
17 2/5	lft. of wood	2	..	lft. 34 2 9/16	
17 3/8	Planking	1	12	..	30 5 7/8
7	Cut Granite rest stones inclusive of fixing	..	6	each 2 10	..
7	Dozens of Iron nails 5" long	..	4	Doz 1 12	68 16 1/4
<u>Rack C</u>					
17 1/8	Cft. of wood	2	..	lft. 35 4 8 1/16	
18 3/4	Planking	1	12	..	32 13
6	Cut Granite rest stones inclusive of fixing	..	6	each 2 4	..
7	Dozens of Iron nails 5" long	..	4	Doz 1 12	72 1 8
<u>Rack D</u>					
33 1/8	lft. of wood	2	..	lft. 66 7 4	
34 1/16	Planking	1	12	..	60 11 3
12	Cut Granite rest stones inclusive of fixing	..	6	each 4 8	..
15	Dozens of Iron nail 5" long	..	4	Doz 3 12	135 6 7
<u>Rack E & F</u>					
25 3/8	lft. of wood	2	..	lft. 51	.. 11

Carried over 51 .. 11

Mr. 1882/75

Specifications for Ruado. Racks proposed 13
for the Salog butchery at Dindigul

The wood used will be of the best description
of jungle wood, procurable in the locality &
must be well seasoned

The principal rack marked A will
consist of the number of posts, Cross braces &
longitudinal braces specified in Estimate & shown
in Plan. These cross & longitudinal braces will
form mortice and tenon joints with the posts,
to be further secured by nails.

The remaining racks will be of smaller
dimension as specified in Estimate & shown in
Plan the above remarks applying to these as well.

All dimensions in Plans & Estimates to be
strictly adhered to -

[Signed] E. M. Gill
Sdg. Officer

Mr. Kumbhkarth
Executive Engineer
In charge of 2nd Range

30	Left of Planting	7	15	4	51	11			
8	Cut granite rest stones inclusive of paving	-	6	each	3	-			
8	Dozens of Iron Nails 5"	-	1	doz	2	-	108	8	1
11 1/2	Left of wood <u>Rack B.</u>	2	-	4 1/2	23	8			
7 3/4	Left of Planting	1	12	-	13	15	1		
6	Cut granite rest stones inclusive of paving	-	6	each	2	1			
5 1/2	Dozens of Iron Nails 5" long	-	1	doz	1	6	41	-	9
Sundries							738	13	1
Total amount of Estimate, Rs.							730	-	-

[Signed] E. M. Gill
Sdg. Officer

Dindigul
2nd April 1874

Mr. Kumbhkarth
Executive Engineer
In charge of 2nd Range

Mr. Subbar
Collector
Dindigul
District Engineer

District *Madurai Taluk Tencaimangalam*

Work

Enlarging and improving Sub Registrars Office at Tencaimangalam.

Particulars of work.	Measurements in feet and inches.			Contents.
	Length.	Depth or Height.	Breadth or Thickness.	
1	2	3	4	5
<i>Removing Old Works</i>				
Parapet wall over Terrace	17	1	2 1/2	42 1/2
Portion of Terrace under parapet wall below	15 1/2	1 1/2	1	34
Slope terrace over Veranda	18	9 1/2	1	171
Side and End walls of small room	12 3/4	3/4	6	57 3/8
Remove wall for new Window ways in Side Wall	2 1/2	1 1/2	5	30
Total Cft. of removing Old Masonry work				567 3/8
Being Equal to Cft.				21
<i>Foundation</i>				
Front Wall	16 1/2	2 1/2	3	123 3/4
Portion of Side Wall	4	2 1/2	3	30
Total Cft. of Foundation in house				153 3/4
Being Equal to Cft.				5 2/3
<i>Brick in house</i>				
Basement to front wall including with old work	17	2	3/4	25 1/2
Do to Side Wall	5	2	3/4	7 1/2
Front wall above	17	1 1/2	10	255
Side Wall above	5 1/2	1 1/2	10	82 1/2
High Side Wall (over gate) Do	7	1 1/2	2 1/4	23 5/8
Parapet Wall over terrace on 3 sides	30	1	2 1/2	75
Block up Window way in rear wall	4	1 1/2	5	30

*At a district District**2nd or District**Madurai No 1915/75**11/18 82 1/2**Estimate for construction of building & improving the Record Books in the District Registry at Brindigan -*

75

*Enclaves. No 2 in a. latter from the District Engineer Madurai to the Secretary to Government. dated 11/11/75.**16/10/74.**11/11/75**Estimate for construction of building & improving the Record Books in the District Registry at Brindigan**Estimate No 1915/75*

Block up doorway in side wall	4	12	6 1/2	39
Total Cft of Brick in Chumau				538 1/8
Window way	2 x 3	1 1/2	4	36
Doorway in front	3	1 1/2	6	27
Total Cft of Brick in Chumau				63
Being Equal to 17 5/8				17 5/8
Over front part	18	8 1/2	3/4	114 3/4
Total Cft of tiling with brick on				
2 courses of flat tiles 3" thick				
to top of ceiling				
Being Equal to 11 1/4				11 1/4
Being Equal to 4 1/4				4 1/4
Joists	17	1	1 1/2	22 3/8
Total Cft of Sangan wood tongue & groove	11 x 6 1/2	2	1/3	11 5/6
including 2 coats of red paint				34 1/3
Corrue Work around in front	33	"	"	33
Total summing of Corrue Work including 2 coats of plastering with Chumau				33
Plastering				
Basement of front wall	18 1/2	"	1	18 1/2
Do above	18	"	10	180
Side Wall above	7	"	10	70
Suberior				
Front Wall	15 1/2	"	10	155
Side Wall	5	"	10	50
Traces of walls below beam	2 x 2	"	10	40
Right side wall above	6 1/2	"	4 1/2	29 1/4
Both Sides of Window way blacking	8	"	5	40
Do Doorway	8	"	7	56
Top Sides and Bottom of New Window way	2 x 16	"	2 1/4	72
Parapet wall over beam	30	"	6	180
Total Sqrft of Plastering with 2 coats of Chumau				890 3/4
Being Equal to 8				8

Particulars of work.	Measurements.			Cubic Contents.
	Length	Breadth	Height	
1	2	3	4	5
Flooring	15	15	1/4	56 1/4
Total Cft of flooring with Concrete in Chumau well rammed down & plaster over				56 1/4
Being Equal to 2 1/2				2 1/2
1. Pair of Panelled Door with frames & (old) 3 x 6				
4. Do. 2 Windows with frames with Shutter iron bars & 2 old & 2 new 3 x 4				
2. Lat Ventilators				
2. stone slabs to be placed under end of beam each 1 1/4 x 1 1/4 x 3/4				
1. step stone in bed of Concrete 9" deep 5 x 1 x 3/4				

Eulandigt in fröjlig behållning

345

provides for every thing

necessary, and that no Supplementary works will afterwards be required.

P. Pain Con
9/6/75 Defⁿ

[Signature]
Lieut. J. E.
Range Officer

[illegible]

Dear Mr. Webb
 I have the pleasure
 to acknowledge the
 receipt of your letter
 of the 10th inst. and
 in reply to inform
 you that the same
 has been forwarded
 to the proper
 authorities for their
 consideration. I am,
 Sir, very respectfully,
 Yours,
 J. W. Webb

1794 Dec 1
1795
Admission to the 375
of the 1795
of the 1795

Madison 14 July 1875

1872

From ... 23

Lieutenant Colonel J. G. Fisher C.E.

Deputy Engineer of Ordnance

Sept. 1944

Colonel G. W. Walker &c.

Secretary to Government D. W. Adams

1000

I have the honor to subscribe

Encls: 2 - The British Govt. the accm.

Substrate of

Ch 375 - *Springing* - *Hard* - *Historical* - *1-1-1*
 Plan - *1-1-1* - *the sub* - *Res*

enlarging and improving the

transferred at Trincomalee.

The Plan Rotinaks have been

Countersigned by the Registrar of Marine

and Regular General at Meadus in

tokens of their approval.

Out of the Budget allotment of

Rs 400 for minor new works (Civil Buildg.)

Provincial) there remains an unapportioned

• appropriated balance of net cash, net sum

for

Madam

[illegible]

D. W. 1875 ^{no 1423} Sept.

From No: 4630

The District Engineer
Madras

To

The Secretary to Govern-
ment
Madras

Charg's No 726 d/17-11-75

Dated 14th 3 July 1875
Recd 17 3 July 1875

Encls: 2
* 1 Plan rel'd to 8th Dec 75
Submits for sanction
the Plan & Estimate of Rs
375 for enlarging & im-
proving the Sub. Registrar
Office at Tenoomungalam

G.O. No 3565. 20-12-75

Cin/4-12-75

No 726

Op. 14/30

Letter from the District Engineer Madras
No 1423 of 14th July 1875.

The District Engineer Madras is
requested like so good as to return the
plan and Estimate for the Record Books
in the Salugutcherry at Prindigul which
were returned to him as requested in
his letter No. 1396 dated 7th July 1875.
(By Order)

For A. George, Supt. Ad. L. Scott Major R.
Under Secy to Govt.
17th Nov 1875

To The District Engineer
Madras

to above services can be met from

No. 3565

Subd. of 10/11/1875

Public Works Dept.

Proceedings of the Madras Government.

Order date the 20 Dec: 1875

Read the following

From

The District Engineer
Madura

(H.E. No 1423 of 14 July 1875
" 3616 of 7 Dec 75)

The Estimate is

sanctioned; and

funds have been

provided in G.O.

No 3378 of 26 Nov: 1875

The amount of the

estimate for Record

Racko, sanctioned

in G.O. No 688 of

29 May 1874 is reduced

Dist. Eng: Madura.
with plans. 6

from Rs 430 to Rs 400.

Controller P.W. Accounts. S

Financial Department
Plan & section of Pub. Regio. Office
at Tirumangalam showing the

7 drops - 7-1-76

4-12-75

7-0-1081200

3812th June/74 to 145 hrs
26th Nov/75 .. 589-590
Memo: to 7269/75 Nov/75

alterations & additions proposed
Plan - Interior of Record Room
showing future of Record
Racks.
Sections of Record Racks
improved

25/9/75
28/8/75
31

Govt. of 1875 Madras.
PUBLIC WORKS.

To J. G. Madras

21/12

Dated

Issued

Recd.

Encl.

G. O., 20th Dec 1875. No. 3545

Mos. 333/24

Est. Registrar's Office at
Provincial, Madras
Est. — Estimate of
Rs 375 for Enlargement
— Province — Sanctioned
— ed with remarks.