

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No. 1291 (W)	Press
B.P. No.	Mis.
Dated 5-6 -	1876.

Not to be folded or roughly handled

11

*Proceedings of the Madras Government, Public Works Department,
5th June 1876.*

No. 69. Read the following letter from Lieutenant-Colonel R. F. OAKES, R.E.,
Superintending Engineer, Tanjore, to Major-General G. W. WALKER, R.E.,
Secretary to Government, Public Works Department, dated Tanjore, 28th
April 1876, No. 704 :—

As the work marginally noted is one of the salt works transferred to the Imperial

1 Plan.
1 Sketch.
1 Estimate.
Constructing 1 Head Constable's and fourteen
Constables' Huts at Adrampatam, Rs. 7,950.
* Letter No. 2,142.

Public Works Budget of 1876-77 in G.O.,
No. 569, dated 3rd March 1876, and as it
was found that an estimate for the same,
amounting to Rupees 7,950, had been
forwarded from this office to the Collector
on the 30th November 1874,* a reference

was made to that officer on the subject, on the receipt of the above Government Order.
The Collector in his reply, dated the 10th instant, has returned the plans and estimate
countersigned in token of his approval, with a request that they may be submitted for the
sanction of Government. I have the honor, therefore, to submit herewith the plans and
estimate in question, and to solicit early sanction for the same, to admit of the work
being commenced during the present working season.

No. 70.

ORDER THEREON, 5th June 1876, No. 1,391.

CIVIL WORKS, No. 9.

(a) Heads of Service.—Imperial.
Fund.—Ordinary.
Class.—Original Works.
Main-head.—Other Services.
Sub-head.—Civil Buildings—D Salt Department.
Section.—ii Huts (Preventive Service).
Name of Work.—One Head Constable and fourteen
Constables' huts for Salt Police at Adrampatam.
Amount.—Rupees 7,950.
To be carried out by the Public Works Department.

* G.O., No. 1,022, dated 24th April 1876.

(True Extract.)

THE estimate, amounting to Rupees
7,950, is sanctioned for immediate execution.
An allotment to the full extent has been
provided in the Salt Budget* of the current
year.

The above sanction has been registered
as Imperial No. 33 W. of 1876-77.

Colonel,
Offg. Under Secy. to Govt., P.W.D.

To the District Engineer, Tanjore.
" Examiner of Public Works Accounts.
" Revenue Department.

Exd. S. T. Austin.
Spare Copies

Provincial
Tanjore District
No 4 or Manargoody Range
Puttu Kottai Taluk
Original Works Civil Building
Salt Department

Huts - Police
 Work - Constructing 1 Head Constable Hut and 14
 Constable Huts in two blocks, for the Salt Police
 at Adirampatnam.
To be executed by the Public Works Department

Quantity Description of Charges Rate per Amount Total

Head Constables Hut

Concrete

526½ Total Cubic ft. Concrete 2.00 6513.1

Brick work

2718 Total

72½ Total Deduction

2645½ Cubic ft. Brick in Chambers 23.00 372.2

Plastering

1991¾ Total

96¾ Total Deduction

1895 Sq ft. of Plastering 28.00 476.0

Wood work

5¾ Cubic ft. of Country wood

Swrought and put up 14.00 73.0

Roofing

530¾ Total Roofing with Palmyrah
 rafters, keepers, collar pieces
 and two Courses of pan tiles 18.00 9586.0

Carried over - 587148

This estimate has been
 prepared for Rs. 7950 & 1/2
 as per order No. 33 of 1896-97.

Flooring

B. Forward-587 14 8

114 1/8
4 42/216
Flooring Cubic yards with
refuse Bricks soaked and
well rammed and lastly
rubbed smooth with a
wet Brick
2 Doors (batten) (3 x 6 1/2) 8 . Cyp 219
1 Windows (D°) (2 1/2 x 3 1/2) 15 . . each 30 . .
10 . . 50 10 . .
630 . 5
Excavation and sundries 19 15 7
Total Estimate for Head Constable hut 650 . .

Estimate for 14 Constables Huts

2700 3/4
Total Cubic ft. Concrete 2 . Cft 712 96
28820 7/16
630
Total Deduction
28190 7/16
342 1/2
Cubic ft. bricks in Chumam 23 Cft 3964 4 5
Honey Comb work above wall 6 . . Lps 20 2 2

Plastering

19549 1/2
840
Total Deduction
18709 1/2
Sqr ft. of Plastering 28 . . Lps 467 8

Wood work

56 25/32
Cubic ft. Country wood wrought
and put up 14 . Cft 70 6 11

Roofing

717 1/2
Total Roofing with Palmyrah
rafters, keepers, collar pieces
and 2 Course of pan tiles 18 . . Lps 129 15 2

Flooring

1362 17/16
50 205/432
Total flooring Cubic yards
Carried over-71778 3
7176 14 2

with refuse Bricks soaked
and well rammed & lastly
rubbed smooth with a wet
brick

14 Doors (batten) (3 x 6) 8 . Cyp 25 39
28 Windows (batten) (2 x 3) 15 . . each 210 . .
8 . . 50 224 . .

Excavating foundation and
sundries 113 14 1
7750 . .

Compensation for land
near Throvepathy unmen
Covil 200 . .

Total Estimate Rs for 1
Head Constable and 14 Constable
Huts 7950 . .

Supts Engrs office } (signed) W. Leggatt A.I.C.E.
Jaipore
30 November 1874 } Executive Engineer in charge
Supts Engrs Office, Jaipore

(signed) H. J. Thomas
Collector.

H. F. Tate
Supt. Engineer Jaipore

P. N. 3144/46

Abstract estimate
of Rs. 7950 for con-
struction of 180 Conical
Pier Conical Piers
at A. B. C. Piers

Enclosure in a letter
from the Deputy Engineer
Dumaine to the Secretary
to Govt. No. 701 dated
25 April 1876.

No. 704.

Superintending Engineer's Office
Dumaine 28 April 1876

From
Lieut Colonel R. F. Coker M.
Superintending Engineer Dumaine

To
Major General E. W. Walker M.
Secretary to Government P.W.D.

Sir,

As the work marginally
noted is one of the Salt works trans-
ferred to the Imperial
Public Works Budget
of 1876-77 in G.O. No. 569.
dated 3rd March 1876, and
as it was found that an estimate
for the same amounting to Rs. 7950
had been forwarded from this
Office to the Collector on the 30th
November 1874, a reference was
made to that Officer on the subject,
on the receipt of the above G.O.
The Collector, in his reply dated
the 10th instant, has returned
the Plans and Estimate con-
signed in token of his approval
with

with a request that they may be submitted for the sanction of Government. I have the honor, therefore, to submit herewith the Plans and Estimate in question, and to solicit early sanction for the same, to admit of the work being commenced during the present working season.

I have the honor to be
 Sir
 Your most obedient servant
 W. F. Baker Esq. (C. 118)
 Deputy Engineer, Bangalore.

G.O. 3 March 76. No 509.
 24 April 76 - 1022.

1269
 C. 1-1-76 (M. 5/6/76)
 O.L. Dept. 63 May
 29/5/76
 Please intimate of
 Rs 7950 for constructing
 140 Constables' huts at
 Adraipattana

To the Secretary, Govt.
 No 28 April 1876
 No 2 May
 The Deputy Engineer
 Bangalore
 No 704

(a) Heads of Service—*Imperial*
 Fund. *ordinary*
 Class. *original Works*
 Main-head. *Other Services*
 Sub-head. *Civil Buildings & Salt Deptt*
 Section—*Huts (Preventive Service)*
 Name of Work. *One Head Constable & fourteen Constables' huts for Salt Police at Adraipattana.*

Amount. *Rs 7950*
 To be carried out by the *P. M.* Department.
 Printed in the margin of G.O. No 1041 of 6 June 1876—

No 1391

Public Works Department.

PROCEEDINGS of the MADRAS GOVERNMENT.

UNDER date the 5th June 76

READ the following:—

From

The Sup^r Eng^r Tanjore (H.E. No. 7014 of 28th April 76)

The Estimate amounting to Rs 7,950 is sanctioned for immediate execution. An allotment to the full extent has been provided in the Salt Budget of the current year.

G.O. 1022 of 24th April 1876.

The above sanction has been registered as Imperial No. 33 W. J. 1876-77.

D.C. Tanjore ✓
Encl^d P.W. Accts. ✓
Revenue Dept. ✓

Detd 17/6/76

Encl^d

31445

Govt. of 1876: Madras.

PUBLIC WORKS.

No. 10. C. Lajore

Page

Page

Page

C. C. 5th Division, No. 1391

No. 6-70

Constables Huts for the
Salt Police in the
Lajore District Estimate
of Rs 7950 for en-
-structing — Lajore —

Subm. 17-11-76