

- (1) Number of pages _____
 (2) Date of repair _____
 (3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No.	1418	(w) Press
B.P. No.		Mis.
Dated	7-6-	1876

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
7th June 1876.*

No. 117. Read the following letter from W. B. LEGGATT, Esq., A.I.C.E., Officiating District Engineer, Bellary, to Colonel W. T. F. FAREWELL, Officiating Deputy Chief Engineer and Under Secretary to Government, Public Works Department, dated Camp at Ramandroog, 12th May 1876, No. 488:—

ADVERTING to your memorandum, No. 147 of the 22nd January last, I have the honor to forward, for the early sanction of Government, a plan and two revised estimates amounting together to Rs. 1,745, accompanied by specifications and site plans, for the undermentioned works, in the Hospett Range of this district, viz.:—

	Rs.
I.—For constructing an Overseer's Office and Store-room at Ramandroog of Hospett taluq	875
II.—For constructing an Overseer's Office and Store-room at Humpsagur of Hudgully taluq	870
Total ...	1,745

2. I beg to state that the above estimates have been carefully revised with reference to the instructions contained in the memorandum under reply, thus a reduction of Rupees 350 has been effected on the original amount (Rupees 2,095).

3. I further beg to add that, as stated in my letter to the Secretary to Government, Public Works Department, No. 1,238, dated 2nd September 1875, these buildings are urgently required.

Nos. 117 & 119. ORDER THEREON, 7th June 1876, No. 1,418.

CIVIL WORKS, No. 18.

(a) *Heads of Service.*—Provincial.
Fund.—Ordinary.
Class.—Original Works.
Main-head.—Civil Buildings.
Sub-head.—D. Public Works Department.
Section.—i Offices.
Name of Work.—No. 56 W. Overseer's Office at Ramandroog ... 875
 No. 57 W. do. do. at Humpsagur ... 870
 To be carried out by the Public Works Department.

HIS GRACE the Governor in Council sanctions the estimates of Rupees 875 and 870 respectively, submitted with the above letter, for constructing offices for the use of Overseers at Ramandroog and Humpsagur.

2. These sanctions have been registered as Provincial Nos. 56 and 57 W. of 1876-77.

(True Extract.)

Colonel,
Offg. Under Secy. to Govt., P.W.D.

To the District Engineer, Bellary.
 „ Examiner of Public Works Accounts.

Exd. S. T. Austin.
 Spare Copies

Report to accompany the Estimate for
Constructing an Overseer's Office and Store room
at Gampasagra.

Amount of Estimate Rupees 270 only.

The building to be constructed in strict
accordance with the accompanying Plan.

Foundations & Basement. The foundations of all walls to be 3 feet
deep & 2' 6" broad. Above the foundations the basement
to be 2 feet high & 2 feet thick.

The foundations & basement of verandah
will be of the same depth & height as those for the
main walls but will be 6" less in thickness in
both cases.

Superstructure. The building will consist of two rooms
each 12' x 12' with a verandah 7' 9" wide at one
end.

The walls will be 1 1/2' thick & 12' high up to
gables & these will be 4 feet high.

Flooring. The flooring will consist of stone jelly
in clay, the level of the ground being brought up
to that of basement with the earth taken out of
the foundations.

Slabs for steps
& lintels. There will be 3 steps each 1 foot tread
& 6" rise at the entrance, the slabs forming them
being

being 4 feet long & 1.6 broad over the two doors and windows granite slabs 6" thick & 1 1/2' broad will be laid to form lintels; these slabs will be 9' longer on each side than the doors & windows over which they are laid.

The roof over the rooms will be composed of palmyrah rafters 18" apart from centre to centre, the rafters being 10 1/2' feet long (four only to be cut from one palmyrah) will be laid on a ridge pole running over the gables.

This frame work will be covered with 1 course of flat & 2 of pan tiles with rafter & chumam borders in the usual way.

A wall plate 4" broad & 2" thick will be laid on the walls which carry the rafters.

The verandah roof will be of the same description as for rooms.

The roof will be supported by a full palmyrah bresummer 15 feet long, the latter being carried upon two stone pillars 1.6" square & 5 1/2' feet high.

The palmyrah work to be turned before fixing.

Pointing

All the exposed surface of masonry will be pointed with chumam.

Doors & windows.

One door batten 3 1/2' x 7' & one shutter door 7' x 3' also four windows with batten shutters will be provided with locks hinges & bolts.

Complete and fixed in the positions shown in the Plan.

Forsett Range Office
6 May - 1896

H. F. Smith
Range Officer

Report to accompany the Estimate for
Constructing an armour's office and store room at
Ramandroy.

Amount of Estimate Rs 880 only
The building to be constructed in strict
accordance with the accompanying Plan.

Foundations & Basement. The foundations of all walls to be 3 feet
deep & 2 1/2 feet broad. Above the foundations the basement
to be 2 feet high & 2 feet thick.

The foundations & basement of verandah
will be of the same depth & height as those for the
main walls but will be 1 foot less in thickness in
both cases.

Superstructure. The building will consist of two rooms
each 12x12, with a verandah 7-9 wide at one
end.

The walls will be 1-6 thick & 12 feet high
up to gables & these will be 4 feet high.

Flooring. The flooring will consist of stone jelly
in clay, the level of the ground being brought
up to that of basement with the earth taken
out of the foundations.

Slabs for steps
& lintels. There will be 3 steps each 1 foot broad
and

P. N. 3528/76

Belong District
Fort St. George
From
1876-77
The Officer in charge
of Fort St. George
The District Engineer
Battery
Dated 15th May 1876.
Received
Amount of Estimate Rs 880
Report to accompany
the Estimate for building
an armour's office and
store room at Ramandroy.

and 6' rise at the entrance the slabs forming them being 4' long & 1-6' broad over the two doors and windows granite slabs 6" thick & 1-6' broad will be laid to form lintels, these slabs will be 9" longer on each side than the doors & windows over which they are laid.

The roof over the rooms will be composed of palmyrah rafters 18" apart from centre to centre the rafters being 10 1/2' long four only to be cut from one palmyrah will be laid on a ridge pole running over the gables.

This frame work will be covered with 1 course of flat & 2 of palm leaves with proper & chumam borders in the usual way.

A wall plate 4' broad & 2" thick will be laid on the walls which carry the rafters.

The verandah roof will be of the same description as for rooms.

This roof will be supported by a full palmyrah tree trunk 6' long.

Roof

this is the plan

the latter being carried upon two stone pillars 1-6' square & 5 1/2' feet high.

The palmyrah work to be tarred before fixing.

Pointing

All the exposed surface of masonry will be pointed with chumam.

Doors & windows

One door batten 3/4 x 7' & one batten door 7' x 5' also four windows with batten shutters will be provided with locks hinges & bolts complete and fixed in the positions shown in the Plan.

Forsett Range Office
1st May 1876

Wm. Sheld
Range Officer

Commercial Bank

District Bellary Taluk Gospett Village Ramandooz
 Work Constructing surveyor's office & store room at Ramandooz

<i>Amount of Estimate Refused</i>					\$800.00
-----------------------------------	--	--	--	--	----------

27 Proclaimed
 Range Officer
 (I.S.C.E.)
 M. J. P.
 Off. L. B. T. Inquest W. H. H.

1

Walling District
Forest Range

new work

7 Provincial Civil Building

ABSTRACT- ESTIMATE.

District Bellary Talook Kadagully Village Kumpasagra
Work Constructing an overser's office & store room at Kumpasagra

Quantities.	Description of Work.	Rate.	Per.	Amount.	Amount of each part.
2967 Cft of	Rough stone in chumam	23	Cft	417 3 9	
60 Sq ^{ft} of	Slabs	16	Sft	5 10	
4 1/6 Sq ^{ft} of	Flooring with stone jelly in clay	3	Sq	12 8	
6 3/5 Sq ^{ft} of	Roofing with palm-yrak (rafters 10 1/2 long) piers, nail, ridge pole, & course of flat & 2 of plank & chumam borders complete including tarring the rafters &c	22	Sq	145 3 2	
7 3/4 Sq ^{ft} of	Roofing with palm-yrak (rafters 10 1/2 long) piers, nail, & 2 Course of plank &c including tarring the rafters &c	22	Sq	38 8	
25 Sq ^{ft} of	Pointing	1	Sq	37 0	
42 Cys ^{ft} of	Excavation & filling for Basement	3	Cys	7 14	
1	Batten door with frame 7x3	23	Each	23 0	
1	do do do 3 1/2 x 7	27	Each	27 0	
4	Windows with iron bars & Batten shutters 2x4	20	Each	82	
	Carriage from Bellary			7	
	Total			804 6 11	
	Sundries & Superintendent @ 5 per cent			40 9 1	
	Compensation for the land & register			25	
	1. of Bangalore Puri				870

To Field Range office & Mr. Dist. Inq. Natl. Range office

P. N. 3528/76
H

Bellary District

From, 1876-77.

The Officer
In charge - Hospett Range.

To,
District
The Superintending Engineer,
Bellary

Dated 6th May 1876.

Received.

Abstract Estimate amounting to
Rupees 870

for Constructing an
overseer's office and store
room at Hampapur.
Dominated
Civil Buildings
Department

Dist. Engineer's Office
Camp Ramandroog
12th May 1876.

10th 1888

From

The Offg. District Engineer
Bellary

To

The Offg. Deputy Chief Engineer
Under Secretary to Government
P.M.D.

Enclosures

Sir

- 1 Plan
2 Reports
2 Abstracts
2 Site plans

Adverting to your Memo No. 147
of the 22nd January last, I have the honor
to forward for the early sanction of
Government a Plan and two revised Es-
timates amounting together to Rs. 1745
accompanied by Specifications and Site
plans, for the undermentioned works, in
the Hospett Range of this District viz;

- i For Constructing an Overseer's
Office & Store room at Ha-
-mandroog of Hospett Ta-
-look } 875
 - ii For Constructing an Overseer's
Office & Store room at Him-
-nasagar of Hampapur Taluk } 870
- Total Rs. 1745

I beg to state that the above Estimates have been carefully revised with reference to the instructions contained in the Memo under reply, thus a reduction of Rs 350 has been effected on the original amount (Rs 2045).

I further beg to add that, as stated in my letter to the Secretary to Government P. W. D. No. 1238 dated 2nd September 1915, these buildings are urgently required.

I have the honor to be
Sir,
Your most Obedt. Servant
W. E. Wyatt A. S. C. E.
Off. Dist. Engineer
Bikaner

№ 3528

10

Fund.	Ordinary
Class.	Original Works
Main-head.	Civil Buildings
Sub-head.	L. Public Works Dept. Ramandhary-
Section -	i. Offices
Name of Work.	No 56 W. Overseer's office at Hoopett Rs. 870
	No 57 W. Do do at Hundagar - 870

To be carried out by the P. W. Department.

To be carried out by the P. H. Dep.
 Permit in the margin of G. O. No. 1418 of 7 June 1876--

117

cu-2/6/76 Peta 7/6/76
 Despatch 30-5-76. 19-6-76

No. 1418

civil works.

Public Works Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 7 June 76.

Read the following:—

From,

The D. Engr Bellary (M.E. No. 488 of 12th May 76)

His Grace the
Governor in Council
sanctions the estimates
of Rs 875 and 870 res-
pectively submitted
with the above letter
for constructing offices
for the use of Overseers
at ^{Ramandrag} ~~Coast~~ and
Kumpegar.

2. These sanctions
have been registered
as Provincial Nos
56 & 57 W of 1876-77.

J. L. Bellary
Secy. P. W. Dept.
Dated 17/6/76

30.5.76

352 8/11

Govt. of 1870 Madras.

PUBLIC WORKS.

To

The War and Eng. Bellary

Refer

Refer

Refer

G. O., 7th June 1870, No. 1418

No. 117-119

Offices for the use of
Overseers at Namandoo
and Hampasagur
Bellary Dist. Estimates
for constructing —
sanatoriums

2. 11. 1870
R. J. 1870
1870