

(1) Number of pages \_\_\_\_\_

(2) Date of repair \_\_\_\_\_

(3) Initials of the Referencer \_\_\_\_\_

# MADRAS RECORD OFFICE

## Government of Madras

*Public Works* DEPARTMENT

|          |       |     |       |
|----------|-------|-----|-------|
| G.O. No. | 1470  | (W) | Press |
| B.P. No. |       |     | Mis.  |
| Dated    | 13-6- |     | 1876. |

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,  
13th June 1876.*

Read the following letters:—

No. 219. From Major H. SMALLEY, R.E., Officiating District Engineer, Ganjam, to Major-General G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Camp at Cunchily, 4th March 1876, No. 68.

I HAVE the honor to submit herewith one plan and estimate for constructing a Police Station-house at Punditgam, Rupees 1,010, and estimate for improvements, &c., to Police Hospital at Russelcondah, Rupees 1,004, duly countersigned by the

1 Plan. } Police Station-house.  
1 Estimate. }  
1 Estimate for improvements to Police Hospital at Russelcondah.

Inspector-General of Police for sanction by Government.

2. Funds for the above works have been provided in the Police Budget for 1876-77, *vide* G.O., No. 3,610, dated 24th December 1875.

No. 220. From G. R. LEGGATT, Esq., C.E., Officiating District Engineer, Ganjam, to Colonel W. T. F. FAREWELL, Deputy Chief Engineer, Public Works Department, dated Ganjam, 14th May 1876, No. 18.

WITH reference to your memorandum, No. 617, dated the 3rd April 1876, I have the honor to report that the rates, as allowed in the last schedule of the Berhampore range for the items therein referred to, are as follow, *viz.*:—

|                                                             | RS. | A. | P. |
|-------------------------------------------------------------|-----|----|----|
| Brickwork per 100 cubic feet = Rs. 12, or per cubic yard... | 3   | 3  | 10 |
| Flat archwork per 100 " = " 15, " " ...                     | 4   | 0  | 9  |
| Iron doors per square foot ...                              | 1   | 2  | 0  |
| Asphalte square $\frac{1}{2}$ inch thick ...                | 24  | 8  | 0  |
| Batten doors per square foot ...                            | 0   | 12 | 0  |

The rates noted in your memorandum do not agree with the above and appear to have been taken from the schedule of the Chiccacole range. The only items which have exceeded the rates in the schedule are—

1. Iron doors.
2. Batten doors.

The price of iron has risen since the estimate was framed, and the village of Punditgam where the Station-house is proposed to be built is an out-of-the-way place where materials and labor have to be imported, and some allowance must therefore be made for extra rates. The rate allowed for batten doors 1 square foot has been exceeded by only Annas 1-4 and is absolutely necessary, the rate for iron having risen.

2. There has been no competent draughtsman in this office for some years, and all the endeavours that have been made to get one have been without avail, the salary being so low, *viz.*, Rupees 45, men will not come up to the remotest end of the Madras Presidency when they can get employment for the same salary in the Southern Districts.

The estimate has been corrected which with the plan are herewith retransmitted.

Proceedings of the Madras Government, Public Works Department,  
13th June 1876.

No. 221.

ORDER THEREON, 13th June 1876, No. 1,470.

CIVIL WORKS, No. 34.

(a) Heads of Service.—Provincial.  
Fund.—Ordinary.  
Class.—Original Works.  
Main-head.—Civil Buildings.  
Sub-head.—F. Police Department.  
Section.—ii, Stations.  
Name of Work.—Station-house at Punditgam.  
Amount.—Rupees 980.  
To be carried out by the Public Works Department.

Rupees 431 in G.O., Judicial Department,  
Public Works No. 63 of 9th May 1876.

the Inspector-General of Police to submit, through the Judicial Department, proposals for providing the additional sum of Rupees 401 required.

3. This sanction has been registered as Provincial No. 66 W. of 1876-77.

(True Extract.)

Offg. Under Secy. to Govt., P.W.D.

Colonel,

York - Abstract  
on construction of Police Station-house at

(a) Heads of Service—Provincial

Fund.

Ordinary

Class.

Original Works

Main-head.

Civil Buildings

Sub-head.

F. Police Dept.

Section.—ii, Stations

Name of Work.

Station-house at Punditgam.

Amount. Rs 980

To be carried out by the P.W. Department.

Print in the margin of G.O. No. 1470 of 13-6-76

6

at Fort Hall  
 York - Construction of Police Station House at  
 Pinditigan

| Quantity  | Description of work                                                                     | Per<br>unit | Rate  | Amount   | Total |
|-----------|-----------------------------------------------------------------------------------------|-------------|-------|----------|-------|
| 17 1/2    | Cyds of concrete at Foundations                                                         | cyd         | 1 8   | 25 10 8  |       |
| 43 27     | " of Rubble stone in do<br>and Basement                                                 | "           | 1 14  | 81 2 10  |       |
| 52 1/2    | " of Brickwork —                                                                        | "           | 2 12  | 137 11 0 |       |
| 3 1/4     | " of Plaster work —                                                                     | "           | 3 8   | 12 1 8   |       |
| 41 3 1/2  | Cft of preparation of<br>Basement steps in do                                           | Cft         | 8     | 207 1/2  |       |
| 4 9       | cyds of cut stone work —                                                                | cyd         | 12    | 55 4     |       |
| 9 6       | Rft of corner work —                                                                    | Rft         | 8     | 48       |       |
| 2.52      | Sqrs of floor with asphalt<br>1/2 inch thick concrete —                                 | Sqr         | 20    | 50 6 4   |       |
| 20.46     | " of Plastering inside<br>and outside                                                   | "           | 1 7 8 | 30 11    |       |
| 5.10      | " of Roofing with copper<br>nails, and bantles<br>in corners                            | "           | 10    | 51       |       |
| 83 17 1/2 | Cft of sand brought<br>and put up —                                                     | Cft         | 1     | 83 11 4  |       |
| 2.04      | Sqrs of sloping in Bengal roof<br>with copper shingles,<br>Concrete fill & 1/4" asphalt | Sqr         | 18    | 36 11 6  |       |
| 31 1/2    | Sqft of iron banded ventil-<br>lators with weather boards                               | Sqft        | 1 4   | 38 14    |       |
| 96 1/2    | " of Iron doors with fixtures<br>all complete                                           | "           | 1 8   | 144 12   |       |
| 133 3/4   | Cyds of Earth work —                                                                    | cyd         | 1     | 8 5 7    |       |
| 1         | Wooden arch rack<br>fixing in the wall                                                  | Each        | 5     | 5        |       |
|           |                                                                                         |             |       | 967 11 9 |       |
|           |                                                                                         |             |       | 107 3 0  |       |

130

957/119

52 1/2  
4243

1010  
980

Continues p.c. 5  
Total Rupees.

I do hereby certify that the Accommodation  
Estimate made for every thing necessary and  
that no supplementary estimate will be  
required.

W. H. H. H.

Major R. E.

Off. District Engineer

Garrison

Carey, Berhampore  
2 July 1876

W. H. H. H. Captain  
Ch. Dept. of Police

Chief Office of the Inspector General  
of Police  
Madras 5th February 1876

W. H. H. H.

For Inspector General  
of Police

29th 31/3/76

Specification

7

Accommodation - hounded

1. Guard room 12x12x12 with iron  
banded entrance gate 9x8 and 2  
ventilators each 3x16" with weather  
board & lattice. 1 arm rack 12' long.

1. Room 12x9x12 with iron banded  
door 4x3 and 4 ventilators each 3x16"  
with weather board.

Foundations 3' deep in 2 steps, rubble work  
on concrete.

Basement 2' high, rubble work face  
dressed.

Superstructure. Brick in Chumain plaster  
with coat inside and out.

Caps of pillars to be of cut stone.  
Roof of building - corrie roof. Flat and  
Pan tiled.

Do. of Veranda. Flooring terraed with  
1/4" asphalt over concrete jelly.  
Floor of building. Asphalt 1/2" thick  
on concrete.

Do. of Veranda. dressed stone  
steps.

Timber Sal wood. all end, and  
exposed surface to be baked  
in boiling tar before put up.

All iron to be baked in boiling  
tar before put up. W. H. H. H. Major R. E.

Off. District Engineer

3819  
PTW #1955/16  
4

C101955/ No 617 of 3.4.76  
Hence Copied

184

Letters 60 dated 4 March  
10 70 from the Dist Supt  
Enquiry -

The District Enquirer  
is requested to report  
upon the success of the  
change over, <sup>from the</sup> District  
Schedule in the following  
items after estimation  
~~of the~~ with list of  
above given -

Enq. -  
Brick & Cement - 5-11  
M. G. -  
Flaharck work to 11-5-  
Smithers. 4/4. 1.10  
Replaster. 4/4. 1-0  
Batter bars. 3-4.

Account inaccuracy in  
the calculations for the  
quantities having  
been detected the  
Estimates are returned  
for correction, the  
responsible person  
therein be called  
to account for furnishing  
determining the estimate  
to free of errors & it  
is requested that the  
Estimate cannot  
be made here  
Carefully  
checked  
in the  
Dist Enq. Office  
before its submission  
to Govt

Fork — Instructions of a Police Station.  
 Voice at Penditogan. —

| Detail & work                         | Quantity | Measurement |       |       |       |                         |        | Cubic ft. | Total quantity of<br>each item in work |
|---------------------------------------|----------|-------------|-------|-------|-------|-------------------------|--------|-----------|----------------------------------------|
|                                       |          | Length      |       |       |       | Breadth or<br>Thickness | Height |           |                                        |
|                                       |          | Sq ft       | Total | Total | Sq ft |                         |        |           |                                        |
| <b>Concrete in Foundations</b>        |          |             |       |       |       |                         |        |           |                                        |
| Front and rear walls—                 | 2        | 28          | 56    |       |       |                         |        |           |                                        |
| End and cross walls                   | 3        | 9½          | 28½   |       |       |                         |        |           |                                        |
| Retaining wall in front               | 1        | "           | 28    |       |       |                         |        |           |                                        |
| do " in sides                         | 2        | 1½          | 3     | 115½  | 4     | 1                       | 462    |           | 179                                    |
| <b>Total concrete in foundations</b>  |          |             |       |       |       |                         |        |           |                                        |
| <b>Foundations</b>                    |          |             |       |       |       |                         |        |           |                                        |
| Front and rear walls                  | 2        | 26¾         | 53½   |       |       |                         |        |           |                                        |
| End and cross walls                   | 3        | 10¾         | 32¼   |       |       |                         |        |           |                                        |
| Retaining walls in front              | 1        | "           | 26¾   |       |       |                         |        |           |                                        |
| do " in sides                         | 2        | 2¾          | 5½    | 118   | 2¾    | 3                       | 973½   |           |                                        |
| Steps                                 | 1        | "           | "     | 14½   | 3     | ½                       | 21¾    |           |                                        |
| <b>Basement</b>                       |          |             |       |       |       |                         |        |           |                                        |
| Front and rear walls                  | 2        | 26          | 52    |       |       |                         |        |           |                                        |
| End and cross walls                   | 3        | 11½         | 34½   |       |       |                         |        |           |                                        |
| Retaining walls in front              | 1        | "           | 26    |       |       |                         |        |           |                                        |
| do " in sides                         | 2        | 3½          | 7     | 119½  | 12    | 2                       | 187    |           |                                        |
| Steps                                 | 1        | "           | "     | 28    | 3¼    | 1½                      | 478    |           |                                        |
| Veneered floor                        |          |             |       |       |       |                         | 136    |           |                                        |
| Deduct for dressed stone              |          |             |       |       |       |                         | 1169¾  |           | 438                                    |
| <b>Total Foundations and Basement</b> |          |             |       |       |       |                         | 1320   |           | 197                                    |



Four doors  
 In door into kitchen  
 also couple  
 large door gate in  
 front of the Guard  
 Room

Total Square

Earth work -

Front and rear walls

End and cross walls

Retaining walls in  
 front

Total Earth work

Wooden framework the  
 lined in the wall  
 containing -

3319  
~~1418~~  
 3

3 1/2 " 7 24 1/2  
 9 " 8 72

96 1/2

96 1/2

2 30 60

3 1/2 22 1/2

1 30

11 1/2 4 4 18 1/2

133 1/2

1

Distt Engg Office  
 Cawnpur  
 Cawnpur  
 4 March 76

A: 68

From  
 The District Engineer  
 Cawnpur

To The Secretary to Government  
 Public Works Dept  
 Fort St George

Encls.

1 Plan of Police Station  
 1 Scheme of Station H.

Estimate for  
 Improvement  
 to Police Hospital now with  
 at Staplehead

I have the honor to submit  
 1 Plan and Estimate for constructing  
 Police Station House at Pundit.  
 - Jan. Rs 1010  
 2 Estimate for Improvement of  
 Police Hospital at Pundit.  
 - Jan. Rs 1004

duly countersigned by the  
 Inspector General of Police  
 for sanction by Government.  
 2. Funds for the above works  
 have

A: 522



1896

would then be  
 that the whole  
 of the world  
 is a vast  
 and beautiful  
 and wonderful  
 and glorious  
 and sublime  
 and majestic  
 and divine  
 and eternal  
 and infinite  
 and boundless  
 and unchangeable  
 and immovable  
 and indestructible  
 and inviolable  
 and incorruptible  
 and immortal  
 and everlasting  
 and forever  
 and evermore  
 and amen

*[Handwritten notes:]*  
- 10/12/72  
A. 10/12/72  
R

2.6. 1976 Det  
7.2.1958

The District Secy.  
Bangalore.  
10 The Secretary to Govt.  
Chennai

Oct 4<sup>th</sup> }  
Dec 17<sup>th</sup> } Maxwell 176.

Forwards Organized  
Schedule for Embarking  
Schedule for  
at Washington and  
one Schedule for  
Here to Police Headquarters  
at Washington and  
Embarking by the  
General of Police for  
Suction.

FORMER CASES.

Current No.

of 187

P. M. WORKS FORM No. 3.  
 W-1896 Dept.  
 Current No. 1958

From

The Lt. Engr.  
 Ganjam

No. 68  
 Dated 2  
 Recd. 17

March 1876

C. No 617 of 3-4-76

Subject:— Submit plans & Est.  
 for Consty. Police Station  
 house at Kunditgar  
 and one Est. for improve-  
 ments to Police Hospital  
 at Rapselendah.

ENCLOSURES.

5 Returns

From

G. O. 1470

Orders and Proceedings in file.

| Depart-<br>ment. | No.  | Date.    | ENDORSEMENTS.   |     |        |
|------------------|------|----------|-----------------|-----|--------|
|                  |      |          | Depart-<br>ment | No. | Dated. |
| P.H.D.           | 5610 | 24/11/75 |                 |     |        |
| "                | 63   | 9/5/76   |                 |     |        |

14219  
 Gi-9-6-76- Ma 13-6-76  
 Resd 6-6-76 D. 18-6-76

No. 78

Camp Chikhatol  
 District Engineer's Office.

GANJAM, 14<sup>th</sup> May 1876.

FROM

THE DISTRICT ENGINEER,  
 GANJAM.

TO

THE Dy. Chief Engineer  
 Fort St. George

SIR,

Enclosure.

With reference to your Memo  
 No. 617 dated the 3<sup>rd</sup> April/76 I have  
 the honor to report that the rates as allowed  
 in the last schedule of the Barampur  
 Range for the items therein referred to are  
 as follows:—  
 1. Brickwork per 100 cft = 12 or 12 1/2 = 3-3-10  
 Flat Archwork " " " " = 4-0-9  
 Iron doors " " " " square feet = 1-2-0  
 Asphalt square 1/2 " " " " = 24-8-0  
 Battens " " " " square feet = 12-0-0

The rates noted in your Memo do  
 not agree with the above and appear  
 to have been taken from the schedule  
 of the Chikhatol Range — The

The only items which have exceeded  
the rates in the schedule are—

- 1 Iron doors.
- 2 Batten doors.

The price of iron has risen since the  
estimate was framed and the Village of  
Punditgam where the Station House  
is proposed to be built is an out of the  
way place where materials and labour  
have to be imported and some allowance  
must therefore be made for extra rates.

The rate allowed for Batten doors  
1 square ft has been exceeded by only  
annas 1-4 and is absolutely necessary  
the rate for iron having risen—

2. There has been no competent  
draughtsman in this office for some  
years and all the endeavours that have  
been made to get one have been without  
avail the salary being so low viz Rs 45  
mens will not come up to the remotest  
end of the Madras Presidency where  
they

they can get employment for the same  
salary in the Southern Districts—

The estimate has been corrected  
which with the plan are herewith  
retransmitted.

I have the honour  
to be, Sir,  
Yours obedient servant

C. E.  
Off<sup>d</sup> District Engineer  
Gangani.

889-1/26 No 63.

P. H. 1876 Department

88-3819

Handwritten notes in Tamil script, likely a memorandum or report.

Handwritten notes in Tamil script, likely a memorandum or report.

Dated 14 May 1876.  
Dispatched 14 May 1876.  
Received 14 May 1876.  
Enclosure 2.

No. 18

THE Deputy District Engineer

To

FROM  
The District Engineer  
CANNIAI.

N. 220

Ci-9.6.76 Dtd 13.6.76

14.6.76 (13.6.76)

Depdt 29-5-76

No. 1470

Public Works Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 13 June 76.

Read the following:-

From

The District Engineer  
Gangam

(14.6.76 74 March 76)  
(18.11.76 May 76)

His Grace the Governor  
in Council sanctions  
the estimate of Rs 980  
for constructing a Police  
Station House at Pan.  
delgam in the Gangam  
District.

2. A sum of Rs 1010  
was provided for the  
work in list A printed  
with S.O. 3610 of the  
31 December 1875, but  
this amount was reduced  
by

by Rs 431 in L. O. in  
Judicial Department

No 779 of the 24<sup>th</sup> April  
1876 leaving a balance

8. 63 of 9. May 1876.

of Rs 579 for the Station

house at Puntitum

and It will rest with

the Inspector General

of Police to submit

through the Judicial

Department proposals

for providing the ad-

ditional sum of Rs 401

required.

3. This sanction has

been registered as Pro-

vincial No 667 of

1876-77.

N-219-221

6. 6. 76

8. 6. 76

8. 6. 76

8. 6. 76

8. 6. 76

8. 6. 76

214 Depd to 6-6-76

8. 6. 76

1950  
38/9  
G.O. 11270  
PUBLIC WORKS.

to D. C. Ganjam

Dist

Local

Recd

Recd

G. O. 18<sup>th</sup> June 1950, No. 1470

No. 219  
But in Reg. 221  
28-8-50

Police Station House at  
Punditganj, Ganjam Str.  
The Estimate of Rs. 900 for  
constructing a ———,  
sanctioned with remarks  
as to the provision of  
funds.