

- (1) Number of pages _____
(2) Date of repair _____
(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No.	1931	Press
B.P. No.		Mis. _____
Dated	28 - 7 - 1876	195 -

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
28th July 1876. No. 1,931.*

No. 506. Read the following letter from Lieutenant-Colonel J. H. M. SHAW-STEWART, R.E., Consulting Engineer for Railways, to Major-General G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Madras, 19th July 1876, No. 350 :—

I HAVE the honor to submit, for the sanction of Government, an estimate,* amounting to Rupees 9,792, for additional accommodation required for General Stores building at Negapatam on the South Indian Railway.

* With plan No. 779.

2. The Agent, in forwarding the estimate, remarks as follows:—

“The building used at a present for storage purposes is much too small to contain the increased quantity of articles which an increased mileage necessitates being kept on hand. Two or three temporary sheds have been erected to cover stores which cannot be allowed to remain unsheltered, but I wish to dispense with these sheds as soon as possible as they are liable to be destroyed by fire. Other stores have to be exposed in the yard, and although watchmen are employed by night and day, still we feel the want of security which a locked building supplies.”

3. The amount of Rupees 9,792 will be met from the provision made in Schedule B of the Budget Estimate for stations and buildings. The sanction will lapse on 31st December 1877.

4. The necessity for this work has been foreseen for some time past, and a sum of Rupees 30,000 was entered against it in the schedule for the half-year ended 30th June 1875, submitted to Government with this Office No. 142* of the 4th March 1875 and sanctioned by the Government of India in their letter embodied in the Proceedings of Government, No. 1,332, of the 10th May 1875.

No. 507.

ORDER THEREON, 28th July 1876, No. 1,931.

RAILWAY, No. 52.

THE reduced estimate, amounting to Rupees 9,792, for providing additional accommodation for the Store Department of the South Indian Railway at Negapatam is sanctioned as a charge against Capital, Schedule B, of the Budget Estimate of the current year.

2. The above sanction has been registered as Railway No. 8 W. of 1876-77.

(True Extract.)

To the Consulting Engineer for Railways.
„ Examiner of Railway Accounts.

Colonel,
Offg. Under Secy. to Govt., P.W.D.

Exd. J. W. Fischer.
Spare Copies

South Indian Railway.

Additional Accommodation General Stores
Building at Negapatam.

	To be expended ed. depart mentally					To be drawn from Stores		Total
V. <u>Station and Buildings</u>								
II. <u>Workshop and Stores</u> Buildings	9,792	00	-	-	-			9,792 00
Total Rupees								9,792 00

Note: - Provision is made in Schedule B
of Budget - Sanction to lapse
31st December 1877.

[Signature]
Chief Auditor
[Signature]
K. K. K. K.
Deputy Secy. Examiner
of Railway Accounts.

Chief Auditors Office
Negapatam, July 7th 1876.

[Signature]
Williams B. L. K.

Capital for Rs 97,920 and
registered as Railway Co.
& M. C. 1876-77. P. P.

South Indian Railway

Megapalam Terminal Station

Estimate for additional accommodation Megapalam Goods shed building

Particulars	Unit	Quantity	Rate	To be expended on the works	To be drawn from the stores	Total	Total
				Rs. a. p.	Rs. a. p.	Rs. a. p.	Rs. a. p.
<u>Stations and Buildings</u>							
2. Workshops & Store buildings							9792 ..
Excavation of foundations	Cyds	236	9/3/0	44 ..			
Masonry	"	260	8/0/0	2080 ..			
Flooring with brick on edge	Sqrs	58	5/0/0	290 ..			
Trak timber in rafters & posts							
wall plates & "							
Bungal, roofing	Sqrs	70	12/0/0	840 ..			
Doors 2/3 Venetians & 1/3 panel 8' x 5'	Sqrs	4	64/0/0	256 ..			
Windows Venetians	"	28	34/0/0	952 ..			
				9326 ..			
Contingencies @ 5%				466 ..			
				9792 ..			9792 ..
2. Workshops & Store buildings							9792 ..

Chief Engineer's Office
Trichinopoly 6th July 1878

Robert
Chief Engineer

RAILWAY DEPARTMENT.

CONSULTING ENGINEER'S OFFICE,

Madras, 19th July 1876.

No. 350.

From

LIEUT.-COLONEL J. H. M. SHAW-STEWART, R.E.,

Consulting Engineer for Railways,

To

MAJOR-GENERAL G. W. WALKER, R.E.,

Secretary to Government,

Public Works Department,

Fort Saint George.

SIR,

* with plan
No. 777.

I have the honour to submit for the sanction of Government, an estimate amounting to Rs. 9792, for additional accommodation required for General Stores building at Negapatnam on the South Indian Railway.

2. The Agent in forwarding the estimate remarks as follows:-

"The building used at present for storage purposes is much too small to contain the increased quantity of articles which an increased mileage necessitates

5820-3-75 No 792
10-5-75 - 1332

L. H. 1876 Department
80-5175

No 1931. Public Works Department.
PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 28th July 1876.
Read the following:—

From
The Cons. Eng^r. for
Railways (H.C. No. 350 of 19th July 1876)

The reduced Estimate
amounting to Rs 9792 for
providing additional ac-
commodation for the Store
Department of the South
Indian Railway at
Negapatam is sanctioned
as a charge against
Capital, Schedule B
of the Budget Estimate
of the current year.

The above sanction
has been registered as
Railway No. 811. of 1876-77.

Cons. Eng^r. for Ryos
Ex. Ry. Accts. ✓
28.7.76

From
The Consulting Engineer
for Railways,
RAILWAY DEPARTMENT.

To
The Secretary to Government,
P. W. Department,
Fort Saint George.

Dated 19th July
Received 10th July
No. 350
1876.

12506
24.7.76 (H.C. 28.7.76)
Despatched to Govt 20-7-76.
Submitted by
for the sanctioning
of the current ac-
count for the
Store Building
at Negapatam.

Entwurf
15-8-78-