(1) Number of pages

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No. 1985 (W) Press
B.P. No. Mis.

Dated 3 8 1876.

Not to be folded or roughly handled

Proceedings of the Madras Government, Pub. Works Department,*
3rd August 1876. *No.* 1,985.

No. 77. Read the following Proceedings of the Madras Government in the Military Department, dated 8th July 1876, No. 3,406 :—

ABSTRACT.—Approving an estimate, amounting to Rupees 1,376, for converting the old Royal Artillery Barracks at Bellary into a Commissariat Beer Godown.

No. 78. ORDER THEREON, 3rd August 1876, No. 1,985.

MILITARY, No. 4.

(a) *Heads of Service.*—Imperial.
Fund.—Ordinary.
Class.—Original Works.
Main-head.—Military.
Sub-head.—Commissariat Buildings.
Name of Work.—Converting old Artillery Barracks at Bellary into a Beer Godown.
Amount.—Rupees 1,376.
To be carried out by the Public Works Department.

THE plan and estimate of Rupees 1,376 for converting the old Royal Artillery Barracks at Bellary into a Beer Godown are sanctioned.

2. The work may be put in hand in anticipation of a specific allotment of funds which will be made on the total grant for Minor Works being increased by the Government of India; proposals to this effect having been submitted.

3. This sanction has been registered as Imperial No. 49-W. of 1876-77.

(True Extract.)
(Signed) G. W. WALKER, Major-General, R.E.,
Secretary to Government.

To the District Engineer, Bellary.
" Examiner of Public Works Accounts.
" Military Department.

Exd. W. H. French.
Spare Copies

With Reference to the request

(a) Heads of Service— Imperial

Fund. Ordinary

Class. Original Works

Main-head. Military-

Sub-head. Commissariat Buildings

Name of Work. Converting old Artillery Barracks at Bellary into a Rice godown-

Amount. Rs 1376

To be carried out by the P.W. Department.

Remit in the margin of G.O.No 1985 of 3/8/76-

30

573

Specification Report to accompany the Amended Plan and Estimate for converting the Old Royal Artillery Barracks into a Rice Godown for the Commissariat Dept.

Amount of Estimate Rs 1376/

In compliance with the Commissary General's letter No: 8843 dated 28 March 1876 and with the sketch drawn on the paper plan which accompanied the correspondence, the present estimate provides for an iron palisading to be placed across part of the prison yard from the outer edge of the verandahs of the two opposite wings of the building. the verandahs at the points where the railings cease will be closed by stone walls built from the pillars to the main walls of the building and of an average height of 8 feet to reach the sloping roof, the barrack, viz: Palisading & Walls, is in place of that originally proposed to be fixed between the verandah pillars - It will now be necessary to provide 2 hinged iron barred doors, to allow the inner verandah to be used for storage, in addition to the two formerly proposed for the outer faces of the building-

With reference to the request that

ridge ventilation be provided, the fact does not seem to have been known that four large ventilators w. skylights exist giving 8 openings on the roof each with an open iron barred front 3½×4. The position and dimensions of these ventilators are shown on the new ground plan and section - It must also be stated that it would not be practicable to fix the new timber required for ridge ventilation to the old plumpa rafters which have had to be propped up by wooden posts at some former period -

A request has also been made for wooden shutters to the doors and windows, the doors and windows are already provided with such shutters which are in fair order.

The general repairs required to the building will be separately estimated for under the heads of Repairs Civil &c

Lt
Assistant Engineer
In charge Kellar Range

Kellar Range Office
Kellar 2? June 1876

P.W. 5274/2/16

From
The Officiating Chief Engineer
Kussyfange
To The Dist: Engineer
Kellaz

Sir 2nd June 1876

Have the honor to forward herewith Specification, Plan & Estimate for converting the Old Royal Artillery Barracks into a Reel Godown for the use of the Commissariat Department

I have accompany the Estimate for converting the Old Royal Artillery Barracks into a Reel Godown for the use of the Commissariat Department

ABSTRACT ESTIMATE.

Kellaz DISTRICT

WORK Converting the Old Royal Artillery Barracks into a Reel Godown for the use of the Commissariat Dept^t vide letter No: 843 from Commissary General Madras to the Quarter Master General Fort Saint George of 28th March/76

Quantities.	Description of Work.	Rate.	Per	Amount.	Amount of each part.
	Cost of Building as per Estimate dated 15th May 1875				
776.50	6ft. Stone masonry in Lime mortar	" 2 6	6ft	151 5 3 / 194 7 3	/
17.44	6x2 Excavating foundations	" 2 -	6 yds	2 2 10	/
66	2ft. Square Bolts 1/2 x 3/8	" 6 -	Ft.	24 12 -	/
8	Slab 2x2 6 Bolt Heads	1 2 -	Each	9 - -	/
5.25	6ft. Tarred jungle Wood	3 - -	6ft	15 12 -	/
324	6ft. Brick masonry in Lime mortar including flat iron cramps and bars	1 2 -	6ft	364 8 -	/
578	6ft. Pointing	1 10 -	Ft.	9 6 3	/
457.37	-- Fixed Iron Bars with the present frame with flat iron cramps and bars	1 2 -	6ft	516 12 8	/
4	Iron barred Doors	60 - -	Each	240 - -	/
	Removing 4 Door frames 6 1/2 x 3 3/4 & fixing 2 frames and 7x4 & rebuilding and replastering the masonry	1 - - - -		4 - -	/
	Total			1310 13 - / 1307 11 / 66 - 3 / 68 - -	
	Sundries at 5 per cent			1376 - -	1376 / -
	Total Estimate Rupees				

Kellaz Range Office
Kellaz 2nd June 1876

Assistant Engineer
In charge Kellaz Range

No 1905

PROCEEDINGS OF THE MADRAS GOVERNMENT

Under date the 5th August 1876

Read the following:—

Proceedings of the Military Department } No. 1346 dated 8th July 1876

The plan and estimate of the proposal for converting the old Royal Artillery Barracks at Bellary into a Beer godown are sanctioned.

2. The work may be put in hand in anticipation of a specific allotment of funds which will be made on the total grant for Minor Works being increased by the Government of India on proposals

P.W. 5274/1/76

From

The Asst. Engineer

In charge Bellary Range,

To

The Superintending Engineer

2nd Division,

Dated 21 } June 1876.
Received }

Abstract Estimate amounting to Rupees 1376

for converting the old Royal Artillery barracks into a Commissariat beer godown for the use of the Commissariat Dept:

Rupees 1376

Rs. 11,5086

Proceedings of the Madras Government, Military Department,
8th July 1876.

Barracks and Buildings.

Read the following letter :—

No. 117. From Brigadier-General A. HOWLETT, C.B., Quartermaster-General, to Colonel J. MICHAEL, C.S.I., Secretary to Government, Military Department; dated Head Quarters, Ootacamund, 15th June 1876, No. 130-4192.

The Commander-in-Chief having approved the estimate* marginally noted, I am directed by His Excellency to submit them for the consideration and orders of Government.

2. If approved by Government, it is requested that the papers may be forwarded to the Department Public Works for disposal.

Enclosures 3 (1 *Plan.*)

* Amounting to Rupees 1,376 for converting the old Royal Artillery barracks at Bellary into a Commissariat beer godown, in consequence of the present building not being adapted for the storage of malt liquor.

No. 118. ORDER THEREON, 8th July 1876, No. 3406.

Approved.

(True Extract.)

(Signed) J. MICHAEL, Colonel,
Secretary to Government.

To the Public Works Department, with three enclosures.
„ Quartermaster-General.

Exd. A. Raitt.

proposals to this
effect having been
submitted.

3. This sanction has
been [illegible]
Imperial Irrig Wks
1876-77.

District Engineer,
Chicago Ill.
Engrs. U.S. Army
Military Department.
Dated 8/5/76

Xo attd

5274 CH.

Estt. of 1876 Madras.

PUBLIC WORKS.

To

The W. & B. Railway

Dist.

Estd.

Dist.

Rec.d 3 Aug.t 1876, No. 1985

Rec.d at 1/4 5/8.

Rs. 11,495.—

Excavating the old Royal Artillery Barracks at Bellary into a Beer Godown - Plans & Estimate for 1 sanctd.

Ex.v. in Rly. 17-8-76.

X.v. 11/8