

(1) Number of pages_____

(2) Date of repair_____

(3) Initials of the Referencer_____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No.	2236	Press
B.P. No.		Mis.
Dated	2-6-8	C876 -195-

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
24th August 1876. No. 2,236.*

No. 548. Read the following letter from Major H. M. VIBART, R E, District Engineer, Bangalore, to Major-General G. W. WALKER, R E, Chief Engineer, Public Works Department, dated Bangalore, 8th August 1876, No 100.—

I HAVE the honor to forward the accompanying estimate for repairing the range of buildings on the western side of the Commissariat square, amounting to Rupees 8,900,* for sanction.

* Rupees 1,125 more than one-fourth the value of the building

2. Funds allotted for repairs being insufficient to carry out such extensive repairs, I request that special allotment may be granted for the execution of this work

3 The estimate has been approved by the Major-General Commanding the Division.

No. 549. ORDER THEREON, 24th August 1876, No. 2,236.

MILITARY WORKS, No. 20.

(a) *Head of Service* — Imperial.
Fund — Ordinary
Class — Repairs
Main head — Military
Sub-head — Commissariat Buildings
Name of Work — Repairing the range of buildings on the western side of Commissariat square at Bangalore
Amount — Rupees 8,900
To be carried out by the Public Works Department.

THE estimate of Rupees 8,900 for repairing the range of buildings on the western side of Commissariat square at Bangalore is sanctioned. There are no funds at the disposal of Government for allotment to the work. The District Engineer should appropriate such a sum as he may be in a position to provide.

2. This sanction has been registered as Imperial No. 69 W. of 1876-77.

(True Extract.)

Colonel,
Offg. Under Secy. to Govt, P.W.D.

To the District Engineer, Bangalore
" Examiner of Public Works Accounts
" Military Department.

Exd E C Shunker
Spare Copies

Imperial Ordinary Military Commission ^{in 2011} Repairs
Revised Detail Estimate No 64 of 1876/77

District Bangalore

Work Repairing the range of buildings on the western side of the Commissariat Square for storing Malt Liquor. Vide Asstt. Dy. Mr. Genl. M.D. No 249 dated 3rd June 1876.

Particulars of work	Measure No. - unit	Contents	Total
Removing roof			
North & south side room	2 2 1/2 14	6.02 1	
West Range inner side	1 3 40 25	85 00	
Do Old Bakery	1 16 1/2 25	42 12 1/2	
Do Ventilators roof	2 50 1/2 5	55 85	
Do Outside including Bakery	1 58 1/2 14 1/2	73 13 1/4	
Total Sps of removing roof			259 7 3/4
Total Sps of re-roofing with 1/2 new flat and pan tiles & teakwood paper			259 7 3/4
nails & chunam borders			

Dismantling

Partition walls between work	2 10 1 1/2 13	702	
shop and flour godown			
Do Gable	1 18 1/2 3	81	
Making openings in back wall for windows	29 4 2 5	1160	

Carried Over 1943

Particulars of work	Measure			Contents	Total
	No.	ment	L B D		

Brought Over 1743

Dismantling ovens of old bakery . 133 12 6 7576

Le four walls between ver-

-randah pillars . 4 6 1/2 6 216

From between rafters . 1 500 1/2 1/4 187 1/2

11722 1/2

Deduct for spaces in Ovens . 133 8 4 11256

Total left of Dismantling & removing rubble 766 1/2

Brick in chunam

Building up between rafters . 500 1/2 1/4 187 1/2

Repairs to windows . 17 4 1/2 1 102

Total left of brick in chunam 287 1/2

Wood work

Prestummers . 50 6 8 16 8

Rafters for 100 couples . 200 12 1/4 3 6 36 3

Collar pieces large . 100 15 1/4 3 11 157 1

Do Small . 100 9 1/2 3 4 77 5

Rafters for ventilator roof . 200 4 1/2 3 2 45 1 2

Rafters for verandah . 100 15 3 6 87 6

Total left of jungle wood wrought and 11-78

Plastering

Walls inside . 2 340 13 . 2840

Do Gables . 2 18 13 . 168

Do Do . 2 18 8 . 108

Carried Over 9416

Particulars of work	Measure			Contents	Total
	No.	ment	L B D		

Brought Over 9416

Walls out side . 2 340 12 1/2 . 8580

Pillars . 41 1 1/4 8 . 1968

Basement . 2 348 1/2 . 1029

South verandah room outside . 47 8 . 376

Do inside . 2 20 9 . 360

Do Do . 2 22 11 . 484

South side room outside . 34 9 . 306

Do inside . 60 11 . 660

Main wall of Bakery &c . 2 166 13 . 4316

Verandah & out side - Do . 2 166 12 1/2 . 4150

Outer walls of verandah - Do . 2 166 8 . 2656

Basement . 1 166 1/2 . 249

34470

Deductions

Doors . 4 5 8 . 160

Windows . 16 5 4 . 320

Do proposed to be opened

in back wall . 16 5 4 . 320

Arch ways . 9 3 7 . 189

Door ways . 4 5 8 . 160

Windows . 17 4 1/2 4 1/2 . 324 1/4

Do proposed to be opened . 13 4 5 . 260

Total 1753 1/4

Total Srs of Plastering 8179

Particulars of work	Measure	Quantity	Unit	Total
<u>Whitewashing</u>				
Walls inside	2	240	13	8820
Do Gables	2	18	13	168
Do Do	2	18	3	108
Pillars	11	1 1/4	3	1968
South verandah room inside	2	20	9	360
Do Do	2	22	11	1124
South side room inside	60	11		660
Main walls of kitchen	2	166	13	1316
Verandah Do	1	166	13 1/2	2075
Total Sps of whitewashing				17271
<u>Blue washing</u>				
Walls outside	2	240	13 1/2	8500
Pavement	2	240	1 1/2	1029
South verandah room outside	47	8		376
South side room outside	34	9		306
Verandah outside	1	166	12 1/2	2075
Outer walls of verandah outside	2	166	9	2656
Pavement	1	166	1 1/2	249
Total Sps of Blue washing				15191
<u>Flooring</u>				
Present work shop	165	10		2770
Door ways	2	5	1 1/2	15
Old wheat & flour godown	170	18		3060
Door ways	2	5	1 1/2	15
Carried Over				6060

Particulars of work	Measure	Quantity	Unit	Total
<u>Drought Over</u>				
Front verandah	316	12		3792
South verandah room	23	10		230
South side room	18	10		180
Under Queens old Bakery	133	12		1596
				11858
Deduct verandah Pillars	41	1 1/2	1 1/2	92 1/4
Total Sps of taking up flooring and relaying on 3 glass concrete with half new flags				11765 3/4
<u>Doors</u>				
New battened doors with iron fittings & complete	4	5	8	4
<u>Windows</u>				
New battened with frames, iron bars shutters fastenings & complete	29	4	5	29
Renewing old windows with shutters frames & complete	7	4	5	7
Removing glass & replacing with pannelled mentioned shutters also 8 additional iron bars 3/4 dia be put in to east windows	17	4 1/2	4 1/2	17
Repairing 2 windows to South side room	2			2

Particulars of work

Measure
of
ment
8 1/2
Cubits
Total

Painting

Doors	5	16	5	400
Windows	66	8	5	2640
Total Sp. of green painting 2 coats				3040
Carriage to Coimbatore				
Light 1 stone for doors	5	4	2	5
Do windows	66	6	2	66

56

P.W.D.

Imperial

9/1/76

Military

Repairs

Revised Abstract Estimate No 64 of 18/6/77

District Bangalore

Work Repairing the range of buildings on the western side of the Commemorial Square for storing Malt Liquor. Vide Estt. No 124 Genl. M. No 249 dated 3rd June 1876.

Quantity	Description of work	Rate	Amount	Total
1	Sp. of Removing roof	258	✓	
254.73	Sp. of Re-roofing with 2 new flat and pan tiles & slate, uppers & nails & chunam borders	11 8	2964	
7667	Sp. of Dismantling, brickwork and removing rubbish	3	120	
290	Sp. of Brick in chunam	8	54	
761.98	Sp. of Junglwood wrought and put up	2 8	1908	
81.79	Sp. of Plastering	2 8	204	
192.79	Sp. of White washing	2 6	24	
151.91	Sp. of Blue washing	3	28	
117.66	Sp. of Taking up flooring & relaying on 3 glass concrete with half new flags	10	1174	
4	New battened doors with iron fittings & complete	40	160	

Carried Over 6,894

L. 6
 Description of work. Rate Per Sq. Ft.

No. 694

29	New buttoned windows with frames, iron bars shutters fastenings &c complete	31	Rs.	706
7	Renewing old windows with shutters frames &c complete	15	Rs.	105
17	Removing glass & replacing with pannelled & actioned shutters also 8 additional iron bars $\frac{3}{4}$ in. to be put in to east windows	15	Rs.	255
2	Repairing 2 windows to south side room	5	Rs.	10
30	40 Sps. of green painting 2 coats	3	Rs.	106
5	Barring to complete		Rs.	120
5	Lintel stones for doors	1	Rs.	8
66	Do - Windows	1	Rs.	66

2,170
 400
 Total Estimate Rs. 2,570

M. S. M. S. M. S.

Dist. Eng. Office
 Bangalore
 4th Aug. 1876.
 District Engineer.

P. H. 5891/76

No 100

DISTRICT ENGINEERS OFFICE,
BANGALORE 8 August 1876

From

THE DISTRICT ENGINEER,
BANGALORE

To

THE Chief Engineer P.O.W.
Madras.

From

The District Engineer
Bangalore

To
The Chief Engineer
P.O.W.
Madras.

Dated 8 August 1876.

Recd

Estimate for repairing
the range of buildings
on the Western side
of the Commissariat
Square for storing
Malt-Legumes
Amounting to Rs 8900

I have the honor to forward
the accompanying estimate for
repairing the Range of buildings
on the Western side of the
Commissariat Square, Amounting
to Rupees 8900* for sanction. —
* 1125 Rs more than one fourth
the value of the building —

Funds allotted for repairs
being insufficient to carry out such
extensive repairs I request that
special allotment may be granted
for the execution of this work. —

3. The Estimate has been approved
by the Major General Commanding
the Division. —

I have the honor, to be, Sir,
Your most Obedient Servant
H. J. Stewart Major R.E.
District Engineer.

P.W.D.
S. 176
No. 5691

From
The District Engineer
Bangalore
To
The Chief Engineer
P. W. D.
Madras.
Dated 30
Dec 3 August 1916
H. 2
Rs. 100.
Rupees one
Range of building
on the Western side
of the Bangalore
Station for
an estimate amounting
to Rs. 8900 for repairs
viz the — and no extra
special allotment
of funds.

(a) Heads of Service— *Imperial*

Fund. *Ordinary*

Class. *Repairs*

Main-head. *Military*

Sub-head. *Commissioned Buildings*

Name of Work. *Repairs to range of buildings on
the Western side of Commissioned
Square at Bangalore*

Amount. *8900 Rs.*

To be carried out by the *P.W.D.* Department.

Ci-19-2-76 1/2 24-2-76
Resd to Ci-17-2-76

Dated 7/9/16

No 2236

Public Works Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT

UNDER date the 24 Aug 76

Read the following —

From
The District Engineer
Bangalore } (No. 100 of 8th Aug 1876)

The Estimate of Rs 8900
for repairing the Range of
buildings on the Western
side of Commissariat
Square at Bangalore, is
sanctioned. There are
no funds at the disposal
of Government for allot-
ment to the work. The
District Engineer should
appropriate such a sum
as he may be in a position
to provide.

2. This sanction has been
registered as Imperial

Dist Engr. Bangalore. No 69 of 1876-77.

By Mr. P. W. Accounts

Military Department.

Settled 7/9/76

Civ. 14. 2. 76 1st 24. 2. 76

56913

GOVT. OF MYSORE
PUBLIC WORKS.

to H. B. Bangalore

100

100

100

to H. B. Bangalore 2236

to H. B. Bangalore 549

Regarding the cause of
buildings on the western side
of Commisariat square
at Bangalore. Estimate
for ———— can be estimated
made regarding the
value of ground for the work

to H. B. Bangalore
549