M.R.O. I—10,006—28-2-50.

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No. 2876 Press Original
B.P.—No.— —Mis.—

Dated 27-10-1876 —195—

Not to be folded or roughly handled

No. 437. Read the following Proceedings of the Madras Government in the Judicial Department, dated 28th September 1876, No. 1,971 :—

ABSTRACT.—*Taluq Cutcherries.*—Plan and estimate, amounting to Rupees 130, for converting a room in the Calicut Town Magistrate's Court into a record-room approved, and the necessary orders to be issued in the Public Works Department.

No. 438. ORDER THEREON, 27th October 1876, No. 2,876.

CIVIL WORKS, No. 27.

(a) *Heads of Service.*—Provincial.
Fund.—Ordinary.
Class.—Original Works.
Main-head.—Civil Buildings.
Sub-head.—A, Judicial Department.
Section.—i, Court-houses.
Name of Work.—Record-room for Sub-Magistrate's Cutcherry, Calicut.
Amount.—Rupees 130.
To be carried out by the Public Works Department.

THE plan and estimate of Rupees 130, for converting a portion of the ground-floor of the Sub-Magistrate's Cutcherry at Calicut, in the Malabar District, into a record-room, are sanctioned.

2. The District Engineer will supply the requisite funds from the allotment for Minor New Works, Civil Buildings, Provincial, at his disposal.

3. This sanction has been registered as Provincial No. 171 W. of 1876-77.

(True Extract.)

Major-General, R.E.,
Secretary to Government.

To the District Engineer, Malabar.
" Examiner of Public Works Accounts.
" Judicial Department.

Exd. S. T. Austin.
Spare Copies

P.A.COLLE
16 JUL
1876
S.E.C.S.

Specification to accompany Estimate for constructing a Record Room on the ground floor of the Sub-Magistrates Court at Cabcut.

Amt. of Estimate Rs 130-0-0

It is proposed to convert a portion of the large Room on the ground floor of the Sub Magistrates' Court at Cabcut into a Record Room measuring 16¾ × 11½, by constructing a wall (marked AA on plan) 1½ feet thick and to the full height of the existing walls, with a foundation 2 feet broad and 3 feet deep.

One batten door (7'×4') and two iron grated windows (5'×3½') to be fitted into the walls of the proposed room as shewn in plan and the whole to have flat arches 1½ feet deep constructed over them. The iron bars of windows to be 1 inch thick and placed horizontally 4½ inches apart from centre to centre. The ends of bars being let 2 inches into the frame.

The timber used for the doors and windows to be well seasoned Sirol or Kanmaruthu, free from flaws and other defects, and the masonry to be of picked laterite in Chunnam, Composed of 1½ parts of sand to one of chunnam and plastered with two coats of chunnam, the first coat being composed of ½ of sand to one of chunnam and the second coat of equal parts of Chunnam and sand. The joints in masonry to be raked out to a depth of half an inch before laying on the plastering.

The existing door and window (marked BB on plan) to be removed & the spaces closed with masonry.

After the completion of work all rubbish is to be removed and the ground [illegible]

Cochin
Executive Engineer
Calicut Range Office
Calicut 7th July 19[illegible]

P.W.D. Main [illegible]
Vizhinjam [illegible]

P.W.D.
7 OCT 76
5218

Re a letter from
the Master of Brahalea
J 25th August 1876
No 223.

Ltr Rec'd 11th Oct 1876

Specification for
Constructing a record
room.

Rec'd 26 Oct 1876

Taking Measurements	Nos.	Breadth	Height	Particulars	Rate	Amount.
					per	Cubic Work.
				Net Total 431¾ cft of laterite in chunam	@ 15 as	64 12 2
	4½	1½	7½	108 Over door in partition wall.		
	4	1½	1½	18 Over windows.		
				Total 288 cub. feet of flat arch work	@ 20 as	Do. 5 10 as
				5 squares of plastering and white-washing to walls	@ 2 4 sqre	11 4
				1 Batten door (4×7') of Erinhor Hardwood complete	@ 15 as each	15 as
				2 Louvered windows (3½×5) with batten shutters (3 inch battens 1 inch thick & 4½ apart from centre to centre)	@ 12 8 as	Do. 25 as
				Removing 1 door (4¾×7)	@	8 as
				Do. 1 window (5×3)	@	6 as
				Demolishing portions of existing walls for 2 windows	@ 8 as each	1 as
	2	3	9½	57 Cub. feet or 2 cubic yds of re-Casting foundations to partition wall	@ 2 cyd	72
				Total Rupees		123 54
				Sundries & Superintendence @ 5 per cent		6 8
				Amount of Estimate Rupees		130 as

H.M. Calicut Range Office
Calicut 7th July 1876

Captain.
Executive Engineer
In charge Calicut Range

Examined

before Calicut

Malabar Dist. Engr's Office
Cannanore 11th July 1876

Lt. Col. H. Kennedy
District Engineer, Malabar

Proceedings of the Madras Government, Judicial Department,
23th September 1876. *No.* 1971.

Taluq Cutcherries.

No. 115. *Read the following Proceedings of the Board of Revenue, dated* 16*th September* 1876, *No.* 7920 (*Miscellaneous*):—

Read the following letter from the Magistrate of Malabar, to the Acting Secretary to the Board of Revenue, dated Calicut, 25th August 1876, No. 223:—

I have the honor to forward a plan and estimate, amounting to Rupees 130, for converting a portion of the large room on the ground-floor of the Town Magistrate's Court, Calicut, into a record-room, and to request that Government may be moved to provide funds for the expenditure.

2. The necessity for this work is the absence of sufficient space in the record-room recently repaired, it being partly occupied by the Sub-Registrar.

Submitted for the sanction of Government.

(A true Copy and Extract.)

(Signed) H. E. STOKES,
Acting Secretary.

Transferred to the Judicial Department.

(Signed) D. F. CARMICHAEL,
Secretary to Government.

OOTACAMUND,
21*st September* 1876.

No. 116. ORDER THEREON, 28th September 1876, No. 1971.

Approved.

2. The necessary orders will be issued in Public Works Department.

(True Extract.)

for Chief Secretary.

To the Public Works Department, with plan and estimate.
" Revenue Department.
" Accountant-General.

Ed. J. Wright.

P.W.D.
76576
2113

Govt. of 1876 Madras.

JUDICIAL.

To

THE PUBLIC WORKS DEPARTMENT,

&c., &c., &c.

Dated 5 September, 1876.

G.O., 29th September 1876, No. 1071.

SEPTEMBER.
Nos. 115-116.

Taluq Cutcherries—Plan and estimate, amounting to Rupees 130, for converting a room in the Cuddalore Town Magistrate's Court into a record room approved, and the necessary orders to be issued in the Public Works Department.

P.W.D.

Funds from the allotment
for minor new works
Civil Buildings Provincial
at his disposal.

2. This sanction has
been registered as Provincial
No. 1716 of 1876-77.

[signature]
27.10.76.

No. 437/38

Cir 24-10-76
Despatched 27-10-76.

H.E. the Governor
C.C. & H.A.
Judicial Dept.
Board - 3-11-76.

(a) Heads of Service— Provincial

Fund. Ordinary

Class. Original Works

Main-head. Civil Buildings

Sub-head. A. Judicial Department

Name of Work. Section-1 Court houses.
Record room for Sub Magistrate's
Cutchery, Calicut—

Amount. Rs 130

To be carried out by the P. W. Department.

Remit in the margin of G.O. No. 2876 of 27-10-76—

7-219

Govt. of {1876} Madras.

PUBLIC WORKS.

To The H. B. Metcalfe

28-10

Dated

Rec'd

Recd. 1 Encl.

G. O. 27 October 1876, No. 896

Nos. 437/38

Recd Coom for the Engr
Superintendent Calicut Malabar Dist.
Plan & Estimate amounting
to Rs 150 for erecting
a ——— Lavatories &c &c
Answered as the proposals
Estimate of sum &c

Entd in Reg.
4-11-76.

Signed