

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No.	3506	Press
B.P. No.		Mis.
Dated	21 - 12 - 195	48.76

Not to be folded or roughly handled

Read the following:—

No. 299 W.

No. 513. *Note by the Chief Engineer for Irrigation.*

THE District Engineer, Cuddapah, forwards, with his letter marginally noted, an estimate in connection with the Darasavancha Boyani Tank, situated in the Budwail Taluq, Sidhout Range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow:—

ORDINARY AGRICULTURAL.

Repairs.

Raising and repairing the bund and revetment	...	...	...	Rs. 350
				Total Rs. 350

3. The following particulars of this tank are recorded—

Ayacut area	...	...	...	...	20 Acres.
Assessment...	...	...	...	...	200 Rupees.
Average revenue	...	...	...	...	168 "
Highest do.	...	...	...	...	191 "
Expenditure during the previous four years	...	...	...	...	Not known.

The area of the catchment basin is 2 square miles; the maximum flood supply is calculated at 756 cubic feet per second, for discharging which as surplus there is a natural escape 118 feet in length at the northern side of the bund, formed on a bed of kunkur.

The bund of this tank is low, irregular and weak, especially towards the northern end. The revetment of the bund has slipped in many places and is at various inclinations, but as the greater part is in good order it will not be disturbed, only those portions which need repair will be repacked.

The sluice has been lately repaired and the outlay on it should have been entered in the report accompanying the estimate.

The estimate provides for raising and strengthening the bund, relaying such portions of the revetment as are out of order, also for raising the revetments to a uniform level of 1.5 feet above the highest water mark, and for gravelling the front slope above stone-work, top of bund and along the rear slope.

The estimate is recommended for sanction.

(Signed) A. DE C. SCOTT, Major, R.E.,
Dy. Chief Engineer for Irrigation,
for Chief Engineer for Irrigation.

FORT ST. GEORGE,
16th December 1876.
To the Secretary to Government, Public Works Department.

Proceedings of the Madras Government, Public Works Department,
21st December 1876. No. 3,506.

No. 514.

ORDER THEREON, 21st December 1876, No. 3,506.

IRRIGATION, No. 41-A.

Account.

THE following estimate from the
Sidhout Range, forwarded by the District
Engineer, Cuddapah, is sanctioned:—

DARASAVANCHA BOYANI TANK.

IRRIGATION.

Group or Project.

Fund.—Ordinary Agricultural.

Class.—Repairs.

Name of Tank, Canal or Channel.—Darasavancha Boyani Tank.

Particulars of work.—Repairing the bund.

Amount.—Rupees 350.

To be carried out by the Public Works Department Officer in charge Sidhout Range.

2. This sanction has been registered as No. 213 I. of 1876-77.

(True Extract.)

Major-General, R.E.,

Secretary to Government.

E. I. Form No. 9.

OFFICE OF THE CHIEF ENGINEER

FOR IRRIGATION,

Fort St. George, 16th December 1876.

No. 299-W.

Note by Chief Engineer for Irrigation.

THE District Engineer, Cuddapah,

forwards, with his letter marginally noted, an Estimate in connection
with the Darasavancha Boyani Tank situated in the
Rudivail Taluq, Sidhout Range.

2. The nature of the work proposed for execution and the heads of account
to which it is chargeable are as follow:—

Ordinary Agricultural.	
Repairs	Rupees.
Raising and repairing the bund	
and revetment.	350.
Total Rupees.	350.

3. The following particulars of this Tank are recorded—

Ayacent area.	20 Acres.
Assessment.	200 Rupees.
Average revenue.	168 Rupees.
Highest do.	191 Rupees.
Expenditure during the previous four years.	Not known.

P.W.D.
1876 18DEC76

From
The Chief Engineer for Irrigation
To
The Secretary to Govt.
P. W. D.

Dated 16.3 Decr 1876.
Despt. 18 3 Decr 1876.

Encls 6

N. 299-W.

N-573
Barasavancha Bozani Tank.
— Cuddapah District. — Note
recommending for sanction
Estimate for Rs. 350 for raising and
repairing the bund of the —.

103506

E. I. Form No. 4.

Proceedings of the Madras Govt.
Under date the 21st Decr 76
Read the following
From the Chief Engineer for Irrigation (A.E. No 299 W of 16 Decr 76).

The following Estimate from
the Sidhout Range
forwarded by the District Engineer,
Cuddapah is sanctioned:—

Barasavancha Bozani Tank.

Irrigation.

Group or Project.	Fund.	Class.	Name of Tank, Canal, or Channel.	Particulars of Work.	Amount. Rs.
	Ordinary. Agricultural	Repairs.	Barasavancha Bozani Tank.	Repairing the bund.	350.

To be carried out by the P. W. Department Officer in charge of Sidhout Range.

2. This sanction has been registered as No. 213 I. of 1876-77.

Ch. E. Cuddapah
Collector of Cuddapah
Ch. E. for Irrig. with 6 Encls.
D. R. N. A. 10-1-77

9172

Gobt. of 1876 Madras.

PUBLIC WORKS.

To

M. S. Buddapah

Dated

Issued

Recd.

Encl.

G. O. 21st Nov 1876, No.

3526

Nos. 573/14

Darasavanah Bozani
Tank, Buddapah Str.:-

The Estimate of Rs. 350
for repairs to the —
sanctioned.

Encl. no Reg. 3.

N 573/14