

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public Works

DEPARTMENT

G.O. No.	3510	Press
B.P. No.		Mis. —
Dated	21 - 12 -	1876 — 195 —

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
21st December 1876. No. 3,510.*

Read the following :—

No. 303 W.

No. 521. *Note by the Chief Engineer for Irrigation.*

THE Officiating District Engineer, Bellary, forwards, with his letter marginally noted, an estimate in connection with the Chirtapully Tank, situated in the Adoni Taluq, Ghooty Range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow :—

ORDINARY AGRICULTURAL.

Repairs.

Repairing the bund and irrigation sluice	...	...	...	Rs. 200
				Total Rs. 200

3. The following particulars of this tank are recorded—

Ayacut area	...	...	...	42 Acres	{	Circar 31	} Acres.
						Inam 11	
Assessment	...	...	...	193 Rupees	{	Circar 146	} Rupees.
						Inam 47	
Average revenue	...	...	...	114	"		
Highest do.	...	...	...	208	"		
Expenditure during the previous four years.—Not known.							

The area of the catchment basin is 1.5 square miles; the maximum flood supply is calculated at 201.6 cubic feet per second, for discharging which as surplus there is a weir 63 feet in length.

This is an isolated tank. The bund requires to be raised to a uniform height of 3 feet above the maximum water level, with side slopes of 1.5 to 1 and a top width of 4.0 feet. The revetment is out of section and needs to be repacked with gravel backing. The sluice also is leaky and requires attention. The estimate provides for raising and repairing the bund and irrigation sluice and repacking the revetment.

The estimate is recommended for sanction.

(Signed) A. M. C. SCOTT, Major, R.E.,

FORT ST. GEORGE,
18th December 1876.

*Dy. Chief Engineer for Irrigation,
for Chief Engineer for Irrigation.*

To the Secretary to Government, Public Works Department.

No. 522. ORDER THEREON, 21st December 1876, No. 3,510.

IRRIGATION, No. 4I-E.

Account.

THE following estimate from the Ghooty Range, forwarded by the Officiating District Engineer, Bellary, is sanctioned.

Proceedings of the Madras Government, Public Works Department
21st December 1876. No. 3,510.

CHIRTAFULLY TANK.
IRRIGATION.

Group or Project. —
Fund.—Ordinary Agricultural.
Class.—Repairs.
Name of Tank, Canal or Channel.—Chirtapully Tank.
Particulars of Work.—Repairing the bund and irrigation sluice.
Amount.—Rupees 200.
To be carried out by the Public Works Department officer in charge Ghooty Range.
2. This sanction has been registered as No. 217 I. of 1876-77.
(True Extract.)

Major-General, R.E.
Secretary to Government.

E. I. Form No. 9.

OFFICE OF THE CHIEF ENGINEER
FOR IRRIGATION,

Port St. George 18th December 1876.

No. 303-W.

Note by Chief Engineer for Irrigation.

Encls 5.

THE Officiating District Engineer, Bellary.

No. 2766 forwards, with his letter marginally noted, an Estimate in connection
Dated 18th Dec 1876 with the Chirtapully Tank situated in the
Adoni Taluk, Ghooty Range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow:—

Ordinary - Agricultural.
Repairs. Rupees.

Repairing the bund and irrigation
Sluice. 200.
Total Rupees 200.

3. The following particulars of this Tank are recorded—

Ayacut area. 42 Acres. — { Circar 34 } Acres.
Assessment. 193 Rupees. — { Inam 11 } Rupees.
Average revenue. 114 Rupees. — { Circar 146 } Rupees.
Highest do. 208 Rupees. — { Inam 47 } Rupees.
Expenditure during the previous four years. Not known.

The area of the catchment basin is $1\frac{1}{5}$ square miles; the maximum flood supply is calculated at 201.6 cubic feet per second for discharging which, as surplus there is a weir 63 feet in length.

This is an isolated tank. The bund requires to be raised to a uniform height of 3 feet above the maximum water level with side slopes of 1.5 to 1 and a top width of 4.5 feet. The revetment is out of section and needs to be repacked with gravel packing. The sluice also is leaky and requires attention. The estimate provides for raising and repairing the bund, and irrigation sluice and repacking the revetment.

The estimate is recommended for sanction.

Sanctioned by

and

Asst. Secy.

Asst. Secy.

Major R.

Dy. Chief Eng. for Irrig.

for Chief Engineer for Irrig.

To the

The Secretary to Govt.

P. W. D.

Gd

est/6

he
he

d

71

1876. P.W.D.
18DEC76

From
The Chief Engineer for Bridges
to
The Secretary of Gov.
N. W. D.

Dated 18.
Decr. 18. } Decr. 1896

Encls 5.

№ 303-У.

Chirtapully Jack - Seltay
Dietrich - Note recom-
-mending for sanction. Est-
-imate for Rs. 200 for repairs
to the —.

14521

Dec 19-12-26.

No. 3510

Bro

E. I. Form No. 4-A

Pro: Wm Madras Govt
Understate the 21 Dec 76.
Read the following
The Engr for light (HE No 303 W 57.18 Dec 76)

THE following Estimate from the
Gooty Range, forwarded by the
M. E. District Engineer, *Bellary*
 is sanctioned :—

Chirapully Tank.

Irrigation.

Group or Project.	Fund.	Class.	Name of Tank, Canal, or Channel.	Particulars of Work.	Amount. Rs.
—	Ordinary: Agricultural	Repairs.	Chintapully tank	Repairing the bund and irrigation sluice.	200.

To be carried out by the P. W. Department Officer in charge of the Range.

Total Rupees 200.

2. This sanction has been registered
as No. 217 I. of 1875-76.

2. This sanction has
as No. 217 I. of 1873-74.

9786

Govt. of 1876 Madras.

PUBLIC WORKS.

To

The H. B. Bellary

Dated

Issued

Recd.

Encl.

G. O., 21st Dec 1876, No. 3570

Nos. 521/22

Chirtapully Tank, Bellary
Str: - Sanctioning the
estimate of Rs 200 for
repairs to the —.

Done in Dy.