

(1) Number of pages \_\_\_\_\_

(2) Date of repair \_\_\_\_\_

(3) Initials of the Referencer \_\_\_\_\_

# MADRAS RECORD OFFICE

Government of Madras

*Public Works* DEPARTMENT

|          |      |           |
|----------|------|-----------|
| G.O. No. | 641  | (W) Press |
| B.P. No. |      | Mis.      |
| Dated    | 13.3 | 1876.     |

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,  
13th March 1876.*

No. 160. Read the following letter from Major J. N. HUNTER, R.E., District Engineer, Salem, to Major-General G. W. WALKER, R.E., Secretary to Government, Public Works Department, dated Salem, 3rd March 1876, No. 129 :—

I HAVE the honor to forward, for the sanction of Government and an assignment of funds under "Provincial New Works" in 1876-77, an estimate of Rupees 443, accompanied by a plan, for constructing a compound wall to the graveyard at Kristnagherry.

One Detailed Estimate.  
One Plan.

2. The estimate was prepared at the request of the Collector.

No. 161. ORDER THEREON, 13th March 1876, No. 641.

CIVIL WORKS, No. 16.

SANCTIONED for execution when funds may be available.

2. This sanction has been registered as Provincial, No. 20 W. of 1875-76.

(a) *Heads of Service.*—Provincial.  
*Fund.*—Ordinary.  
*Class.*—New Works.  
*Main-head.*—Civil Buildings.  
*Sub-head.*—Ecclesiastical Department, Cemeteries.  
*Name of Work.*—Compound wall for Cemetery at Kristnagherry.  
*Amount.*—Rupees 443.  
To be carried out by the Public Works Department.

(True Extract.)

(Signed) G. W. WALKER, Major-General, R.E.,  
*Secretary to Government.*

To the District Engineer, Salem.  
„ Examiner of Public Works Accounts.  
„ Ecclesiastical Department.

Exd. S. T. Austin.  
Spare Copies

Register  
29-2-75

PUBLIC WORKS DEPARTMENT.

SALEM DISTRICT, NO. II OR OOSSOOR RANGE.

Locality.

Talug.

Kristnagery

DETAILED ESTIMATE No. 84 of 1875

Work

Constructing a Compound <sup>with</sup> for the Cemetery at Kristnagery instead of the present fence.

| Details of work.                           | Measurements in feet. |       |        |                       |                  | Contents. | Total quantity of each description of works. |
|--------------------------------------------|-----------------------|-------|--------|-----------------------|------------------|-----------|----------------------------------------------|
|                                            | Length.               |       |        | Breadth or Thickness. | Height or Depth. |           |                                              |
|                                            | Number.               | Each. | Total. |                       |                  |           |                                              |
| Longitudinal walls East & West sides       | 2                     | 102½  | 405    | 3                     | 2                | 2,430     |                                              |
| North end wall                             | 1                     | .     | 53½    | 3                     | 2                | 321       |                                              |
| South — do —                               | 1                     | "     | 37     | 3                     | 2                | 222       |                                              |
| Total of ab                                |                       |       |        |                       |                  | 2,973     |                                              |
| or Cyd <sup>3</sup> of Earth work          |                       |       |        |                       |                  |           | 110                                          |
| Longitudinal walls east & west sides       | 2                     | 103½  | 407    | 2                     | 2                | 1,628     |                                              |
| North end wall                             | 1                     | "     | 52½    | 2                     | 2                | 210       |                                              |
| South — do —                               | 1                     | "     | 34½    | 2                     | 2                | 137       |                                              |
| Longitudinal walls east & west sides       | 2                     | 104   | 408    | 1½                    | 3½               | 2,142     |                                              |
| North end wall                             | 1                     | .     | 52     | 1½                    | 3½               | 273       |                                              |
| South — do —                               | 1                     | .     | 36     | 1½                    | 3½               | 189       |                                              |
| Total of ab                                |                       |       |        |                       |                  | 4,579     |                                              |
| or Cyd <sup>3</sup> of Burnt Stone in muel |                       |       |        |                       |                  |           | 169 5/7                                      |
| Coping all round                           | 1                     | .     | 496    | 1 3/8                 | ½                |           |                                              |
| Total of ab                                |                       |       |        |                       |                  | 341       |                                              |
| or Cyd <sup>3</sup> of Burnt Stone in muel |                       |       |        |                       |                  |           | 12 3/4                                       |

This estimate has been prepared by Mr. H. S. and is valid as of 1875/76.

|                                                         |   |                   |                 |   |      |
|---------------------------------------------------------|---|-------------------|-----------------|---|------|
| Plastering to the mud in stone wall                     | 1 | 993 $\frac{1}{2}$ | 2 $\frac{1}{2}$ | " | 1    |
| Total of work                                           |   |                   |                 |   | 3477 |
| or Sq <sup>rs</sup> of Plastering with 1 coat of Chumam |   |                   |                 |   | 3477 |

### Specification

The Wall to be constructed as shown in the accompanying Plan the Foundations being 2 ft deep & 2 ft broad and the Wall above 3 ft high & 1 ft thick of Kuruk stone or clay plastered with one coat of Chumam -  
a coping of brick in chumam 6 inches deep to be added.

### ABSTRACT OF THE FORGOING ESTIMATE.

| Number of Quantity. | Description of work.                                 | Rates.           |     |    |    | Amount. |    |    | Total Amount. |       |
|---------------------|------------------------------------------------------|------------------|-----|----|----|---------|----|----|---------------|-------|
|                     |                                                      | Per.             | Rs. | a. | p. | Rs.     | a. | p. | Rs.           | a. p. |
| 110                 | Cy <sup>s</sup> of Earth works excavating            | Cy <sup>s</sup>  | "   | 1  | "  | 6       | 14 | "  |               |       |
| 169 $\frac{1}{2}$   | " of Burnt Stone in Mud                              | "                | 1   | 12 | "  | 296     | 10 | "  |               |       |
| 12 $\frac{2}{3}$    | " of Bricks in Chumam                                | "                | 4   | "  | "  | 50      | 10 | 8  |               |       |
| 3477                | Sq <sup>rs</sup> of Plastering with 1 coat of Chumam | Sq <sup>rs</sup> | 1   | 8  | "  | 52      | 2  | 5  |               |       |
|                     | Removing above Hedges                                |                  |     |    |    | 15      | "  | "  |               |       |
|                     |                                                      |                  |     |    |    | 58      | 1  | 5  |               |       |
|                     | Sundries and Superintendence at present              |                  |     |    |    | 21      | 10 | 11 |               |       |

Amount of Estimate Rupees 442

C. D. Lumsden.  
Collector of Salem  
11<sup>th</sup> July 1875

A. Bailey Captain  
Executive Engineer

C. D. Lumsden.  
Collector of Salem

J. A. Stevenson Major R.E.,  
District Engineer

*Mr. T. P. ...*

(a) Heads of Service—*Provincial*

Fund. *Preliminary*

Class. *New Works*

Main-head. *Civil Building*

Sub-head. *Ecclesiastical Repts. Cemeteries*

Name of Work.  
*Confined wall for cemetery  
at Kristnagar.*

Amount. *Rs. 143*

To be carried out by the *P. W.* Department.

*14-8-76*

PUBLIC WORKS DEPARTMENT.

SALEM DISTRICT.

No. 11 ON OOSOOOR RANGE.

Locality. *Kristnagar Taluk.*

Detailed Estimate No. *574* of 1875.

Dated *14th July* }  
Received } 1875.

Work:— *Constructing a*

*Confined wall for the*

*Cemetery at Kristnagar.*

*instead of the present fence.*

Amount of Estimate Rupees. *Rs. 143*

No. 127

From

District Engineer's Office,  
Salem 3<sup>d</sup> March 1876.

The District Engineer  
of Salem

To

The Secretary to Government  
D. P. W.

Enclosures 2

1 Detailed Estimate

1 Plan.

Sir, I have the honor to forward  
for the sanction of Government and  
an Assignment of funds under  
"Provincial New Works" in 1876-77  
an estimate of Rupees 443 accompanied  
by a plan for constructing a compound  
wall to the Grave yard at Kistnagiri.

2. The estimate was prepared  
at the request of the Collector.

I have the honor to be,

Sir,

Yours Most Obediently,

J. W. B. M. Major, R.E.,  
District Engineer.

*[Faint handwritten notes at the top left of the page]*

*[Faint handwritten notes in the middle left of the page]*

160 - 161

Cin 8-2-76

M. H. 1876 Oct  
 The District Engineer  
 To the Secretary of the Government  
 Dated 3<sup>rd</sup> March 1876  
 Received 65

No. 641 of 13<sup>th</sup> March 1876  
 Sanctioned for execution when funds may be available

This sanction has been registered as Provincial No. 20 W. of 1875-76-

D. E. Salem ✓  
 Secy to the Secy. ✓  
 Secy Dept. ✓  
 Recd - 21-3-76

1846  
Capt. of 1876 Madras.

PUBLIC WORKS.

To

The St Engineer  
Salem

15/3

Dated

Issued

Recd.

Encl.

G. O. 13 March 1876. No.

641

Nos. 160-161

Continued with the same  
ground at Sittapherry,  
Salem Dist. — Estimate  
of Rs 443 for constructing  
a — — — — — sanctioned for  
execution, when funds are  
available.