

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No.	773	(9)	Press
B.P. No.			Mis.
Dated	27.3		1876

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
27th March 1876.*

Read the following:—

No. 12 W.

No. 423. *Note by the Chief Engineer for Irrigation.*

THE District Engineer, Cuddapah District, forwards, with his letter marginally noted, an estimate in connection with the No. 2,305, dated 12th February 1876. Muttayobal Reddy Cheravoo tank situated in the Royachoty taluq, Madanapully range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow:—

Raising and strengthening the bund and repairing the sluice and existing weir—Revenue Repairs	rs. 236
Extending the existing weir 59 feet—Revenue Extensions	224
Total ...	460

3. The following particulars of this tank are recorded:—

Ayacut area	Acres 26
Assessment	Rupees 55
Average revenue	42
Highest do.	58
Expenditure during the previous four years	100

The area of the catchment basin is $4\frac{1}{2}$ square miles; the maximum flood supply is calculated at 1,089 cubic feet per second, for discharging which, as surplus there is one rough stone weir 51 feet in length, and an escape 50 feet in length; it is proposed to close the latter and extend the former 59 feet in addition to its present length, making in all a length of 110 feet available for the surplus discharge.

This tank is the head of a series of four, and it is necessary to incur the proposed expenditure which is very large compared with the revenue in order to secure the lower tanks. But the particulars of the revenue, &c., of the other tanks might in such cases well be given and the circumstances of the whole series discussed.

FORT ST. GEORGE,
17th March 1876.

(Signed) A. DEC. SCOTT, Major, R.E.,
Depy. Chief Engineer for Irrigation,
for Chief Engineer for Irrigation.

No. 424. ORDER THEREON, 27th March 1876, No. 773.

IRRIGATION, No. 40.
Account.

THE following estimate from the Madanapully range, forwarded by the District Engineer, Cuddapah, is sanctioned:—

(1) Raising and strengthening the bund, repairing the sluice and weir; and (2), extending the existing weir of the Muttayobal Reddy Cheravoo tank—	rs.
(1.) Revenue Repairs	236
(2.) Do. Extensions	224
Total ...	460

Proceedings of the Madras Government, Public Works Department,
27th March 1876.

2. This sanction has been registered as Irrigation, No. 65 I. of 1875-76.
(True Extract.)

Major-General, R.E.,
Secretary to Government.

To the District Engineer, Cuddapah.
" Collector of do.
" Chief Engineer for Irrigation.
" Examiner of Public Works Accounts.
" Revenue Department.

I. Form No. 9.

OFFICE OF THE CHIEF ENGINEER

FOR IRRIGATION, 17th March 1876.

No. 12 W

Note by Chief Engineer for Irrigation.

THE District Engineer, Cuddapah District

2305 forwards, with his letter marginally noted, an Estimate in connection
2 Feb/76 with the *Muttysabal Reddycheram* Tank situated in the
by 10. *Royachoty* Taluq, *Madanapully* Range.

2. The nature of the work proposed for execution and the heads of account
to which it is chargeable are as follows:—

*Raising & strengthening the bund
repairing the sluice and
existing weir. Revenue Repairs* } Rs. 236.
*Extending the existing weir 59 feet
Revenue Extensions* } 224
Rupees - 460.

3. The following particulars of this Tank are recorded—

Ayacut area. 26 Acres.
Assessment. 55 Rupees.
Average revenue. 42 Rupees.
Highest do. 58 Rupees.
Expenditure during the previous four years. 100 Rupees.

P. W. 1876 Dept

No 2013

From
The Chief Engrs
for Irig:

No 12W

Dated 17 3 March 1876
Recd 18 3

L. 10

Note on Estimate
for certain repairs to
the Muttigobal Reddy bheram
Tank, Buddapah Dist.

40 773

Pd 27 March 76 W 223

Ar. 21-3-76

No 773
Pto. of the Madras Government.
Under date the 27th March 76.
Read the following:

From
The Chief Engineer } (N.E. No 128 of 14th March 76)
for Irrigation }

The following estimate
from the Madanapally
Range, forwarded
by the District Engineer,
Buddapah, is sanc-
tioned.

(1) Raising & strengthening
the bund, repairing the
sluice and weir, & ex-
tending the existing
weir of the Muttigobal
Reddycheravoo Tank.

(1) Revenue Repairs Rs. 236.

(2) - " - Extensions - 224.

Total Rs. 460.

D. Eluddapah 5

Collector do 5

Ch. E. for J. S. with 10

Ex. P. W. do 5

Recd. - Sept. 15

Cut. 17

2. This sanction has
been registered as
of 1875-76.

65 I- Enclos- Adul 8

How 17 to 7-2-76

Amr

213 ✓
Govt. of 1876 Madras.
PUBLIC WORKS.

To

Mr H. E. Kandappa

Dated

Issued

Recd.

Encl.

G. O. 27th March 1876, No.

773

Nos. 423/4

Muttial Reddycharru
Cuddalore Dist
Estimate of Rs 460 for
improving the —————
Sanctioned

18-4-76