

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE

Government of Madras

Public Works DEPARTMENT

G.O. No.	859	(W)	Press
B.P. No.			Mis.
Dated		1-4-	1876

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
1st April 1876.*

Read the following papers :—

- No. 11. From Colonel W. A. CROMMELIN, R.E., Deputy Secretary to the Government of India, Public Works Department, (Military Works,) to Major-General G. W. WALKER, R.E., Secretary to the Government of Madras, Public Works Department, dated Fort William, 18th January 1876, No. 85 M.W. :—

REFERRING to your letter, No. 3,194, dated the 8th November 1875, submitting plans and an estimate, amounting to Rupees 13,400, for the construction of a Lock Hospital at Wellington, I am directed to point out that no data are given to show the extent of accommodation really required in the Hospital, and to request that statistics may be submitted showing the maximum number of patients in any one day of each year since the rules in regard to them came into operation at Wellington, and also the maximum number of women on the register.

2. With regard to the proposed building, I am to intimate that its character is considered more substantial and expensive than is at all necessary; chunam pointing, teak flooring, and cut granite stone are not required for a Lock Hospital, nor should it be necessary to provide a peon with quarters at a cost of Rupees 1,500.

3. I am further to remark that no building, however excellent, will assist in preventing venereal disease among the troops. The great difficulty is to bring under surveillance the women who cause disease, and this is a difficulty which is in no degree met by having a fine building for a Lock Hospital. At a time, moreover, when the advisability of continuing the preventive measures is open to much question, all unnecessary expenditure on Lock Hospitals should be avoided. In most stations a few native huts with an enclosing wall should answer every purpose, and where better accommodation is desired it should be provided by Cantonment Committees out of the funds at their disposal. Were such buildings as those proposed for Wellington generally provided for Lock Hospitals, a very large expenditure would be necessitated which might be devoted to much more important sanitary works.

4. With reference to the foregoing remarks, I am to intimate that the Government of India is not disposed to grant so large a sum as Rupees 13,400 for a Lock Hospital at Wellington for so small a number as sixteen patients. The existing building, if improved, might probably be made to answer every purpose, as all that is said against it is that its position is considered most objectionable and its accommodation defective.

- No. 11-A. From the District Engineer, Nilgiris, dated 13th March 1876, No. 77.

- No. 12. ORDER THEREON, 1st April 1876, No. 859.

MILITARY WORKS, No. 1.

COMMUNICATED to the Military Department.

2. Under the opinions so decidedly expressed by the Government of India, it is remitted for consideration whether the original estimates alluded to in Military Department Order, No. 823, of 11th March 1874, may not be approved and carried out.

Proceedings of the Madras Government, Public Works Department,
1st April 1876.

3. One of Rupees 2,950 in amount (by reduction of the item for sundries) appears to provide for a high teakwood railing and gate in front of the Hospital, and for a brick wall round the three other sides, and for a verandah in rear covered with corrugated iron, and enclosing a surgery and bath-room. The other amounting to Rupees 2,250 provides for a Dresser's house just outside the gate.

(True Extract.)

To the District Engineer, Nilgiris.
" Military Department.

— Detailed Estimate No 77 of 1876-76 —

— Nilgiris District —

work.

Cost of additions to the Lock
Hospital at Wellington

no measurements
L B & Contents

Particulars

— Brick in Chumam —

1	55-6	2-0	2-6	277-6	Foundation to longitudinal wall of Verandah
4	7-0	2-2	2-6	151-8	End and cross walls
1	55-0	1-6	5-6	453-9	Basement to longitudinal wall of Verandah
1	7-6	1-8	4-6	225-0	End and cross walls
84	4	1-8	1-6	210-0	Foundation to rear enclosure wall
73	6	1-8	1-6	367-6	Side walls
16	6	1-2	1-0	38-6	Around doors of Surgery & Bath room
10	0	1-2	1-0	23-4	Windows
8	6	1-2	1-0	39-8	Top of triangular pieces to end & cross walls
11	9	1-2	1-0	27-5	Rear wall
231	4	1-2	1-0	270-1	Coping of enclosure walls all round
1	2	1-2	2-0	35-0	Around foot of uprights to front Paving
1	6	0	4-6	162-0	Steps including foundation
2	5	6	1-2	1-6	19-3 Flat archwork over doors

2300-8 Total cft. of Brick in Chumam

— Brick in mud —

1	83	6	1-2	7-0	681-11	Rear enclosure wall exclusive of coping
2	73	9	1-2	7-0	1204-7	Side walls
2	11	9	1-2	6-6	178-1	Rear walls in verandah
4	8	0	1-2	6-6	242-8	End and cross walls
4	8	0	1-2	1-0	37-4	Triangular pieces

2344-7 Total

290-6 Deduct

2054-1 Total cft. of Brick in clay

Plastering

1 24-9 . 6-6 160-10 1/2 Interior of Surgery
 1 24-9 . 6-6 160-10 1/2 Bath room
 1 54-6 . 5-6 299-9 Rear Basement
 2 9-9 . 5-6 107-3 End
 2 11-9 . 6-0 141-0 Rear walls of Bath room and Surgery
 2 9-6 . 7-0 133-0 End
 2 9-6 . 7-0 133-0 Crops
 2 6-6 . 5-0 65-0 Sides of steps including coping
 1 24-1-9 . 420-0 Coping to enclosure wall
 1620-9 Total
 82-9 Deduct
 1538-0 Total square feet of Plastering

1538 sq ft. of white washing

1 83-6 . 7-0 584-6 Exterior of rear wall of enclosure
 2 75-6 . 7-0 1057-0 Side
 1 80-6 . 7-0 563-6 Interior of rear
 2 74-0 . 7-0 1036-0 Side
 3241-0 Total sq ft. of Chumam Painting

1 8-9 20 . 70-0 Surgery
 1 8-9 8-0 . 70-0 Bath room
 2 3-0 1-3 . 7-6 doorways
 1 32-6 8-0 . 260-0 Verandah
 1 7-0 4-0 . 28-0 Steps
 1 32-6 1-6 . 48-9 Between Pillars
 484-3 Total sq ft. of flooring with square bricks

Inches

3 9-0 4 1/2 2 1/2 2-1-3-9 Principal rafters to Verandah
 1 32-6 4 1/2 2 1/2 2-8-11-7 Breezsummer
 2 12-9 4 1/2 2 1/2 1-11-6-10 Wall plate to Surgery & Bath room
 2 56-6 4 1/2 2 1/2 7-0-2-0 to eaves of old building
 3 2-0 6 4 1-0-0-0 Corbels to support wall plate at eaves

Inches

3 1-6 4 3 1/2 0-5-3-0 Feet to Verandah wooden pillars
 2 1-6 4 3 1/2 0-5-3-0 Caps to
 6 6-6 4 3 3-3-0-0 uprights to
 2 56-6 2 1/2 1 1/2 3-11-0-8 Battens to fasten iron
 2 18-0 4 3 3-0-8-0 window frames
 2 18-6 4 3 3-1-0-0 door
 2 3-6 6 1/2 1 1/4 4-8-10-1 doors
 4 3-6 3 1/2 1 0-4-1-0 stiles to windows
 4 3-0 3 1/2 1 0-3-6-0 Sash and bottom rails to windows
 8 3-0 1 1/2 1 1/2 0-4-6-0 Sash lines to windows
 2 5-0 1 1/2 2 2-6-0-0 Lintels over windows
 6 3-0 3 1 1/4 0-5-7-6 Battens to door
 10 8-0 5 4 11-1-4-0 Uprights to Front Paving
 3 75-6 5 2 1/4 5-11-9-4 Crops pieces
 2 6-0 4 2 1/2 0-10-0-0 stiles to gate
 2 5-0 4 2 1/2 0-8-4-0 crops pieces to gate
 2 5-0 4 2 1/2 0-8-4-0 diagonal pieces to gate
 130 6-0 3 1 1/2 24-4-6-0 Rails to Paving
 9 6-0 3 1 1/2 1-8-3-0 Rails to gate
 83-10-8-2 Total

29-1-3-10 Wash

103-0 Total cft of Teakwood wrought and put up

33 Shells corrugated iron 8 ft.
33 " " 6 ft.
8 3 ft iron bolts with nuts
3 1 1/2 ft iron bolts with nuts
3 9 inch
12 8 inch
70 6 inch

1 56-6 12-0 . 678-0 Iron on roof
 678-0 sq ft. of painting 3 coats

1 80-6 . 6-0 483-0 Palings
 483-0 Total cost of Laming
 231-6 Cost of broken glass on enclosure wall
 1 Lock to surgery
 1 Lock to gate
 4 lbs of Iron for Hinges
 10 lbs of Iron for gate Hinges
 107 C. yds of Excavation and Filling in &c

— Abstract Estimate No 77 of 1875-76 —

— Nilgerry District —

Work. Cost of additions to the Luck Hospital
 at Wellington

No	Particulars	Rate	Per Amt	Total
2301	Cft. of Brick in chunam	40	100	920 64
2345	Cft. of Brick in clay	24	100	562 129
1538	Sqft of Plastering	8	100	123 7
1538	Sqft. of white washing	8	100	7 11
3241	Sqft. of chunam Pointing	5	100	162 9
484	Sqft. of flooring with 1 ft. sq. bricks	28	100	135 83
103	Cft. of Teakwood wrought & put up	4	100	4 12
33	8 ft. sheets corrugated Iron including fixing	5 8	100	181 8
33	6 ft	4 8	100	14 8 8
8	3 ft. Iron bolts with nuts	12	100	6
3	1 1/2 ft	6	100	1 2
3	9 ftches	4	100	12
12	8 inches	3	100	2 4
70	6 inches	26	100	10 15
678	Sqft. of Painting 3 coats	7 8	100	50 137
483	Sqft. of Laming	3	100	14 7 10
231	Running feet of fixing broken glass	2	100	28 14
1	Lock to surgery		100	6

1 Lock to gate 2 8
 14 lbs of Iron for Hinges &c 4 lbs 3 8
 107 C. yds of Excavation & Filling in &c 4 C. yds 26 12
 Total 2807 81

Surplus 2827 4

Total 3090

add cost for constructing Dispensary as per Est.

No 72 of 1875-76 2348

Total Estimate Rupees 5438

— Specification —

Foundations, Basement, Flat archwork, 1 foot below top of walls, around doors and windows, steps and coping to compound walls to be of Brick in chunam, the rest of Brick in mud, the building to be plastered inside and outside with chunam and both sides of compound walls to be pointed with chunam, the additions to be white washed. Flooring to be of 1 foot square bricks, woodwork to be of Teak. A Teakwood railing with gateway will run in front of the Building joining the extremities of the compound wall as shown on plan.

St. Surg. Officer
 Nilgerry
 Coimbatore 13th March 1878

— J. C. Morant —
 Captain R. E.
 District Engineer

PW 19/13/76

— Detailed Estimate No 78 of 1875-76 —

— Kilgenny District —

Work

Cost of constructing Draper's quarters adjacent to the Lock Hospital at Wellington

Measurements
No. 2 1/2 3 & Contents

Particulars

— Brick in Chumaw —

4	2-2	2-2	2-0	37-7	Foundation to Pillars
1	4-0	4-0	2-6	40-0	Chimney
1	96-0	2-2	2-0	416-0	walls
2	3-0	1-8	2-0	20-0	retaining walls
3	4-6	1-8	2-0	45-0	
4	1-8	1-8	1-0	11-1	Basement to Pillars
1	3-6	3-6	1-0	12-3	Chimney
1	98-0	1-8	1-0	163-4	walls
2	3-6	1-2	1-0	8-2	retaining walls
3	5-0	1-2	1-0	17-6	
4	1-2	1-2	7-0	38-1	Pillars above Basement
1	3-0	3-0	18-0	162-0	Chimney
1	5-6	2-0	9-6	5-6	Steps
1	126-6	1-2	1-0	147-7	top of walls
1	112-0	1-2	0-9	98-0	round openings

1222-1 Total cft of Brick in Chumaw

— Brick in mud —

1	100-0	1-2	10-0	1166-8	walls above Basement
3	11-6	1-2	2-0	80-6	fables
2	3-6	1-2	1-6	12-3	
1	5-0	1-2	15-0	87-6	Partition wall

1346-1 Total

249-1 deduct

1097-0 Total cft of Brick in mud

Plt 1st Apr 76 PW 11

28 Squares of Plastering
 28 Squares of color washing
 Flooring

1 10-0 10-0 100-0 } Rooms
 1 10-0 8-0 80-0 }
 180-0 Total sqft of Teak wood flooring

1 17-8 4-0 78-8 verandah
 78-8 Total sqft of flooring with 1 ft. sq. bricks

1 5-4 4-4 21-8 Total sqft of asphaltic flooring

21-8 Total sqft of flooring with earth well rammed

1 29-0 18-0 522-0 Rooms

1 22-6 7-0 157-6 verandah

679-6 Total sqft of roofing with teakwood
 reapers, flat and Pantiles &c

1 22-6 4 6 3-9-0 Pressumer

2 30-0 5 3 6-3-0 Purlins

2 29-0 4 2 3-2-8 wall plate

1 29-0 6 3 3-7-6 ridge piece

40 9-6 4 2 1/4 23-9-0 Rafters

16 9-6 4 2 1/4 9-6-0

50-1-2 Total

11-10-10 waste

62-0-0 Total cft of Teakwood wrought and put up

2 3-6 6-6 45-6 doors

2 2-6 4-0 20-0 windows

2 2-0 2-0 8-0

73-6 Total sqft of glazed doors & windows

42-6 1 6-0 60-0 doors

18-0 6-6 19-6

79-6 Total sqft of batten doors

Abstract Estimate No 78 of 1975-76

Nilgheem District

Work - Cost of constructing repairs quarters adjacent to
 the Lock Hospital at Wellington

Qty.	Particulars	Rate Per	Ant	Total
1222	cft of Brick in chumam	40	100	488 12 9
1097	cft of Brick in clay	24	263	45
28	sqrs of Plastering	8	224	
28	sqrs of color washing	8	14	
180	sqft of Teakwood flooring &c	102	183	9 7
79	sqft of flooring with 1 ft. sq. bricks	28	22	1 11
22	sqft of asphaltic flooring	75	16	8
22	sqft of flooring with earth well rammed	2 8	89	
679 1/2	sqft of roofing with Teakwood reapers, flat and Pantiles &c complete	65	441	10 9
62	cft of Teakwood wrought & put up	4	248	
73 1/2	sqft of glazed doors and windows	2	147	
79 1/2	sqft of Batten doors	1	79	8
	Excavating foundations &c		6	

Total 2135.2

Sundries 204 15 10

Total Estimate Rupees 2340.

The building consists of 2 large rooms 10x10' and 10x8' respectively, one Bath room and a closet 5x4x4' each. Foundation and Basement to Pillars, retaining walls, chimney, top of walls below roof and round opening bce of Brick in chumam, the rest of Brick in mud

Plastered and coln washed; the two large rooms to be
 floored with Teakwood, Bath room with asphalt, closet
 with with earth well rammed and the W.C. with
 1 1/2 sq bricks; the roof to be of Teakwood rafters, Purlin
 ridge pole, wall plate, flat and Pan tiles with
 Chumam borders —

PW 19/3/76
 3

1st Engr's Office
 Nilgiris
 Coimbatore 13th March 1876
 Memorant
 Captain R. E.
 District Engineer

Imperial — Abstract Estimate No 77 of 1875-76 — Military
 Nilgiris District — Original
 Work - Cost of additions to the Lock Hospital
 at Wellington

No	Particulars	Rate	Per Amt	Total
2381	cft. of Brick in chumam	40	.. mps	920 64
2345	cft. of Brick in clay	24	..	562 129
1538	sqft. of Plastering	8	.. sqe	123 7
1538	sqft. of white washing	8	..	7
3241	sqft. of chumam Pointing	5	..	162 9
484	sqft. of flooring with 1ft. sqe bricks	28	..	135 83
113	cft. of Teakwood wrought and put up	4	.. cft	412
33	8ft. sheets corrugated Iron including filly	5	8.. mch	181 8.
33	8ft. "	4	8..	148 8.
8	3ft. Iron bolts with nuts	12	..	6
3	1 1/2 ft. "	6	..	1 2.
3	9 inches "	4	..	12.
12	8 inches "	3	..	2 4.
70	6 inches "	26	..	10 15.
678	sqft. of Painting 3 coats	7	8.. sqe	50 137
483	sqft. of Lining	3	..	14 7 10
231	sqft. of fixing broken glass &c	2	.. sqft	28 16.
1	Lock to Surgery	..	..	6
1	Lock to gate	..	..	2 8.
14	lbs of Iron for Hasps & Shingles &c	4	.. lbs	3 8.
107	C. yds of Excavation &c	4	.. c. yds	26 12.
Total				2807 81
sundries				2827 2950
addent for constructing repairs quantities as per Est. No 73 of 1875-76				2340
Total Estimate Ruben				5430

Ph 1st April 76 PW 11

James Morant P.W. 1913/76

Captain R. E.

District Engineer

St. Engineer's Office
Nailghensis
Botacaim 13th March 1875

Ph 1st AM 16 03N 11

Abstract Estimate No 78 of 1875-76
Nailghensy District

Cost of Constructing Depens quarters adjacent to the Lock Hospital at Wellington

Qty Particulars Rate Per Amt Total

1222	cft. of Brick in chumam	40	100 cft	488 12 9
1097	cft. of Brick in clay	24		263 4 5
28	sqrs of Plastering	8	sq	224
28	sqrs of color washing	8		14
180	sqrs of Teakwood flooring &c	102		1839 7
79	sqrs of Flooring with 1 ft. sq bricks	28		22 1 11
22	sqrs of Asphalte flooring	75		16 8
22	sqrs of flooring with earth well sand	28		89
67 1/2	sqrs of roofing with Teakwood & paper flat and Pan tiles &c	65		441 10 9
62	cft. of Teakwood wrought & put up	4	cft	248
73 1/2	sqrs of glazed doors and windows	2	sq	147
79 1/2	sqrs of Rattan doors	1		79 8
	Excavating foundations			6

Total 2135. 2

Dundries 100 224 15 10

Total Estimate Rupees 2250 2340

James Morant

Captain R. E.

District Engineer

St. Engineer's Office
Nailghensis
Botacaim 13th March 1876

19/3/76

District Engineer's Office
Catacomund 13th March 1876

No. 77
From

The District Engineer
Nilpheries

The Chief Engineer
P. W. Department
Madras.

with reference to memo
No. 380 of the 25th Ultimo, I have
the honor to forward the Plans
and Estimates for improvements
to the Lock Hospital at Wellington,
therein called for.

I have the honor to be
Sir
your most Obedt. Servant
J. Morant Captain R. E.
District Engineer

Pl. 1st Apr 76 BR 11

16

12

12

1

Military Works.

To,

The Secretary to the Govt. of Madras.
Public Works Deptt.

Fort William 18th January 1797

Sir,

Referring to your letter No 3194 dated the 8th November 1875, submitting plans and an estimate amounting to Rs 13,400/- for the construction of a Lock Hospital at Wellington, I am directed to point out that no data are given to shew the extent of accommodation really required in the Hospital, and to request that statistics may be submitted showing the maximum number of patients in any one day of each year since the rules in regard to them came into operation at Wellington, and also the maximum number of women on the Register.

2.

2. With regard to the proposed building, I am to intimate that its character

1

21st 1913. Ant. Graham

To Mr. Swift (our inner)
20 N. 4th St.

1875

Adm'd 13th } Jacob 1878
Dec 2/8

Enclosed A-

Adelphi

Friends Lane

Notwithstanding for me.

Provincendo de Ocaso

Worship at Wallingford,
on 18th Dec in presence of

Callad for us again
#1 ordered at 380.

P. 1st April 16 or 11 A-

is considered more substantial and expensive than is at all necessary. Chumam pointing, Teak flooring, and cut granite stone, are not required for a Lock Hospital, nor should it be necessary to provide a person with quarters at a cost of Rs 1,500/-

3. I am further to remark that no building however excellent will assist in preventing venereal disease among the troops. The great difficulty is to bring under surveillance the women who cause disease, and this is a difficulty which is in no degree met by having a fine building for a Lock Hospital. At a time moreover when the advisability of continuing the preventive measures is open to much question, all unnecessary expenditure on Lock Hospitals should be avoided. In most stations a few native huts with an enclosing wall should answer every purpose, and where better accommodation is desired it should be provided by Cantonment Committees out of the funds at their disposal. Were such buildings as those proposed for Wellington generally provided for Lock Hospitals a very large expenditure would be necessitated which might be devoted

devoted to much more important sanitary works.

With reference to the foregoing remarks I am to intimate that the Government of India is not disposed to grant so large a sum as Rs 13,400/- for a Lock Hospital at Wellington for so small a number as 16 patients. The existing building if improved might probably be made to answer every purpose as all that is said against it is that its position is considered most objectionable and its accommodation defective.

I have the honor to be,
Sir

Your most obedient servant,

Mumukshu Coll. R. E. Esq.
Deputy Secy. to the Govt of India

149 9 17 - March 74
 - 1116 - 20 April 75
 - 218 - 21st June "
 - 2263 - 5 Aug "
 - 3152 - 8 Nov "
 - 3154 - 8 Nov "
 Memo: No 298 8 16/3/75
 - 91 - 19/6/75
 - 380 - 25/2/76

P. W. 1876 Defts
 No 571

From The Govt of
 India

Chngs No 380 dt 25-2-76

Dated 18th 3rd Jan 76
 Recd 24th 3rd Jan 76

No 85. M. T.

Remarks on the pt.
 for constructing a Lock
 Hospital at Wellington

Pl 1st Apr 76 PM 11

16-339-3-76 12-4-76

26-4-76

No 571

No 380.

Memo.

102

The Chief Engineer has the honor to
 request the District Engineer Melchior
 to forward the Plans for improvements
 to the Lock Hospital at Wellington,
 for which he furnished approximate
 estimates with his letter to the
 Commandant, No 151 of 26th
 August 1873.

For Sent Encl. / Signed G. W. Walker Major R.E.
 25th February 1876. Chief Eng. R.E.W.

To The District Engineer Melchior

of
 21
 bears

1116

Chargers No 380 d/25.2.76

Ph 1st M 76 OR H

13
The objections to making
certain alterations in the
Loth Hospital at Wellington
to act to prevent soldiers getting
access to the women - came
from the Military authorities.
They properly objected to the
site of the Hospital as it was
near the barracks & thought
it much better to build an
entirely new Hospital.

The Govt of India object to the
cost. I think we must therefore
revert to the original suggestion
to the best we can with
the existing building -
at a cost of about 5,500 Rs.

This provides for the ~~apothecary~~
apothecary residing on the
premises. Some means
of guarding the premises
either by a Military Sentry
or by Police - seem absolutely
required ~~in addition~~ of the ~~detention~~
confinement, as formerly reported.
The necessity for putting
the Lock Hospital in a
proper condition is urgent.

I think these papers had
better go to R.E. Murphy
in Chief, and if he agrees
we had better go up to
Murphy of India with the
smaller estimate & they
will probably sanction.
20/2/76 R.E.

building an enclosure
wall - & providing housing -

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Read the following:—

From the fort of India (K.E. No 85 in W 278 Jan 1866)

Lock Hospital
Wellington

Communicated to the Military Dept.

Under the opinions so decidedly expressed by the Government of India it is manifest that the subject of improving the existing Lock Hospital accommodation at Wellington must be dropped.

Law

Atty

Pl 1. PM 26 BW 11

3-20-1945

57

[Faint handwritten notes, possibly "M. L. 11" and "M. L. 11"]

[Faint handwritten notes]

[Faint handwritten notes]

[Faint handwritten notes]

[Faint handwritten notes]

[Faint handwritten notes]

[Faint handwritten notes]

[Faint handwritten notes]

[Faint handwritten notes]

[Faint handwritten notes]

[Faint handwritten notes]

[Faint handwritten notes, possibly "The report of the Military Department"]

[Faint handwritten notes, possibly "M. L. 11"]

No 859

Public Works Department

PROCEEDINGS of the MADRAS GOVERNMENT.

UNDER date the 1st April 1876

Read the following:—

From

The Government of India (M. No 85 M.W d/18th Jan'y/76)

The District Engineer } (M. No 77 d/13th Mar/76)
 Nilghevica

Communicated to the Military Department

2. Under the opinions so decidedly expressed by the Government of India, it is remitted for consideration whether the original estimates alluded to as Military Department Order No 823 of 11th March 1874, may not be approved and carried out.

3. One of Rs 2950 in amount (by reduction of the item for sundries) appears

Ph 1st Apr 76 NW 11

Recd 3-2-76

Gr 26-1-76

26-1-76

6/2/76

[Handwritten signature]

appears to provide for a
 high teakwood railing
 and gate in front of the
 Hospital, and for a
 brick wall round the
 3 other sides; and for a
 Verandah in rear covered
 with corrugated iron,
 and enclosing a surgery
 and Bathrooms. The
 other amounting to
 Rs 2250 provides for a
^{house} Driveway just outside
 the gate.

[Faint handwritten notes, possibly "G.M." and "11/12"]

Govt. of 1876 Madras.
 PUBLIC WORKS.

To the M. E. Keilgham

3/4/76

Dated
 Issued
 Recd. Encl
 G. O. 1st April 1876, No. 859
 Nos. 11-12

Lock Hospital at Wallingford
 — Letter from the Govt
 of India recommending the
 plans submitted for construction
 — and — committed
 with sanction to the
 Military Dept.

J. S. Keilgham Esq.
 Military Dept.
 Dec 15/4/76