

(1) Number of pages \_\_\_\_\_

(2) Date of repair \_\_\_\_\_

(3) Initials of the Referencer \_\_\_\_\_

## MADRAS RECORD OFFICE.

Government of Madras.

*Public Works* DEPARTMENT.G.O. No. 1138 (W) Press  
Mis. \_\_\_\_\_

Dated 4-4-1877.

Not to be folded or roughly handled

Read the following papers:—

No. 79. From J. O'SHAUGHNESSY, Esq., District Engineer, Nellore, to the Acting Joint Secretary to Government, Public Works Department, dated Nellore, 7th February 1877, No. 187.

I HAVE the honor to submit, for the sanction of Government, plan and estimate of a bungalow and out-houses proposed to be built at Ongole for the Assistant Superintendent of Police of this district.

|                         |                                    |
|-------------------------|------------------------------------|
| 1 Plan of Bungalow.     | 2. The plan is in accordance with  |
| 1 do. of Out-buildings. | the standard circulated with G.O., |
| 1 Site Plan.            | No. 518, dated 20th March 1875.    |
| 1 Detailed Estimate.    |                                    |
| 2 Abstract Estimates.   |                                    |
| 2 Specifications.       |                                    |

3. The Superintendent of Police informs me that funds are not likely to be available for the work in 1877-78, but he wishes to have sanction obtained now to carry out the work when funds become available for it.

No. 606.

RETURNED to the District Engineer, Nellore, for submission to Government through the Inspector-General of Police.

FORT ST. GEORGE,  
8th March 1877.

(Signed) W. FAREWELL, Colonel,  
Acting Chief Engineer, P.W.D.,  
Buildings and Roads Branch.

No. 340.

SUBMITTED to Government through the Inspector-General of Police, as directed in No. 606, dated 8th March 1877, from Acting Chief Engineer, Buildings and Roads Branch.

(Signed) J. O'SHAUGHNESSY,  
District Engineer, Nellore.

11th March 1877.

No. 79-A. From Lieutenant-Colonel C. S. HEARN, Inspector-General of Police, to the Acting Joint Secretary to Government, Public Works Department, Building and Roads Branch, dated Madras, 19th March 1877, No. 1,306.

ADVERTING to the Nellore District Engineer endorsement,\* of the 11th instant, No. 340, on his letter, dated 7th February

\* Forwarded herewith with the enclosures. last, to Government, I have the honor to recommend that the plan and estimate, &c., (Rupees 7,470) for the Assistant Superintendent's bungalow at Ongole, Nellore District, which it will be seen have been already countersigned by me may be sanctioned with the view of commencing the work whenever funds become available for the purpose.

2. No provision for the above work can be made in 1877-78, owing to the limited grant for hutting and building during that year, unless a special allotment is sanctioned.

3. From the accompanying letter No. 236, dated 23rd May 1876, received from the Superintendent of Police, Nellore, it will be observed that a building of the description at Ongole is an urgent necessity.

No. 80.

ORDER THEREON, 4th April 1877, No. 1,138.

CIVIL WORKS, No. 8.

HIS GRACE the Governor in Council sanctions the estimate of Rupees 7,470 for constructing a residence for the Assistant Superintendent of Police at Ongole on the standard plan.

2. There are at present no funds available for the work.

3. This sanction has been registered as Provincial No. 1-W of 1877-78.

Fund.—PROVINCIAL SERVICES.

Class.—Civil Buildings.

Main-head.—Original Works.

Head.—(32), Police Buildings.

Project of which the work forms part.—Residence for Assistant Superintendent of Police at Ongole.

Work.—Constructing a residence for the Assistant Superintendent of Police at Ongole.

Amount.—Rupees 7,470.

To be carried out by the Public Works Department.

(True Extract.)

(Signed) W. FAREWELL, Colonel,  
Acting Joint Secy. to Govt., P.W.D.,  
Buildings and Roads Branch.

To the District Engineer, Nellore.  
" Examiner of Public Works Accounts.  
" Inspector-General of Police.  
" Judicial Department.

Exd. E. C. Shunker.  
Spare Copies

*I have not seen the plan of the house - there might be two or three - but I will make the work more*

Office of the Superintendent of Police  
Nellore 25 May 1876

From  
The Superintendent of Police  
Nellore

To  
The Inspector General of Police  
The Deputy Inspector General of Police  
C. R.

Sir,  
I have the honor to submit plan and estimate for a house

and outbuildings for the Assistant Superintendent of Police at Ongole prepared by the D. P. W. amounting to Rs. 7,470.

The best left house at Ongole is worse than an Irish cabin. 2. This building is urgently required as there is no house available at Ongole at all suitable for the occupation of a European. I request you will be so kind to provide for it as early as possible.

I have the honor to be  
Sir

Sir  
Your most obedient servant

Jos. Charles Laplanche  
Superintendent of Police

P.W.D.  
21 MAR 77  
NO. 3051

Nellore

Submits plan & estimate  
for a house & outbuildings  
of 1000 sq. ft. of Police at  
Nellore and requests to provide  
for it as early as possible

No. 236  
Enclosed 11.  
Subject.

The Inspector General  
of Police  
Nellore

Received from the  
General of Police at  
Nellore 10th March  
1877 No. 1306.

23rd April 1877

Specification to accompany the estimate  
for constructing the stable in connection  
with the proposed Bungalow for the Assistant  
Superintendent of Police at Ongole in the  
Nellore District.

The foundations to be of Rough stone  
in Hydraulic mortar 2 ft. in depth and 2 ft.  
in breadth and that of the Pillars in the  
Centre 3 ft. in breadth. The whole of the  
foundations to rest on a bed of concrete  
1 foot in thickness. The concrete to be made  
with Hydraulic mortar and kept moist  
for 15 days after it is laid in the  
foundations.

The superstructure walls to be 1-6  
in breadth and 7-0 in height. The Pillars  
going up to Ridge in the Centre to be  
2 ft. square and 13 feet in height. The  
front pillars to be 1-6 square and 7-0 in  
height. The gables over end walls to be 1-6  
in thickness and built up to ridge.  
The roof to consist of country reapers,  
pantiles and to be finished off.

with chumam borders. The internal spaces  
between rafters over the wall to be left open.  
The scantlings of the timbers to be of the  
dimensions given in the detailed estimate.  
The wood work to be of best country wood  
and tarred.

The flooring to be 4" gravel rammed  
to slope to rear.

The whole of the building to be plastered  
with one coat of chumam and white washed.

The masonry to be of rough stone in  
hydraulic mortar and to be kept moist  
for 15 days after construction.

The materials and workmanship  
to be of the best description procurable.

C.B. Henderson 21/7/28

Assistant Engineer in charge  
of the District.

comp.  
H.P.

Specification to accompany the  
estimate for constructing the Cook House  
in connection with the proposed Bungalow  
for the Assistant Superintendent of Police  
at Ongole in the Nellore District.

The foundations to be of Rough stone  
in hydraulic mortar 2 ft in depth and  
2 ft in breadth and to rest on a bed of  
concrete 1 foot in thickness. The concrete  
to be made with hydraulic mortar and  
kept moist for 15 days after it is laid  
in the foundations.

The basement to be 2 ft in breadth and  
1 foot in height.

The superstructure walls to be 1-6 in  
thickness and the heights to be of the  
dimensions given in the detailed  
estimate.

There will be honeycomb ventilators  
in rear and at ends as detailed in the  
estimate. The building will be provided with one country  
wood door as detailed in the estimate.

The roof to consist of country reapers,  
pan tiles and to be finished off with  
chumam borders.

The scantlings of the timbers to  
be