

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 1251 (W) Press
~~Mis.~~

Dated 11-4-1877.

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
11th April 1877. No. 1,251.*

Read the following papers :—

✓ No. 284. Proceedings of the Madras Government in the Ecclesiastical Department, dated 30th June 1876, No. 165.

From G. D. LEMAN, Esq., Collector of the Kistna District, to the Chief Secretary to Government, Fort St. George, dated Masulipatam, 22nd June 1876, No. 1,047.

REFERRING to paragraph 5 of my letter printed in G.O., No. 130, 20th May 1876, I have the honor to report that the purchase of the land for the extension of the Bezwada East Cemetery has been completed. I enclose a plan and estimate for the wall surrounding it, and request that they may be sanctioned and the necessary funds allotted. The estimated cost is Rupees 845, and the work will be done by the Department of Public Works.

APPROVED, and referred to the Public Works Department for the necessary orders.

(True Extract.)

(Signed) W. HUDLESTON,
Chief Secretary.

✓ No. 284-A. From Major J. O. HASTED, R.E., Superintending Engineer, Kistna, to the Acting Chief Engineer, Buildings and Roads Branch, dated Camp, Masulipatam, 9th March 1877, No. 174.

THE Officiating Deputy Chief Engineer's memorandum No. T-578, dated 13th July 1876.

I have the honor to forward, herewith, a revised estimate for constructing a wall round the eastern burial ground at Bezwada, amounting to Rupees 760, you will observe therefrom that the rates noticed have been reduced as far as possible as per enclosed data.

No. 285. ORDER THEREON, 11th April 1877, No. 1,251.

CIVIL WORKS, No. 26.

Fund.—PROVINCIAL SERVICES (IMPERIAL).
Class.—CIVIL BUILDINGS.
Main-head.—Original Works.
Head.—Ecclesiastical (27) Burial Grounds.
Project of which the work forms part.—Bezwada East Cemetery.
Work.—Building a wall to the extension of the Cemetery.
Amount.—Rupees 760.
To be carried out by the Public Works Department.

THE plan and estimate of Rs. 760 for constructing a wall round the ground proposed to be added to the burial ground at Bezwada in the Kistna District are sanctioned.

2. There are no funds available for the work at present.

3. This sanction is registered as Provincial No. 13—W of 1877-78.

(True Extract.)

Colonel, R.E.,
Secretary to Government, P.W.D.

To the Superintending Engineer, Kistna.
" Ecclesiastical Department.
" Examiner of Public Works Accounts.
Exd. S. T. Austin.
Spare Copies

Cemeteries.

No. 31. Read the following letter from G. D. LEMAN, Esq., Collector of the Kistna District, to the Hon. W. HUDLESTON, Chief Secretary to Government, Fort St. George, dated Masulipatam, 22nd June 1876, No. 1047:—

Referring to paragraph 5 of my letter printed in G.O., No. 130, 20th May 1876, I have the honor to report that the purchase of the land for the extension of the Bezwada East Cemetery has been completed. I enclose a plan and estimate for the wall surrounding it, and request that they may be sanctioned and the necessary funds allotted. The estimated cost is Rupees 845, and the work will be done by the Department of Public Works.

No. 32. ORDER THEREON, 30th June 1876, No. 165.

Approved, and referred to the Public Works Department for the necessary orders.

(True Extract.)

W. Hudson
for Chief Secretary.

To the Public Works Department, with plan and estimate.
.. Collector of the Kistna District.
.. Venerable the Archdeacon of Madras.

Ins No 30 of 3 June 1876.

P. 1876 Department
No 4880

Cemetery.—Plan and estimate for a wall round the Bezwada East Cemetery approved and referred to the Public Works Department for order.

JUNE
Nos. 31-32.

G.O. 3074 June 1576, No. 165.

Dated June 30th.

Received
Per. *[Signature]*

To
THE PUBLIC WORKS DEPARTMENT,
Bezwada.

Govt. of 1876
ECCLESIASTICAL.

C.E. & $\frac{17}{57}$ 13 July 1876.

L. C. Mitchell / 11 B No 284

Data for rough stone in chumam and mud for cemetery at Bezwada

Quantity	Particulars	Rate	Amount	Remarks.
<u>Rough stone in chumam</u>				
1	Cyd Stone—Cyd	10	10	
	Cartage 3 trips—per trip	2 7	7 9	
1	Brick layer—each	6	6	
2	Coolies—	3	6	
2	Parras fine mortar—Parras	6	12	
4	— Sand.—	9	3	
4	— grinding hire—	1	4	
	Cartage of lime—		10	
	Sundries—		5	
			3 2	
<u>Rough stone in mud.</u>				
1	Cyd. Stone—Cyd.	10	10	
	Cartage—		7 9	
$\frac{3}{4}$	Brick layer—each	6	4 6	
$1\frac{1}{2}$	man cooly—	3	4	
1	Small cooly—	1 9	1 9	
			1 12 0	

Bezwada Office
Bezwada.
23rd February 1877

[Signature]
Executive Engineer
Bezwada Division

Detailed Estimate No. 95 of 1876-77
Kistna District, Bezavada Division, Bezavada Taluq.
Work. Raising wall round the Eastern Cemetery
at Bezavada.
Prepared in the Range Office

Particulars	Number	Measurements			Contents
		Length	Breadth	Depth	
<u>Rough stone in mud.</u>					
<u>Foundations</u>					
Front and rear walls	1	304.0	2.0	1.75	1064.0 ✓
Ends	1	357.5	2.0	1.75	1251.25 ✓
Gate pillars	2	2.5	2.5	1.75	21.87 ✓
<u>Superstructure</u>					
Front and rear walls	1	303.5	1.5	4.25	1934.81 ✓
End walls	1	359.0	1.5	4.25	2288.62 ✓
Gate pillars	2	2.0	2.0	6.0	48.0 ✓
Total cubic feet of rough stone in mud					6608.55 ✓
Cubic yards					244.76 ✓
<u>Rough stone in chumam</u>					
Coping over walls	1	662.5	2.0	0.62	821.5 ✓
Do over pillars	2	2.5	2.5	0.66	82.5 ✓
Total cubic feet of rough stone in chumam					904.0 ✓
Cubic yards					33.5 ✓
<u>Plastering 2 coats</u>					
Coping over walls	1	662.5	3.5	"	2318.75 ✓
Do pillars	2	3.5	3.5	"	24.5 ✓
Total square feet of plastering					2343.25 ✓
Squares					234.3 ✓

DISTRICT: *Kistnath.*

Work.

Repairing a wall round the eastern cemetery at Biorah.

1 Provincial
2 Ordinary
3 T. & S. walls
4 Minor buildings
5 K. & C. buildings
6 Meeting hall
7 Eastern cemetery
8 at Biorah
9 at Biorah

Particulars.	Number.	Measurement.			Cubical contents
		Length.	Breadth.	Depth.	
<i>Rough Stone in Mud.</i>					
<i>Foundations</i>					
<i>Front & rear walls</i>	1	304.00	2.00	1.75	1064.00
<i>End do.</i>	1	357.50	2.00	1.75	1251.25
<i>Gate Pillars</i>	2	2.50	2.50	1.75	21.87
<i>superstructure</i>					
<i>Front & rear walls</i>	1	303.5	1.50	4.25	1934.81
<i>End walls</i>	1	359.0	1.50	4.25	2288.62
<i>Gate Pillars</i>	2	2.0	2.00	6.00	48.00
				<i>Cf!</i>	1608.55
					<i>Cubic Yards of stone in mud</i> 242.7
<i>Stone in Chumam</i>					
<i>Capping over wall</i>	1	662.5	2.00	0.62	821.50
<i>Capping over Pillars</i>	2	2.5	2.50	0.66	82.50
				<i>Cf!</i>	830.87
					904.00
					<i>Cubic Yards of stone in Chumam</i> 30.733
<i>Pointing to</i>					
<i>Walls both sides</i>	1	662.5	9		5962.50
<i>Pillars all round</i>	2	6.5	6.25		81.25
				<i>Square feet</i>	6043.75
				<i>or squares</i>	60.50
<i>Plastering in 2 coats</i>					
<i>Capping over wall</i>	1	662.50	3.50		2318.75
<i>Capping over pillars</i>	2	3.50	3.50		24.50
				<i>Square feet</i>	2343.25
				<i>Squares of Plastering</i>	23 1/2

Provincial
Civil Buildings

ABSTRACT ESTIMATE No. 47 of 1847

Year. DISTRICT. Madras

Work.

Repairing a well round the eastern cemetery at Borach.

Quantity.	Description of Charges.	Rate.	Amount.	Total.
244 7/8	Cy of Rough stone in mass	2	489 5/11	✓
30 7/8	Do of do in Churnam	3 1/2	115 5/11	✓
60 5/8	Squares of Rubbing	1 1/2	105 1/4	✓
23 50	Do of Plastering - coat	3	70 8	✓
4	Turning the openings in the existing concrete wall and trimming up the sides	1	4	✓
	Digging foundations & filling in		8	✓
	Sundries			
				793 3 11
				~~222 1/4~~
				36 1/2
				~~42 1/4~~
				845 X
				<u>830</u>

Total Estimate Rs.

S. V. S. S. S.
Collector

Sup. Engr's office P. O. M. L.
Masulipatam 27 March 1845

Central office
10/7/76

J. H. S. S. S.
Major R. E.
Sup. Engineer P. O. M. L.

Enclosure in a letter
from the Collector, Krishna
District to the Chief
Secretary to Government
Ecclesiastical Department
Dated 22nd June 1876 No 1047

Estimate -

Recd 224-76

Buildings

No. 174

Supg. Engrs. Office Krishna
Camp & Headquarters
9th Branch 1877
Dated 12th do

From

Major J. O. Hasted M.E.
Superintending Engineer, Krishna.

To

Colonel M. Farewell
Acting Chief Engineer, Roads
and Buildings, Madras.

Sir

The Officiating Deputy Chief
Engineer's Memo No 578 dated 13 July 1876.

I have the honor to forward
herewith a revised estimate for
constructing a wall round the
eastern Burial ground at Bejapoor,
amounting to Rs 760, and you will
observe therefrom that the rates,
^{noted} have been reduced as far as
possible, as per enclosed Data.

I have the honor to be

Sir
Your Most Obedt Servt.

J. O. Hasted Major M.E.
Supg Engineer, Krishna.

Enclosure 1

P.W.D.

17 JUN 77

NA 2006

Buildings

North.

From

The Departmental Paper
No. 114.

To the City & County Engineer
Buildings of Roads.

Dated 9 March 1877

Received

by the

General Engineer of the

Province on behalf of

for consulting a wall

around the station

amounting to Rs 760

4.0.11. April 77. No. 284

(a) Heads of Service

Fund. Provincial Service
Class. Civil Buildings

Main-head. Original Works

Sub-head. Electrical (27) Serial-grounds-
Proposed which the work forms part of
Section East Cemetery

Name of Work. Building a wall to the extension of
the Cemetery

Amount. Rs 760

To be carried out by the P. W. Department.

Print in the margin of G.O. No. 1251 of 11-4-77

11257

Public Works Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 11 April 77
Read the following:—

Rev. in the Eccl Dept (H.R. No 165 of 30 June 76)
From the Supt. Engineer Kistna } (H.C. No 174 dated 9th March 1877).

The Plan and Estimate
of Rs. 760 for Constructing a
wall round the ground pro-
posed to be added to the Burial
ground at Perwarrah in the
Kistna District, sanctioned.

There are no funds a-
vailable for the work at pre-
sent

This sanction is registered
as Provincial No 13M 877-78

L. S. Kistna ✓
Eccl. Dept ✓
H. P. W. ✓

25-4-77

27 10/4/77

No. 11257

1850 of 1876
2980
Govt. of 1877 Madras

PUBLIC WORKS.

To *The S. E. Madras*

Dated

Issued

Recd.

Encl.

G. O. 11th April 1877, No. 1257

Nos. 284-285

Burial ground at
Rayoarach, Pichia Dist.

Estimate of Rs. 750 for the
construction of a wall for the
protection of the — Burial ground

Est. in Reg.