

(1) Number of pages _____
(2) Date of repair _____
(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No.	1891	Press Mis.
Dated	1-11-18	1891.

Not to be folded or roughly handled

PUBLIC WORKS DEPARTMENT.

Buildings and Roads.
Civil Works.

No. 3. From H. G. TURNER, Esq., C.S., Acting Postmaster-General, to the Secretary to Government, Public Works Department, dated Madras, 22nd October 1877, No. 7,822-2,397.

I HAVE the honor to submit copy of a letter* from the District Engineer of Vizagapatam District, and the plan and estimate for Rupees 113 therein referred to for making certain improvements to the Post Office at Vizagapatam, also copy of a letter† from the Director-General of the Post Office of India according sanction to the measure, and request that you will be so good as to move the Government to pass orders for the allotment of the necessary funds from the grant for Minor Works of the Postal Department in this Circle for 1877-78, so that the work may be executed as early as possible.

SANCTIONED.

2. Funds being provided from the balance under Postal Minor New Works.
3. This sanction has been registered as Imperial No. 76 B of 1877-78.

(Signed) E. A. FOORD, Colonel, R.E.,
Secretary to Government, P.W.D.

To the District Engineer, Vizagapatam.
 „ Postmaster-General, Madras.
 „ Public Department.

Spare Copies

new camp Walter
101
Jm.
Rodgers officer
Virginia

Imperial
Post Office
Works
Department

Estimate No. 46 of 1877-78
 Estimate of the Probable expense for certain improvements
 required to the Post office at Vizagapatnam.

Number	Measurements			Superficial contents		Particulars of work.	Rate	Per Sq. ft.	Amount	Total
	Length	Breadth	Depth or Height	Squares	Cu. ft.					
1	76 1/2	1	3		229 1/2	Parapet wall				
1	6 1/4	1 1/2	2		18 3/4	Foundation of across wall.				
1	6 1/4	1	7		43 3/4	Wall above				
					292	110 22/27 Cys of Brick in Churnam	2 12 0	sq.	29 11 10	
2	76 1/2	-	3	4	59	Plastering to Parapet wall				
1	76 1/2	1	-	-	76 1/2	do Tops do				
2	6 1/4	-	7	-	87 1/2	Cross wall				
				6	23	1/2 of Plastering with 2 coats of Churnam, white washed.	2 6 0	sq.	14 12 8	
1	96	-	5	4	80	or 33 1/3 sq. of Bamboos Screens	0 6 0	sq.	20 0 0	
						Digging foundation & filling in			1 0 0	
						Excavating a Pot well & filling in the sides with earth well rammed.			20 0 0	
						Pot rings to the well			20 0 0	
1	3		24			Petty supervision	6 0 0	cont.	6 3 3	
						Lundries	1 0 0	do	0 13 10	
						Contingencies	0 8 0		0 6 5	
									Total Rupees	113

Rs 113 sanctioned by G.O. No. 1091 W of

Vizianagaram Range
 Office Camp Watlay
 16 June 1877.

Major R. B. de Souza
 District Engineer
 Vizagapatnam
 Range officer
 Vizianagaram

Specification to accompany Plans and Estimate of the Probable Cost of Certain Improvements required to the Post Office at Vizagapatam.

Estimate Rs 113-0-0

Brick in Chumam. To be built of Bricks $(9 \times 4 \frac{1}{2} \times 2 \frac{1}{4})$ on English bond uniform in size thoroughly and equally burnt well and equally shaped all Bricks to be thoroughly saturated with water, before being used every second course to be grouted with fluid mortar no joints to be more than $\frac{1}{2}$ thick every part of the walls must be equally and soundly built and every course must be levelled off before another is commenced. During the Progress of the work the portions on which the workmen are not engaged must be kept covered with wet straw or mats no half bricks or bats to be allowed. The proportions for lime and sand to be 2 parts of lime and 3 of sand.

Plastering with 2 coats of Chumam & white washed. The Plastering to consist of two coats a rendering and a floating coat for a rendering coat the work is to be prepared by racking out the joints as for pointing and the surface of the work and inside of the joints must be well wet when they are swept clean. The rendering coat to consist of two parts of lime and three parts of sand. The floating coat to

Estimate No 46 of 1877-78	Vizagapatam Range	Vizagapatam District	Improvements	Estimated of the probable cost for certain improvements required to the Post Office at Vizagapatam	Estimate No 113-0-0
---------------------------	-------------------	----------------------	--------------	--	---------------------

101.2 km/11 10 hr 3

to consist of three parts of lime to one of fine white sand and to be ground fine and polished in the usual way.

White washing to consist of two coats of shell chunam mixed with congee water and gum. The following are the proportions to be used for 10 squares (1 Parab of shell chunam, $\frac{3}{4}$ measure of raw rice, and $7\frac{1}{2}$ Pollars of gum).

There will be ^{made} ~~made~~ from bamboos ^{the} Bamboos ^{made} in narrow strips and fastened together with strong twine.

The well will be constructed in the ^{Pot well} usual native fashion of sinking Pot wells practiced in India. Each ring of the well to be 3 ft. in diameter, and from 3 to 4 ft. in depth. The proposed depth of the well to be 24 ft. deep.

On completion of the work all rubbish to be cleared away and the premises left in a clean condition.

Vijaynagar Range
Office C. S. B. Ballan
June 1877. } Range officer
Vijaynagar.

M. R. B.
District Engineer
Vijaynagar.

4012 (p. 1) 1877-3

Copy of a letter from the District Engineer
Vijayapatnam to the Inspector of Post Office
Vijayapatnam Division No 968 dated 25 July 1877

With reference to your letter No
3950 dated 20th March 1877, I have the honor
to forward herewith a Plan, Estimate
amounting to Rs 113.--- and Specification
for making certain improvements to the
Post Office at Vijayapatnam and request
you will be good enough to return them
to me with your counter signature, if approved.

Copy of a letter from the District Engineer
of the Post Office of Andhra to the Post
Master General Madras No 4561 of 3rd October 1877

Referring to your letter No 879
2597,
dated the 10th September 1877, I beg to
sanction the expenditure of Rupees one
hundred and thirteen only, for making
certain improvements to the Post
Office at Vijayapatnam, the amount
being

Specification to accom-
pany Plan & Estimate
of the probable cost of
certain improvements
required to the Post
Office at Vijayapatnam

Estimate Rs 113.---

I have the honor to be,
Sir
Your most obedient servant
W. Turner
Adj Postmaster General

Public Works Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the

Read the following:

From the Postmaster General
N. E. No. 7822/2397 dated 22nd October 1877 -

Sanctioned.

Funds being provided from the balance under Postal & Minor New Works.

29/10/77

This sanction has been registered as Imperial No 76 B of 1877-78.

J. E. Vigayapattam
Postmaster Genl. Madras
Public Dept.

Despatch 6-11-77.

No. 103, - P. M. O. O. P. - 21-10-77 - 250.

187 - 7

From Department
The Postmaster General,
MADRAS.

To Secretary
to Government,
Department,
PORT N. GEORGE.

No. 7822/2397
1877

Dated 22 October 1877

Received 187

SUBJECT.

Estimate for the maintenance of the Government of the Madras Port N. George. Request to move the Government to sanction for the maintenance of the Madras Port N. George.

401: hwp/10 B. 3

1070936

Govt. of 1877 Madras.

PUBLIC WORKS.

To

Dated

Issued

Recd.

Encl.

G. O., 18th Nov 1877, No. 1391 W

Nos. 3-4

Post office at Vizagapatnam
The plan & rate of
Rs. 713 for improvement to
the — — — — — and
funds provided.

*Subd. Insp.
8.11.77*