

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 188	(W)	Press ~~Mis.~~
Dated	4-6-	1877.

Not to be folded or roughly handled

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

4th June 1877, No. 188 W.

Buildings and Roads.
Civil Works.

Read the following papers :—

No. 23. From Lieutenant-Colonel H. L. PRENDERGAST, R.E., District Engineer, North Arcot, to the Chief Engineer, Public Works Department, Buildings and Roads, dated Vellore, 9th April 1877, No. 80.

I HAVE the honor to submit for sanction a plan and estimate for Rupees 870 for extending the English record room of the Collector's Cutcherry at Chittoor.

- One Plan.
" Detailed Estimate.
" Abstract
" Specification Report.

2. The estimate has been prepared with reference to G.O., No. 201, dated

28th December 1876, and approved by the Collector.

3. I request that the enclosures may be returned when no longer required.

No. 23-A. From the same Officer, dated Vellore, 29th May 1877, No. 705.

WITH reference to your memorandum No. 1,024, dated 20th April 1877, I have the honor to resubmit the plan and estimate for improving the English record room of the Collector's Cutcherry at Chittoor.

- One Plan.
" Detailed Estimate.
" Abstract
" Specification Report.

2. The amount of the estimate has

been raised from 870 to 1,190 Rupees by providing asphalt flooring for the whole of the space to be occupied as record rooms.

No. 24. ORDER THEREON, 4th June 1877, No. 188 W.

Heads of Service.—Provincial.
Fund.—Ordinary.
Class.—Original Works.
Main head.—Civil Buildings.
Sub head.—B, Revenue Department.
Section.—1, Divisional, &c., Cutcheries.
Work.—Extending English record room of the Collector's Cutcherry at Chittoor.
Amount.—Rupees 1,190.
To be carried out by the Public Works Department.

THE estimate of Rupees 1,190 for extending the English record room of the Collector's Cutcherry at Chittoor in the North Arcot District is sanctioned.

2. There are no funds available for the work at present.

3. This sanction is registered as Provincial No. 87 W of 1877-78.

(True Extract.)

Colonel, R.E.,
Secretary to Government, P.W.D.

To the District Engineer, North Arcot.
" Examiner of Public Works Accounts.
" Revenue Department.

Exd. E. C. Shunker.
Spare Copies

Head of Service Provincial

Fund. Ordinary

Class. Original Works

Main-head. Civil Buildings

Sub-Head. S. Revenue Department

Section - I Divisional & Catcheries.
Sub-head.

~~Project of which the works form part~~

Work. Extending English record room of the
Collector's Catchery at Pithore.

Amount. Rs 1190

To be carried out by the Public Works Department.

Printed with G.O. No 188 W of 4 June 1877-

ABSTRACT ESTIMATE No. 42 of 1876-77.

DISTRICT NORTH ARCOT TALUQ *Chittoor*

Heads of Service	Provincial
------------------	------------

Fund
Ordinary

class Original works.

Main. Head Civil Building

Sub. Head . . . Revenue Department

Section Collectors Cutcherry at Chittoor

Extending English Recd room of the Cuthery,

Amount of Estimate Rufus 876 To be carried out by the P. & S.

Quantity.	Description of charges.	Rate.	Per.	Amount.	Total.
10.46	Ceiling Rough Stone in chumam—	9	4	100 cts	97
18.32	" Brickwork in chumam—	15	"	"	274
37	" Flat arch work 24—	20	"	"	8
1.32	" Circular arch work 24—	20	"	"	26
1.43 1/2	Plaster Cornice work—	"	4	Per	36
28.75	Soft of Plastering 2 coats and 1—	2	4	100 cts	65
7.78	" Coating of whitewashing—	3	8	"	27
14.86	" Flooring with Brick & jelly in chumam—	3	8	"	27
	" Roofing with Palimpali rafters supports wall-plaster same Boards flat and pan-tiles and chumam borders &c.—	18	"	"	267
13.12	Ceiling of Earth work—	"	56	100 cts	5
2.22	" Removing old walls—	"	15	"	2
9.90	Soft of Tarring 2 coats—	2	"	100 cts	19
	Scaffolding—				5
	Petty Supervision—				25
	Sundries for removing the old windows and replacing the same in the verandah wall and whitewashing the main walls &c.—				20
	Total Plus 876				

CHITTOOR DIVISION OFFICE.

Chittor 10th March 1877.

In charge of Chittoor Division.

11/11/1871
In charge of Chittoor Division.
Lt. Col. R.E.
District Engineer North Arcot

Specification to accompany the estimate for extending the English Record room attached to the collector's cutcherry at Chittoor. Estimate Rupees 890.1190-4

The present English Record room attached to the collector's cutcherry is 66'-9" x 14'-9" which is found to be insufficient for the proper security of the records. It is therefore proposed to add verandahs in front and back of the room and wall them up.

The foundations of the verandah walls is to be 2' x 3½' built of rough stone in Chumam, and the walls above are to be 1½' thick and the height of the front wall is to be 9', and that of the back 8½' of brick in Chumam and plastered with 2 coats of Chumam.

The floor is to be laid with brick jelly in chumam and plastered except at the front entrance where the present floor is admissible.

The roof of the main room is to be continued with that of verandah and made of palmyrah rafters, reapers, flat

27/10/17

27/10/17

ABSTRACT ESTIMATE

No. 42 of 1876-77.

DISTRICT NORTH ARCOT.

Taluk Chittoor

Work of various kinds

Foundations

Plastering

Painting

Subsidiary

Director's collection at

Chittoor

Extending English Record Room of the cutcherry.

Estimate Rupees 890.1190-4

To be carried out by Mr. O. P. S. S. S.

46/1/17

flat and pautiles and Chumaw
boarders. The old roof over the present
entrance is in good state and is to
be connected with that of the new
verandah.

The old windows marked in the
plan are to be removed to the
verandah wall and at the places
shall be arched passages 6' wide
and 6' height.

There shall be two cross
walls in the front verandah at
the entrance in place of honey
comb work in tiles, which ^{has} ~~are~~ to
be removed. the roof over entrance
remaining as it stands.

Chittoor 20th March 1877. Asst. Engineer Chittoor

Assistant Engineer Chittoor
Division.

Respectfully to Lt. Colonel R. G.

Respectfully to
to Mr. Whitby
We

P.W.D.

1842327

1710

Specification

DETAILED ESTIMATE No. 42 of 1877-78

DISTRICT NORTH ARCOT TALUQ *Chittoor*

Head of Service Provincial

Low of Ordinary

Class Original Works

Super Head Civil Building

Sub Head Revenue Department

Section Collection of Revenue of Chittoor

WORK.

Extending English record room of the collector's office
Amount of estimate Rs 276. To be carried out by the P.W.D.

Particulars.	No.	Measurement.			Contents.
		L.	B.	D.	
<i>Foundation</i>					
Verandah walls	2	68-3-2	3-6	955-6	
Side walls, rear Verandah	1	7-6-2	3-6	52-6	
do front	1	5-6-2	3-6	38-6	
Total left Rough stone in chumam					1046-6
<i>Superstructure</i>					
Front Verandah wall	2	28-1-1	6-9	759-4 1/2	
Rear do	1	68-3-1	6-8	870-2 1/4	
Front Verandah side walls	1	6-1-6	10-9	96-9	
Rear do do	1	8-1-6	10-6	126-	
Brick wall in place of honey comb work tiles	2	6-1-6	7-9	139-6	
Total					1991-9 3/4
Deduct for windows	5	3-6-1	6-4	6118-7/8	
Flat archwork over windows	5	4-6-1	6-1	837-3/32	
Total Deductions					159-7/8
Remaining left of Brick in chumam					1832-9 3/4
Flat archwork as per above Deductions					37-3/32
Carried over.....					

By C. L. J. June 17/77. Lb No 23

P.W.D.

1842827

1710

DETAILED ESTIMATE No. 42 of 1877-78

DISTRICT NORTH ARCOT TALUQ *Chittoor*

Head of Service *Provincial*

Land *Ordinary*

Class *Original works*

Super Head *Civil Building*

Sub Head *Revenue Department*

Section *Collection of Revenue at Chittoor*

WORK.

Extending English record room of the collector's office
Amount of estimate Rs 276. To be carried over the P.W.D.

Specification

Particulars.	No.	Measurement.			Contents.
		L.	B.	D.	
<i>Foundation</i>					
Verandah walls	2	68-3-2	3-6	955-6	
Side walls, rear Verandah	1	7-6-2	3-6	52-6	
do front	1	5-6-2	3-6	38-6	
Total of rough stone in chumam					1046-6
<i>Superstructure</i>					
Front Verandah wall	2	28-1-1	6-9	759-4 1/2	
Rear do	1	68-3-1	6-8	870-2 1/4	
Front Verandah side walls	1	6-1-6	10-9	96-9	
Rear do do	1	8-1-6	10-6	126-	
Brick wall in place of honey comb work tiles	2	6-1-6	7-9	139-6	
Total					1991-9 3/4
Deduct for windows	5	3-6-1	6-4	6118-1/8	
Flat archwork over windows	5	4-6-1	6-1	837-3/32	
Total Deductions					159-7/8
Remaining cost of Brick in chumam					1832-9 3/4
Flat archwork as per above Deductions					37-3/32
Carried over.....					

By (C. L.) June 17/77. Lb No 23

Particulars.	No.	Measurement.			Contents.
		L.	B.	D.	
Brought forward					
Circular arch work					
over arch ways	5	11 9	1 6	1 8	132 - $\frac{3}{10}$
Total Cyl. Circul. arch work					132 -
Cornice work					
Front Verandah walls	2	29 $\frac{1}{2}$			58 - $\frac{1}{2}$
Rear wall	1	69 $\frac{1}{2}$			69 - $\frac{1}{2}$
Side wall of front Verandah	1	7			77 -
" " " "	1	7			77 -
Total Running feet of Cornice					743 - $\frac{1}{2}$
Plastering					
Front Verandah walls outside	2	28 $\frac{1}{2}$	9 - 6		478 - $\frac{1}{2}$
" " " " inside	2	26 $\frac{1}{8}$	9 - 6		496 $\frac{3}{8}$
" " Side walls outside	2	8	10 7		172
" " " " " "	1	7 - 6	10 7		80 $\frac{5}{8}$
" " " " inside	3	6	10 7		193 $\frac{1}{2}$
Rear Verandah wall outside	1	69 - 3	8		546 -
" " " " inside	1	66 - 9	9		600 $\frac{3}{4}$
" " Side walls outside	1	9 - 6	10 - 6		99 $\frac{3}{4}$
" " " " inside	1	5 -	10 - 6		54
Sills and sills and soffits of windows	5	16	1 - 6		120
Arch ways in Main walls	5	21 42	1 - 6		162 $\frac{1}{2}$
Total Sqft. of Plastering					3033 $\frac{1}{8}$
Deduct for Windows	10	3 - 6	1 - 6		157 $\frac{1}{2}$
Remaining Sqft. of Plastering with 2 coats					2875 $\frac{5}{8}$

Particulars	No.	Measurements			Contents
		L.	B.	D.	
Flooring					
Front Verandah	2	25 - 7 1/2	5 - 6		281
Rear " "	1	66 - 3	7 - 6		662 1/2
Total Sqft. flooring with buck jelly in chumans					943 1/2
Roofing					
Front Verandah	2	28 - 1 1/2	10 - 6		590 - 7
Rear " "	1	69 - 6	12 - 9		896 -
Total sqft. roofing with palmyrah rafters & ceiling with plates & bamboo & chumans					1486 - 7
Excavating foundation	1	150	2 - 6	3 - 6	1312 - 6
Total left of Earthwork					1312 - 6
Demolishing					
opening archways up to spring line	5	6	1 1/2	6	270
Circular portions	5		14 1/3		70 - 65
Total					340 - 65
Deduct for old windows	5	3 1/2	1 1/2	4 1/2	118 1/8
Remaining Cft. Demolishing					222 - 52 1/2
Laying palmyrah rafters in front	45	10	1		450
Verandah rafters	45	12	1		540
" " " " rear					
Total Sqft. of Laying					990

ABSTRACT.

15

Quantity.	Description of charges.	Rate.	Per.	Amount.	Total.
10.46	3 ft Rough stone in chumau	9 4	1000 ft	97	
18.32	" Brick work in chumau	14 13	"	274	
37	" Flat arch work	20	"	8	
1.32	" Circular arch work	20	"	26	
143 1/2	Plastering work	"	"	36	
28.75	3 ft of plastering 2 coats and 1 coat of whitewashing	2 4	3 ft	65	
9.43	Flooring with linoleum	17 12	"	318	
14.86	Roofing with galvanized sheet iron, respers roof plates, eave boards, flat and pan tiles and chumau border &c.	18	"	267	
13.12	3 ft of earthwork	5 6	1000 ft	5	
2.22	Removing old walls	15	"	2	
9.90	3 ft of plastering 2 coats	2	3 ft	19	
	Scaffolding			5	
	Plastering			5	
	Sum ofries for removing the old windows and replacing the same in the Veranda wall and whitewashing the main walls			20	

Total Estimate Rupees

876

CHITTOOR DIVISION OFFICE.

Chittoor 10th March 1877.

In charge of Chittoor Division.
District Engineer

P.W.D.
10 APR 77

Order

DETAILED ESTIMATE.
No. 42 of 1876-77.
DISTRICT NORTH ARCOT.
Tulug Chittoor
Head of Service General
Fund Ordinary
Class Original Works
Major Works Civil Building
Sub Works Revenue Department
Section Collection Intending, at
Chittoor
Extending English
Record Room of the Intending
12/10
Estimate Rupees. 876-1-1
To be carried out by
the P.W. Department

4611 June 77 132.23

NORTH ARCOT,
District Engineer's Office,
Buildings and Roads.
Tellico 9th April 87.
No. 80

From
The DISTRICT ENGINEER,
NORTH ARCOT,
To
The Chief Engineer for
Buildings and Roads.
Madras.
Sir,

Encls. 4
Plan,
Dy. estn.
No. 42
Specimen 3.

I have the honour to submit
for sanction a plan and esti-
mate for Papers/870/ Eight hundred
and twenty, for extending the English
Record room of the collector's
butehery at Chittoor.

The estimate has been pre-
pared with reference to G.O. No.
201 dated 28th December 1876, and
approved by the collector.

I request that the enclosures
may

may be returned, when no longer
required.

I have the honor to be,

Sir,

Your most obedient servant,

Westbury, 21st Feb. 1842.

District Engineer, N. Hants.

Ins. No. 201 - 28-12-76.

Buildings and Roads.

104FR77

From

The District Engineer
North Street.

C.E. No 1024 720 April 77.

La. 80

Carlos. 4

Stated, 9th
 Received, } April 1877.

* *Red to red*

Roller tax's factory at Whitton

Q How much for sanitation
and estimate for Rs 870--
for extending the English
Recess room after the

464 June 11, 1882

Car 1-6-27

Roads and Buildings

No. 705

North Arcot,
DISTRICT ENGINEER'S OFFICE,

Yellse 29 May 1877.

*THE DISTRICT ENGINEER,
NORTH ARCOT.*

The Chief Engineer for
Roads and Buildings
Madras.

Sir,

Genl. 1, With reference to your Memo No. 1024 dated
1st May 20th April 1877, I have the honor to re-
spond to you by submitting the plan and estimate for
improving the English record room of
the Collector's Office at Chittoor.

The amount of the estimate has been raised from 870 to 1190 Rupees by providing asphalted flooring for the whole of the space to be occupied as Record Rooms.

I have the honor to be

Yours most obedient servant
Wm. B. Henderson
District Engineer North & Co.

50 28-12-76 No 207 his.

Roads and Buildings.

From the District Engineer
North Arcot.

No. 705

Number of One L. Hour.

Dated 29 } May 1877.
Recd.

Record room of the collector.
Lutcherry at Chittoor.

Resubmitting the re-
vised estimate for the
English.

1. Plan sent but not sent to
the L. E. at most vide.
C. No 7008 of 77

4. 6. 7. 11. 17. 23. 25. 27. 28. 29. 30. 31. 32. 33. 34. 35. 36. 37. 38. 39. 40. 41. 42. 43. 44. 45. 46. 47. 48. 49. 50. 51. 52. 53. 54. 55. 56. 57. 58. 59. 60. 61. 62. 63. 64. 65. 66. 67. 68. 69. 70. 71. 72. 73. 74. 75. 76. 77. 78. 79. 80. 81. 82. 83. 84. 85. 86. 87. 88. 89. 90. 91. 92. 93. 94. 95. 96. 97. 98. 99. 100.

Cent-6-77
1-6-77

8. Road
Low mks

No 108 W Public Works Department
Proceedings of the Madras Government
Under date the 4 June 77
Read the following.

From the D. E. North Arcot (H. E. No. 80 of 9 April 77)
do do do (" " 705 of 29 May 77)

The estimate of
Rs 1190 for extending
the English record room
of the collector's Lutcherry
at Chittoor in the North
Arcot District is sanctioned.

2 There are no funds
available for the work
at present.

3 This sanction is
registered as.
Sub No 87 of 1877/78 345-77
1/77

D. E. Arcot
L. E. A
Rec. D. E. A

12-6-77

500 pages for
3710
3710

Public Works

The H. B. Smith Street

1884

June 1884

No. 23-24

Whitson (a cherry at
Chittoor. Estimate
for extending the infirmary
room room of the -
Sanatorium

Done in 1884