

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.**Government of Madras.***Public Works* **DEPARTMENT.**

G.O. No. 575

Press

Mis.

Dated 22-2-

1877.

Not to be folded or roughly handled

No. 529. Read the following Proceedings of the Madras Government in the Judicial Department, dated 5th February 1877, No. 308:—

Read the following letter from the Acting District Judge, Kistna, dated 6th December 1876, No. 225:—

In enclosing a plan and estimate for making certain additions to the District Munsif's Court-house at Bezorah amounting to Rupees 3,450, I have the honor to request you will be good enough to obtain the sanction of His Excellency the Governor in Council for the work, which is urgently required.

Either the whole or a large portion of the funds needed can be obtained by the sale of the old Court-house in Bezorah, which is now of no use.

Read also letter from the District Judge, Kistna, dated 27th January 1877, No. 30.

With reference to your endorsement, No. 2,104, dated 11th December 1876, calling for full explanation of the necessity of additions to the District Munsif's Court-house at Bezorah, with a complete statement of the facts of the case, or reference to former correspondence, I have the honor to refer you to the Proceedings of the Madras Government, Public Works Department, No. 129 of the 20th January 1876.

2. The necessity of the additions seems sufficiently set forth in Mr. Wilson's letter quoted in the Proceedings of Government above referred to. I need only say that I quite agree with Mr. Wilson. The present building is wholly unfit for a Court-house; and the modifications recommended, though a great improvement, will not afford the amount of space allowed in the standard plan. Owing to the great heat of the summer months at Bezorah, and the high winds which prevail there then, the more room that can be got in a public building the better. At present, when the windows have to be shut to keep out the dust on one side of the Court-house, the rooms become almost uninhabitable.

3. As no copy of the Proceedings of Government quoted above was sent to this Court, I was unable to refer to former correspondence. The enclosure is copied from a copy of the Proceedings which I was able to obtain from the Superintending Engineer.

The proposed addition is approved, and the papers will be referred to the Department Public Works for issue of the necessary orders.

(True Extract.)

(Signed) W. HUDLESTON,
Chief Secretary.

Proceedings of the Madras Government, Public Works Department,
22nd February 1877. No. 595.

No. 530. ORDER THEREON, 22nd February 1877, No. 595.

CIVIL WORKS, No. 44.

(a) Heads of Service.—Provincial.

Fund.—Ordinary.

Class.—Original Works.

Main-head.—Civil Buildings.

Sub-head.—A, Judicial Department.

Section.—1, Court-houses.

Name of Work.—Additions and alterations to the District Munsif's Court-house at Bezurah.

Amount.—Rupees 3,450.

To be carried out by the Public Works Department.

The estimate is sanctioned. Funds will, if practicable, be provided from next year's reserve.

2. This sanction has been registered as Provincial No. 243—W. of 1876-77.

(True Extract.)

(Signed) W. FAREWELL, Colonel,
Acting Joint Secretary to Government.

To the District Engineer, Kistna.

„ Examiner of Public Works Accounts.

„ Judicial Department.

(a) Heads of Service—*Provincial*

Fund. *Ordinary*

Class. *Original Works*

Main-head. *Civil Buildings*

Sub-head. *A. Judicial Deptt.*

Section. *1 Court-houses*

Name of Work. *Additions & alterations to the District Munsiff's Court house at Bezurda.*

Amount. *Rs 3450*

To be carried out by the *P. W.* Department.

Print in the margin of G. O. No. 595 of 22/2/77

Proceedings of the Mass. Government, Public
Works Department, No. 252, 20th January 1876.

No. 252. Read the following endorsement
of the Chief Secretary to Government,
Judicial Department, dated 8th
January 1876, No. 23:-

From J. Whit, Esq., Acting Registrar of
the High Court of Judicature at Mass.,
to the Hon. W. Hudson, Chief Secretary to
Government, Port. Saint George, dated Mass.,
17th January 1876, No. 39.

I am directed to bring to the notice of
Government the state of the building recently
constructed by the Department of Public Works
as a court house for the District of
Burgada in the Western District. The
plans and estimates for this building, pre-
pared under the supervision of the then
superintending Engineer of the 2^d Division,
were sanctioned by Government in their

Proceedings dated 12th October 1870, No. 316.

The work was handed over as complete by

W. H.

Enclosure 3

In a letter from the H. & D.
Judge, Kistua, dated
27th January 1877 A.D.

Copy of G. O. No. 129
dated 20th January 1876.

to J. H. 328/77

with 3 coats of plaster on the outside, over half wood

of brick jelly in chumoms at a cost of
Rs. 60, a material which is not calcu-
lated to stand wear and tear except in
rooms where it is covered with matting.
The repairs might have been carried out
by the local Public Works officers on
Mr. Wilson's demand, without reference
to the High Court or Government. The
District Engineer, Kistua, will now ar-
range for flooring the building with
more lasting material.
He will also submit plan and
estimate for enlarging the court house
to such an extent as the District Judge
may consider necessary. The existing
building appears, however, to have been
a modification of the standard plan
approved in 1857 by the High Court judges.

/C. True C. P. 1877

Signed / J. W. Walker, Major-
General, R. E.,

Secretary to Government.

W. H. 1877

to District Judge.

Specification report for Improving the District
Municipal Court house, and attaching a Privy to
the same at Berzora. 89

Soil Black cotton.

Materials rough stone in Chunan.

Estimate Rupees 3,450.

1. The demolition consists of the removal of the
parapet wall over terrace in rear and cross end
walls of the north rooms of the existing building,
opening 1 archway in the existing wall, and replacing
existing floor and steps by cut stone.

2. The additions are as follows.

Municipal room ———— 14.6 x 8.6

Passage ———— 7.0 x 8.6

Property room ———— 24.6 x 8.6

Vakil's room ———— 12.0 x 17.0

Clerk's room ———— 18.0 x 17.0

Record room ———— 16.0 x 17.0

Verandah in rear ———— 10.5 wide

The materials throughout will be rough stone
in Chunan.

3. The roof over the 3 rooms is to be supported by
rafters with double collar pieces, purlins, wall plates
and brissumers all of teak wood, and covered with
best flat and pantiles and Chunan borders &c.

The roof of the verandah is to be terraced with brick
on edge, 3 of concrete, 3 courses of flat tiles and finished
with 3 coats of plaster on the outside, over teak wood.

joists 4" x 3" at 1 1/2 feet apart.

4. The flooring throughout the whole building will be of cutstone 4" thick over a bed of concrete 3" thick and pointed with lime and Surki cement.

5. The doors and windows will have a flat arch of brick over them 1 1/2 ft thick.

6. The walls inside and out and pillars will be plastered with 1 coat of Chunan and white washed.

7. Each of the 5 teak wood doors will be 1/3 pannelled and 2/3 venetian, and the existing 3 windows will be provided with glazed shutters.

1 to the Municipality room, 1 to the Vakil's room, and 1 to the record room with iron bars, and 1 window pannelled to the record room.

Pring

1. The Pring will be constructed of rough stone in Chunan in accordance with the dimensions on plan and in Estimate.

2. The roof will consist of Palmyra rafters, bamboo piers, flat and pan tiles and Chunan borders complete.

3. The wall plates and bressummers are to be of teak wood.

4. The floor will consist of cutstone 4" thick on a layer of 3" concrete and pointed with Chunan.

5. The walls will be plastered and whitewashed except the tarred portion.

6. The walls inside for a height of 3 feet and the entire floor will be tarred with 1 coat of

tar and asphalt. 3 lbs of tar to 1 lb of asphalt.

Bergorah Office

7th November 1876

} signed/ C. J. Peters

Executive Engineer with
Bergorah Division

Supg Engrs Office R.
Masulipatam.
22nd Nov/76.

In actual
Superintending Engineer District
Major P. E.

P.W.D.

6 FEB 77

1225

No.

Provincial

DETAILED ESTIMATE No. 70 of 1876-77

Kistna DISTRICT.

Buzorah Taluq. Buzorah Village.

Work

Additions and Improvements to the new District
Municipal Court house at Buzorah

Prepared by the Range Officer.

Particulars.	Number.	Measurement.				Cubical contents
		Length.		Breadth.	Depth.	
		Each	Total			
<u>Demolishing</u>						
Cross and End walls of rear rooms	3	8.6	25.6	1.6	10.0	382.6
Parapet wall in rear of the existing building.	1		40.0	1.3	1.6	75.0
Do our end walls of rear rooms.	2	8.6	17.0	1.3	1.6	31.10 1/2
Archway allowing 1 foot for workman to handle.	1		4.0	1.6	10.6	63.0
			Total			552.4 1/2
Doors for door	1		4.0	7.6	8.0	48.0
Do windows	2	3.6	7.0	1.6	4.6	47.3
Total demolitions						95.3
Total Cft of walls to be demolished less demolitions						457.4 1/2
or Chicken Yards						17
Removing existing floor and putting Antetone flooring to existing building						
Chicken Yards						34
Removing masonry for fitting Antetone in old steps						3.0
Total demolishing Chicken Yards						54.0
Excavating foundations and filling in the Earthwork. Chicken Yards						200
Concrete under foundations						
Cross walls of the additions	2	15.9	31.6			
End walls	2	23.0	46.0			

Longitudinal wall — $\frac{1}{2}$ —	1	5.6				
Municipal & Property room walls —	2	14.0	28.0			
Cross wall of rear verandah —	1	7.0				
Pillars and retaining wall in rear	1	67.6	233.3	3.0	4.0	2802.0
Steps in rear —	1		38.0	1.6	4.0	228.0
Under flooring of court room —	1	26.6				
$\frac{1}{2}$ — Vakil's $\frac{1}{2}$ —	1	11.6				
$\frac{1}{2}$ — Clerk's $\frac{1}{2}$ —	1	17.6				
$\frac{1}{2}$ — records $\frac{1}{2}$ —	1	15.6	71.0	16.6	0.3	292.10
$\frac{1}{2}$ — Verandah in front —	1	36.6				
$\frac{1}{2}$ — $\frac{1}{2}$ both sides $\frac{1}{2}$ —	2	28.6	57.0			
$\frac{1}{2}$ — $\frac{1}{2}$ in rear —	1	46.6				
$\frac{1}{2}$ — Municipal room —	1	14.0				
$\frac{1}{2}$ — Passage —	1	6.6				
$\frac{1}{2}$ — Property room —	1	24.0				
			124.6	8.0	0.3	369.0
Total cubic feet of concrete work						369.10
Chalk galls —						136.2

Rough stone in Chunar Foundations

Cross walls of the additions allowing extra 6 for joining new work with old	2	16.6	33.0			
Rear wall of $\frac{1}{2}$ —	1	53.0				
End walls — $\frac{1}{2}$ —	2	28.6	57.0			
Cross wall of rear Verandah —	1	7.6				
Pillars & retaining wall in rear —	1	68.1				
			286.2	6	1.0	546.3
Extending Municipal & Property rooms	4	3.6	14.0			
Side wall of passage —	1	7.6				
			24.6	2.6	3.0	161.3
Steps in rear —	1		37.3	3.9	1.0	136.0
$\frac{1}{2}$ to Property room —	1		4.0	3.9	1.0	15.0

<u>Basement</u>						
Gross walls of additions —	2	17.0	34.0			
Rear wall — $\frac{1}{2}$ —	1	52.6				
End walls — $\frac{1}{2}$ —	2	28.6	57.0			
Cross wall of rear Verandah —	1	8.0				
Pillars and retaining wall in rear —	1	68.6				
Walls of Property & Municipal rooms —	4	4.0	16.0			
Side wall of passage —	1	8.0				
			244.0	2.0	2.0	976.0
Steps in rear —	1		34.0	2.9	1.0	93.6
$\frac{1}{2}$ to Property room —	1		4.0	2.9	1.0	11.0
<u>Superstructure</u>						
Cross walls of additions —	2	17.0	34.0	1.6	13.0	663.0
End walls of additions —	2	23.0	46.0	1.6	13.0	897.0
Rear wall — $\frac{1}{2}$ —	1	52.0	1.6	12.6		975.0
Cross wall of rear Verandah —	1	10.0				
Extending walls of Property and Municipal rooms —	2	14.6	29.0			
			39.0	1.6	10.0	585.0
Chalks —	4	17.0	68.0	1.6	2.10	289.0
Pillars —	5	1.6	7.6	1.6	9.8	108.9
Filling up gap over archway —	1		7.0	1.6	1.0	10.6
Parapet wall of rear Verandah —	1	69.6				
$\frac{1}{2}$ over Property & Municipal rooms —	2	44.9	29.6			
			99.0	1.3	1.6	185.72
Blocking up old windows —	3	3.6	10.6	1.6	4.6	70.10
Total cubic feet.						5723.8
Deduct for door ways —	5	4.0	20.0	1.6	8.0	240.0
$\frac{1}{2}$ windows —	4	3.6	14.0	1.6	4.6	94.6
$\frac{1}{2}$ flat arch work over doors —	5	5.0	25.0			
$\frac{1}{2}$ — $\frac{1}{2}$ — windows —	4	4.6	18.0	1.3	1.6	96.9
Total deductions cubic feet.						431.3
Total rough stone in Chunar (less deductions) cubic feet.						5292.5
Chalk galls —						196.0

Arch work					
Flat arch as per above description					96.9
Circular arch	1	8.7	1.6	1.6	19.4
Total arch work					116.1
Culio Jaro					4.5
Cornice work					
Main building & gables outside	1	184.0			
Terrace	1	104.0			
Total running feet of moulded cornice work		288.0			288.0
Plastering					
Vatiko room	1	51.0			
Cherko R.	1	52.0			
Records R.	1	55.0			
		158.0	13.0		2054.0
Municipal and property rooms, inside	2	18.6	27.0		
R. R. outside	2	16.0	32.0		
Out side walls up to terrace	1	52.0			
Cross walls of rear veranah both sides	2	10.0	20.0		
		14.0	10.0		1410.0
End walls up to gables	2	20.0	40.0	12.0	480.0
Gables, outside	2	20.0	40.0	3.9	150.0
R. Inside	6	17.0	102.0	3.0	306.0
Pillars	5	6.0	30.0	9.8	290.0
Parapet wall over Municipal and Property rooms	2	44.9	29.6		
R. over terrace of rear Veranah	1	69.0			
		98.6	4.3		418.7
Basement all round	1	145.6	2.0		291.0
Jambos and soffits of doors	5	20.0	100.0		
R. R. & sills of Windows	4	16.0	64.0		
Circular arch, side	2	8.7	17.2		
R. arch way, jambos & soffits	1	18.3			
		199.5	1.6		299.2

Windows blocked up, sides					
	6.36	21.0	4.6		94.6
Total sq ft					5793.3
Deduct for					
Doors, both sides	10.40	40.0	8.0		320.0
Windows R.	8.36	28.0	4.6		126.0
Steps against basement	1	34.0	2.0		68.0
Total deduction					514.0
Total plastering (less deduction) square feet					5279.3
White washing as per above					52.80
Plastering squares					52.80
Antetone flooring 4" thick					
Court room	1	27.0			
Records room	1	16.0			
Cherko R.	1	18.0			
Vatiko R.	1	12.0			
Verandah in front			7.2	17.0	1241.0
R. in rear	1	57.0			
R. in front sides	2	28.6	57.0		
			148.6	10.3	1522.1
Passage	1	7.0			
Municipal room	1	14.6			
Property R.	1	24.6			
			46.0	8.6	397.0
Total					3154.1
Deduct for old & new pillars					
	16.16	24.0	1.6		36.0
Total antetone flooring 4" thick (less deduction) square feet					3118.1
Antetone flooring 6" thick					31.18
Steps in front	1	104.0			
R. rear	1	14.5			
		219.0	13.0		34.3

Property room	1	16.0	6.3	20.0	✓
Total entolou flooring & thick squares				331.00	✓
Roofing with teak wood rafters				3.31	✓
recessed flat and panted, and					✓
Chunam borders for main building	1	52.0	25.0	1300	✓
Total squares of roofing				12.0	✓
Terrace roofing					✓
Verandah in rear	1	52.0		1.10	✓
Property and Muniff's rooms	2	6.0	12.0	656.0	✓
Total squares of terrace roofing				6.56	✓
Teak wood work					✓
Brisummers	1	52.0	0.6	13.0	✓
Joists	4	4.0	0.6	38.6	✓
Pillar plates	5	1.0	0.2	0.10	✓
Wall plates	1	18.0	0.6	15.0	✓
Total teak wood work Cubic feet				67.3	✓
Doors with frames & Complete	5	4.0	8.0	5.0	✓
Windows	1	3.6	4.8	1.0	✓
Doors & Slates without frame	3	3.6	4.6	3.0	✓
Iron work					✓
Bar iron 5/8 inch diameter to the window of the record room	1	4.0	4.6		✓
Total lbs of iron work				47.38	✓
Brick					✓
Earthwork for excavating foundation and filling in				10	✓
Rough stone in Chunam					✓
Foundations					✓
Wall all round	1	38.0			✓
Curtain wall	1	8.6	1.1	222.9	✓
Superstructure					✓
Rear wall	1	11.0	1.6	189.9	✓

Front wall	1	8.0	1.6	7.6	412.6	✓	
Side walls	2	8.0	1.6	9.6	228.0	✓	
Curtain wall	1	8.6	1.6	7.0	89.3	✓	
Seats or Counters square					27.0	✓	
Total rough stone in Chunam, Cubic feet					846.9	✓	
or Cubic yards					31.3	✓	
Flooring with entolou	1	8.0	8.0		64	✓	
Total squares of entolou work					0.64	✓	
Concrete under entolou	1	8.0	8.0	0.3	16.0	✓	
Total Concrete Cubic yards					16	✓	
1 Coat of tar and asphalt for floor	1	8.0	8.0		64.0	✓	
Doors 3 ft high to the wall	4	8	32.0	3.0	96.0	✓	
Total asphalt tar square feet					160.0	✓	
or Squares					1.6	✓	
Roofing	1	11.0	12.0		132	✓	
Total squares of roofing					1.32	✓	
Wood work							
Wall plates	2	11.0	22.0	0.6	0.2	1.10	✓
Brisummers	1	5.0	0.6	0.4	0.10		✓
Total Cubic feet of wood work					2.2	✓	
Plastering							
Halls, inside & outside	2	36.6	73.0	7.6		693.6	✓
Curtain wall	2	10.6	21.0	7.0		147.0	✓
Total plastering square feet						840.6	✓
or Squares						8.4	✓
White washing as per above							
Plastering squares						8.4	✓

Supg Engrs Office N.
 Masulipatnam
 22nd Nov 1876

Jr. asst Major Rly
 Supg Engrs Ristna.

P.W.D.

1225

1225

No.

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

1225

ABSTRACT ESTIMATE No. 70 of 1876-77.

District Bergrah Saluz

Work

Additions and Improvements to the New District Municipal Court House at Bergrah.

Prepared by the Range Officers.

Quantity.	Description of Charges.	Rate.	Amount.	Total.
541	C ^g of masonry work to be demolished — per sq. ft.	6.	20 4.	1
200	C ^g of Earthwork for excavating foundations and filling in 1/2 ft. per sq. ft.	1.	12 8.	1
136 2/3	C ^g of Concrete in Churnam per sq. ft.	2 5.	316 4 9.	1
196	C ^g of Rough stone in Churnam per sq. ft.	3 6.	661 8.	1
4 1/2	C ^g of Arch work — per sq. ft.	7 7.	32 12 4.	1
288	R ^{ft} of moulded Cornice — per R ^{ft} .	5 8.	102 . . .	1
52-80	S ^g of Plastering 1 coat — per sq. ft.	2 2.	112 3 2.	1
52-80	S ^g of White washing — per sq. ft.	5.	16 8.	1
31-18	S ^g of Cement flooring 1/2" thick — per sq. ft.	17.	530 1.	1
3-31	D ^g — D ^g 6" thick — per sq. ft.	25.	82 12.	1
13-0	S ^g of Roofing with teak wood. Complete rafters, double collar pices, purlins, rafters and purlin nails, flat and pannels, and Churnam borders &c Complete — per sq. ft.	17.	611 . . .	1
6-56	S ^g of Terracing — per sq. ft.	27.	177 1 11.	1
67 1/2	C ^{ft} of teak wood — per R ^{ft} .	3 10.	244 1 3.	1
4	Doors 2 Venetian & 3 pannels 4x8 each	35.	140 . . .	1
3	Sets of glazed shutters 3x4 without frames — set.	12.	36 . . .	1
			2095	

Quantity.	Description of Charges.	Rate.	Amount.	Total.
1	Window pannelled (window removed from the existing building to be fitted)		30 95	
1	Door $\frac{2}{3}$ venetian $\frac{1}{3}$ pannelled			
47.38	Lbs of iron work	3.	8 14 1	
	Total		31 03 14 6	
	Sundries per cent	5.	156 1 6	
	Total Improvements of Court House			3260
	<u>Pring.</u>			
10	Cy of Earthwork for excavating foundations & filling in	1.	10 5	
31 $\frac{1}{3}$	Cy of Rough stone in Chumam	3 6.	105 12 6	
0.64	Sy of Antelope flooring	17.	10 14 1	
$\frac{16}{27}$	Cy of Concrete in Chumam	2 5.	1 5 11	
1.6	Sy of Tar & Asphalt 1 coat	1.	1 9 7	
1.32	Sy of Roofing with palm-leaf rafters, bamboo rafters, flat & pannels and Chumam borders			
	Complete	23.	30 5 9	
2 $\frac{2}{3}$	Cy of half wood work	3 10.	9 10 8	
8.4	Sy of Plastering 1 coat	2 2.	17 13 7	
8.4	Sy of White washing	5.	2 10 1	
	Total		180 11 7	
	Sundries per cent	5.	4 4 5	185
	Fixing hooks for old doors		5	5
	Total Estimate Rupees.			3450
				Certified

Quantity.	Description of Charges.	Rate.	Amount.	Total.
I do hereby certify that the estimate provides every thing necessary and that no supplementary estimate will be required. (Signed) C. J. Peters <i>Resident Engineer in charge</i> <i>Bizorah Division</i> Bizorah Office 7th November 1876. Supp Eng. Office. K <i>Masulipatam</i> 22nd Nov 76. Central Office 14-2-77 E. M. Jointly with Major A E <i>Superintending Eng.</i> <i>Pistun.</i>				

P.W.D.

6 FEB 77

Enclosing is a letter from
the Dy. Commr. Kistna to
the District Judge, Kistna
dated 22nd November 1876
No. 229.

1222 of 1876-77

1. Provincial

2. District

3. District

4. District

5. District

6. District

7. District

8. District

9. District

10. District

11. District

12. District

13. District

14. District

15. District

16. District

17. District

18. District

19. District

20. District

21. District

22. District

23. District

24. District

25. District

26. District

27. District

28. District

Estimate for Addition
and Improvements to
the District Munsiff
Court house at Bezorah
amounting to Rs. 3450.

In Jan 3387 of 1876

Judicial Department.

PROCEEDINGS of the MADRAS GOVERNMENT.

Read the following letter from

the Dy District Judge, Kistna
dated 6th December 1876 No. 225-

In enclosing a plan and
estimate for making certain ad-
ditions to the District Munsiff
Court House at Bezorah amounting
to Rs. 3450, I have the honor
to request you will be good e-
nough to obtain the sanction
of His Excellency the Governor in
Council for the work which
is urgently required.

Either the whole or a large
portion of the funds needed
can be obtained by the sale
of the old Court House in Bezorah,
which is now of no use.

Read also letter from
the District Judge, Kistna dated
27th January 1877 No. 30-

With reference to your en-
dorsement No. 2104 dated 11 Decem-
ber 1876, calling for full explanation
of

Estimates for the addition
of the Bezorah Court House.
Munsiff's Court House.

Enclosure 1
In a letter from the Dy. Commr. Kistna
dated 22nd November 1876
No. 229.

529-30

of the necessity of additions to the District Municipality Court house at Berzonda, with a complete statement of the facts of the case, as referenced to former correspondence, I have the honor to refer you to the Proceedings of the Indian Government Public Works Dept. No 52 129 of the 20th January 1876.

2. The necessity of the additions seems sufficiently set forth in Mr. Wilson's letter quoted in the Proceedings of Government above referred to. I need only say that I quite agree with Mr. Wilson. The present building is wholly unfit for a Court house, and the modifications recommended, though a great improvement will not afford the amount of space allowed in the standard plan. Owing to the great heat of the summer months at Berzonda, and the high winds which prevail there, the room is not that can be got in a public building, the better. At present when the windows have to be shut to

keep

keep out the dust on our side of the Court house, the rooms become almost uninhabitable. 159

3. As no copy of the Proceedings of Government quoted above was sent to this Court, I was unable to refer to former correspondence. The enclosure is copied from a copy of the Proceedings, which I was able to obtain from the Superintending Engineer.

Order thereon 5 February 1877 No 308

The proposed addition is approved and the papers will be referred to the Department Public Works for issue of the necessary orders.

Per Extract

Minister

Chief Secretary

Public Works Department
with papers.

over

P.W.D.
 68077
 No 1225

Judicial Dept.

Recd. Dated 187 No.

Boht of 187 : Madras.

2.5.27
 47 No. 208.
 S. X. 1. Mem with
 Librarian
 Additions to the St.
 Munsiff's Court House at
 Benjarah - approved.

No 529
 19.2.77

16 Civil Works 4.
 Public Works Department.

No 595

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 22nd Feb/77
 Read the following:—

Pro: in the Judicial Dept. (H.C. No. 308 of 5th Feb 1877)

Pro: in the Judicial Dept.

The Estimate is
 sanctioned. Funds will
 if practicable be pro-
 vided from next year's
 Reserve.

W.H.

10.2.77.

This sanction has
 been registered as
 Provincial No. 243 No. 7
 1876-77-

D. E. Krishna
 Secy. P. W. Dept.
 Jud. Dept.

22 Feb 77

179
Govt. of 1877 Madras.
PUBLIC WORKS.

To The H. E. P. S. P. S.

Dated

Issued

Recd.

Encl.

G. O. 22 Feb. 1877, No. 596

Nos. 529-30

District Municipality's Court
since at Bezorah, Kistna
The estimate of Rs 3,50
for certain additions and alterations to the sanctioned
and funds to be provided,
practicable from what
is Reserve.

But no Ref.