

(1) Number of pages _____

(2) Date of receipt _____

(3) Initial of the Referencer _____

MADRAS RECORD OFFICE.**Government of Madras.***Public Works* **DEPARTMENT.**

G.O. No. 59	(W)	Press Mis.
Dated 14-5-	1877.	

Not to be folded or roughly handled

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

14th May 1877, No. 59 W.

Buildings and Roads.

Military Works.

Read the following paper :—

No. 115. From Major H. M. VIBART, R.E., District Engineer, Bangalore, to the Chief Engineer, Public Works Department, Buildings and Roads Branch, dated Bangalore, 2nd May 1877, No. 28.

WITH reference to G.O., No. 78, dated 6th April 1877, I have the honor to forward, for the sanction of Government, the accompanying detailed plan and estimate, amounting to Rupees 360, with specification, for fixing stone uprights in front of pillars for inserting bamboos on loose-box system to the Cavalry Stables in the Agram Barracks at this station.

2. The plan and estimate have been approved of by the Major-General Commanding the Division and His Excellency the Commander-in-Chief.

No. 116. ORDER THEREON, 14th May 1877, No. 59 W.

Heads of Service.—Imperial.
Fund.—Ordinary.
Class.—Original Works.
Main-head.—Military.
Sub-head.—Military Buildings.
Section.—Accommodation for European Cavalry.
Work.—Carrying out certain work at the Cavalry Stables, Agram Barracks.
Amount.—Rupees 360.
To be carried out by the Public Works Department.

SANCTIONED.

2. The District Engineer will appropriate the necessary funds to the works from Minor New Works allotments at his disposal.

3. The sanction has been registered as Imperial No. 14 W of 1877-78.

(True Extract.)

Colonel, R.E.,
Secretary to Government, P.W.D.

To the District Engineer, Bangalore.
" Examiner of Public Works Accounts.
" Military Department.

Ed. A. Raitt.

Spare Copies

Head of service Imperial
 Fund Ordinary
 Class Original works
 Main Head Military
 Sub Head European Cavalry

To be carried out by the P. W. D.
 Revised Abstract Estimate No. of 1877/78

District Bangalore
 Name of work Fixing stone uprights in front of pillars for inserting bamboos on loose box system to the Cavalry Stables on the Agaram Barracks at Bangalore.
 Vide G. O. No. 78 of 6th April 1877

Quantity	Description of work	Rate	Per	Amount	Total
448	Stone uprights 7 ft long 12" wide & 4" thick with two holes in each for inserting Bamboos on loose box system	12	0	336	
				336	
	Lundries			24	
	Total Estimate				360

By order
 J. B. M. M. M.
 of a m. and m.

District Engineer
 Bangalore
 21st April 1877
 Major P. E.
 District Engineer
 L. B.

Specification to accompany
 Revised Plan and Estimate for
 fixing stone uprights in front of
 pillars for inserting Bamboos
 on Loose Box system to the Cavalry
 Stables on the Agaram Barracks
 at Bangalore.

Amount of Estimate Rupees 360.
 An upright stone slab shall
 be fixed in front of every pillar
 for inserting bamboos.

The upright stones shall be
 7 feet long, 12" wide and 4" thick
 with two holes of 3" x 6" cut in the
 shape shown on the Plan and
 shall be fixed in the ground
 18" below the floor and 5 1/2 feet
 above it. The space around the
 stone to be well tamped with
 stone jelly and gravel.

District Engineer
 Bangalore
 21st April 1877
 Major P. E.
 District Engineer
 L. B.

From
The Dist. Eng^r
Bangalore

To
The Chief Eng^r
P.W.D.
Roads & Buildings
Branch
Madras.

Date 2nd May 1877.

Estimate and Specification
for fixing stone uprights
in front of pillars for
inserting bamboos on
Loose Box System

to the Cavalry Stables
Agraham Barracks at
Bangalore

Amounting to Rs 360

Service Imperial
Ordinary
Original work
Head Military
Head European Cavalry
To be carried out by the P. W. D.
Detail Estimate No. 2 of 1877/78
District Bangalore
Work Fixing stone uprights in front
of pillars for inserting bamboos on loose box
to the Cavalry Stables on the Agraham
Barracks at Bangalore vide Dist. Eng^r No. 64 of 15th February 1877

Particulars of work	Measurement		Total
	No.	Content	
Uprights.			
For Double Block containing 62 stalls	6 64	384	✓
For Single Block containing 31 stalls	2 32	64	✓
Stone uprights with two holes in to be fixed in front of every pillar inserting bamboos 7 x 1 x 4.		448	

L.L.

Roads and Buildings
From
The District Engineer
P.W.D.
4/11/77 Bangalore
To
The Chief Engineer
P.W.D. Roads & Buildings
Bangalore
Madras.

Dated 2nd May 1877.
No. 28.

Enclosures 1 Plan &
one Estimate.

Cavalry Stables.

Forwards for sanction
of Government, detailed
plan and Estimate amount
to Rs. 360 with specifications
for fixing stone uprights
in front of pillars for insert
bamboos in loose boxes
to the — in Agri
Barracks at Bangalore.

No. 59 W Public Works Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 14th May 1877
Read the following:—

The District Engineer
Bangalore } A.E. No 28 of 2 May 1877.
Sanctioned.

Head of Service—Imperial

Fund. Ordinary

Class. Imperial Works

Main-head. Military

Sub-Head. Military Buildings

Section. Accommodation for European Cavalry

~~Project of which the money form part~~

Work. Carrying out certain work at the
Cavalry Stables, Agri Barracks.

Amount. Rs. 360

To be carried out by the P. W. Department.

Print with L.O. No. 59 W. of 14-5-77-

Bangalore ✓
P. W. D. ✓
Mil. Dept. ✓

Recd 28.5.77

Roads and Buildings
 From The District Engineer
 P.W.D. Bangalore
 4 MAY 77
 To The Chief Engineer
 P.W.D. Roads & Buildings
 Branch

to the _____, in Agri
 Branch at Bangalore

Car
 No 59 W Public Works Department.
 PROCEEDINGS OF THE MADRAS GOVERNMENT.
 UNDER date the 14th May 1877
 Read the following:—

From The District Engineer
 Bangalore } H.E. No 28 of 2 May 1877.

Sanctioned.

The District Engineer will appropriate the necessary funds to the works from Minor New works allotments at his disposal

The sanction has been registered as Imperial No. 14 W of 1877-78.

W.H.
 4.5.77.

EAF 9/5/77

H. Bangalore ✓
 En P.W.D. ✓
 Milg. Dept. ✓

Repd 28.5.77

W. L. ...

Cons 515

Govt. of 1877 Madras.

PUBLIC WORKS.

To the W. C. Bangalore

Dated

Issued

15

Encl.

G. O., 14th May 1877, No. 59 W

Nos. 115-116

Cavalry Stables, Agrani
Banacka, Bangalore.

The estimate of Rs 300 for
carrying out certain work
at the — construction

Conf. in P. O.