

(1) Number of pages 6

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No.

5 (9)

Press
Mis.

Dated

2 / 1

18 77

Not to be folded or roughly handled

*Proceedings of the Madras Government, Public Works Department,
2nd January 1877. No. 5.*

Read the following :—

No. 319 W.

No. 9. *Note by Chief Engineer for Irrigation.*

THE District Engineer, Cuddapah, forwards, with his letter marginally noted, an estimate in connection with the Wontimetta large tank, situated in the Sidhout Taluq, Sidhout Range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow :—

ORDINARY AGRICULTURAL.

<i>Original Works.</i>		RS.
Extending the east weir and forming a training bank...	...	4,525
<i>Repairs.</i>		
Repairing north and east bunds, east and west weirs and constructing a cistern to the head of the irrigation sluice...	...	1,435
Total	...	5,960

3. The following particulars of this tank are recorded—

Ayacut area	...	Acres 978	{ Circar 666 Inam 312 }	Acres.
Assessment	...	Rupees 6,714	{ Circar 4,212 Inam 2,502 }	Rupees.
Average revenue	...	" 6,332		
Highest do.	...	" 6,489		
Expenditure during the previous four years	...	" 156		

The area of the catchment basin is 65 square miles; the maximum flood supply is calculated at 11,445 cubic feet per second; for discharging which as surplus there are two weirs, one at each end of the bund, that at the west end is 159 feet in length, while that at the east end is 135 feet, total 294 feet. The eastern weir is to be extended 336 feet, so as to make an aggregate length of 630 feet available for the surplus discharge. A training bank will be carried from the western end of the extended weir as far as the surplus channel, to prevent the flooding of the cultivated lands lying below. The estimate also provides for repairing the bund and the existing east and west weirs and building a cistern to the head of the sluice to prevent its silting up.

The details have been carefully worked out and the plans are creditable to the Range Officer, Mr. Sub-Engineer Schoury.

The estimate is recommended for sanction.

FORT ST. GEORGE,
28th December 1876.

(Signed) A. DEC. SCOTT, Major, R.E.,
Dy. Chief Engr. for Irrigation,
for Chief Engineer for Irrigation.

To the Secretary to Government, Public Works Department.

Proceedings of the Madras Government, Public Works Department,
2nd January 1877. No. 5.

No. 10. ORDER THEREON, 2nd January 1877, No. 5.

IRRIGATION, No. 5.
Account.

The following estimate from the Sidhout Range, forwarded by the District Engineer, Cuddapah, is sanctioned:—

WONTIMETTA LARGE TANK.
Irrigation.

Group or Project.	Fund.	Class.	Name of Tank, Canal or Channel.	Particulars of Work.	Amount.
Gungapoor Gungal Tank group.	Ordinary cultural.	Agri-Original Works ..	Wontimetta large Tank.	1. Extending the east weir and forming a training bank	RS. 4,525
		Repairs ..		2. Repairing north and east bunds, east and west weirs and constructing a cistern to the head of the irrigation sluice..	1,435
				Total ..	5,960

To be carried out by the Public Works Department Officer in charge, Sidhout Range.—I.

2. This sanction has been registered as No. 246 I. of 1876-77.

(True Extract.)

Major-General, R.E.,
Secretary to Government.*

To the District Engineer, Cuddapah.
" Collector of do.
" Chief Engineer for Irrigation.
" Examiner of Public Works Accounts.
" Revenue Department.

Encl. S. T. Austin.
Spare Copies

E. I. Form No. 4-A.

No. 5 of 2nd Jan'y: 1877. *Mr. kept.*
Progo: of the Madras Govt
Read the following
Note by Chief Engineer
for Irrigation } (H.E. kept: 31st Dec/1876)

The following Estimate from the
Sidhout Range forwarded by the
District Engineer, Cuddapah
is sanctioned:—

Wontimetta large Tank.

Irrigation.

Group or Project.	Fund.	Class.	Name of Tank, Canal, or Channel.	Particulars of Work.	Amount. Rs.
Gungapoor Gungal Tank group	Ordinary Agricultural	Original works	Wontimetta large Tank	1. Extending the east weir and forming a training bank	4525
		Repairs		2. Repairing north and east bunds, east and west weirs and constructing a cistern to the head of the irrigation sluice..	1435

To be carried out by the P. W. Department Officer in charge Sidhout Range.

Total Rupees 5960.

2. This sanction has been registered
as No. 246 I. of 1876-77.

Dr. Cuddapah
Collection - do
C. E. for S. T. Austin 6 Encl.
Ex. P. W. D.
Rev. kept.

Decd 8-1-77

9516

Gobt. of 1877 Madras.
PUBLIC WORKS.

To

The H. E. Suddapah

Dated

Issued

Recd.

Encl.

G. O. 2nd 1877 No.

5-

Nos. 9-10

Wontimittah large
tuck - estimate
for certain works
to be sanctioned

But no pay