(1) Number of pages

(2) Date of repair

3. Initials of the Referencer

MADRAS RECORD OFFICE.

I

Government of Madras.

Public Works DEPARTMENT.

G.O. No. 750 (P.W.) Press Mis.

Dated 5 3 1875

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
5th March 1877. *No.* 750.

Read the following papers :—

No. 104. From R. F. CHISHOLM, Esq., Consulting Architect to Government, to the Chief Engineer for Roads and Buildings, Public Works Department, dated Chepauk, 20th February 1877, No. 837.

I HAVE the honor to forward an estimate for putting down encaustic tiles in the chancel and in part of the nave of St. Mary's Church, Fort St. George.

One Plan.
„ Specification and Estimate.
„ Abstract.

2. The specification fully explains the nature of the work to be done.

No. 507.

TRANSFERRED to the Ecclesiastical Department.

(Signed) W. FAREWELL, Colonel,
Acting Joint Secy. to Govt., P.W.D.

27th February 1877.

No. 509.

No. 104-A. APPROVED and retransferred to the Public Works Department.

(Signed) W. HUDLESTON,
Chief Secretary.

1st March 1877.

No. 105. ORDER THEREON, 5th March 1877, No. 750.

CIVIL WORKS, No. 15.

(a) *Heads of Service.*—Provincial.
Fund.—Ordinary.
Class.—Original Works.
Main-head.—Civil Buildings.
Sub-head.—K, Ecclesiastical Department.
Section.—i, Churches.
Name of Work.—Laying down tiles in a portion of St. Mary's Church, Fort St. George.
Amount.—Rupees 1,630.
To be carried out by the Public Works Department.

THE estimate is sanctioned. Arrangements may be made for the commencement of the work after 1st April, when an appropriation of funds from the Provincial Reserve of 1877-78 will be made.

2. This sanction has been registered as Provincial No. 259—W of 1876-77.

(True Extract.)

Colonel,
Acting Joint Secy. to Govt., P.W.D.,
Buildings and Roads Branch.

To the Consulting Architect.
„ Examiner of Public Works Accounts.
„ Ecclesiastical Department.

Exd. S. T. Austin.
Spare Copies

(a) Heads of Service— Provincial

Fund. Ordinary

Class. Original Works

Main-head. Civil Buildings

Sub-head. E. Ecclesiastical Department

Section. 1. Churches—

Name of Work. Laying down tiles in a portion of St Mary's Church, Fort St George

Amount. Rs 1630

To be carried out by the P. W. Department.

Drawn in the margin of G.A. No 7500 of 6-3-77

Archts Office.
February 1877.

ecification and Estimate
r laying tiles &c in
St. Mary's Church
Fort St. George.

mate- Rupees. 1,630—0—0

Archts Office.
February 1877.

Estimate for laying tiles &c. in Saint Marys Church
Fort Saint George.

Quantity		Item	Rate	Per	Amount
		Lowering floor			100 " "
120	sup.ft	Buff and red figured tiles for Chancel	2 4 "	sft	270 " "
70	"	Rich glazed border for Chancel 12" wide	4 " "	"	280 " "
228	"	Plain buff tiles for the Nave	2 " "	"	456 " "
92	"	Unglazed border for Nave 6" wide	4 " "	"	368 " "
10	"	Plain grey tiles for tombs E & F	2 " "	"	20 " "
		Erecting Lord Hobarts Monument including granite base			70 " "
		Removing and fixing Font			5 " "
		Contingencies			61 " "
		Total Rupees			1,630 " "

Rupees One thousand, six hundred and thirty.

Consg Archts Office
Chepauk 20th Feby 1877.

W. Nicholson.
Consg Archt to Govern.

Estimate for laying tiles &c. in Saint Marys Church
Fort Saint George.

1630
Received
26-7-77

Quantity		Item	Rate	Per	Amount
		Lowering floor			100 " "
120	sup.ft	Buff and red figured tiles for Chancel	2 4 "	sft	270 " "
70	"	Rich glazed border for Chancel 12" wide	4 " "	"	280 " "
228	"	Plain buff tiles for the Nave	2 " "	"	456 " "
92	"	Unglazed border for Nave 6" wide	4 " "	"	368 " "
10	"	Plain grey tiles for tombs E & F	2 " "	"	20 " "
		Erecting Lord Hobarts Monument including granite base			70 " "
		Removing and fixing Font			5 " "
		Contingencies			61 " "
		Total Rupees			1,630 " "

Rupees One thousand, six hundred and thirty.

Consg Archts Office
20th February 1877.

W. Nicholson.
Consg Archt to Govt

P.W.D.
22FEB77
No 1895

Estimate for laying tiles &c
in St Mary's Church
Fort Saint George.

Estimate - Rupees 1630—0—0

Consg Archts Office
28th February 1877.

P. 5th March/77 J.B. Rs. 104

Estimate for laying tiles &c in
Saint Mary's Church.

Specification

The existing floor will be picked up all over and lowered to the necessary extent to make the floor of the body of the Church level throughout.

The Chancel will have a rich glazed border 12" broad and plain buff and red figured tiles.

The Chancel step 12" broad will be similar to the Chancel border.

In the nave of the Church the tiles will be arranged as shown on the plan. A 6 inch unglazed border will run round the space and the tombs, the interspace being filled with plain buff tiles.

The tombs marked B and F have not the same sized slabs as A B. C. & D (6×3) The difference should be made up of plain grey tiles, unglazed.

Lord Hobarts Monument will be erected in the spot selected on the south side of the Chancel. The Pulpit and reading desk being both slightly altered in position.

The Font at the west end will be moved back and the arrangement of seats altered to suit its new place.

F. Clerk Ludlow

Consg Archt to Govt

No. 837

CONSULTING ARCHITECT'S OFFICE,

Chepauk, 20th February 1877.

From

THE CONSULTING ARCHITECT TO GOVERNMENT,

To

THE ~~Secretary to~~ Chief Engineer for Roads and Buildings. ~~Government~~ Public Works Dept.

SIR,

Enclosures
Plan
Specification
Estimate
Abstract

I have the honor to forward an Estimate for ~~putting~~ laying down encaustic tiles in the Chancel and in part of the nave of Saint Marys Church Fort Saint George.

The Specification fully explains the nature of the work to be done.

I have the honor to be
Sir
Your most Obedt servt

F. Clerk Ludlow.

Consg Archt to Government

Encls: 97-11-4-76
4.6-79 29-4-76- Ecclesiastical
Encs 128-17-Right/75
" 56. 8-June/75.

P.W.D.
225377
No 1805
2277

No 750

P. W. Dept

Proceedings of the Madras Government
Under date the 5 March/77
Read the following-

Endorsement of the
Ecclesiastical Dept } (No 509 d/ 1st March/77).

The estimate is sanctioned. Arrangements may be made for the commencement of the work after 1st April, when an appropriation of funds from the Provincial Revenue of 1877-78 will be made.

W.H.
3-3-77

This sanction has been registered as Provincial No 259 P. of 1876-77-

Contractitect ✓
Ex: P. Works ✓
Eccl: Dept. ✓
W.H. dispd 23-3-77

Dated 20 February 1877
Received 1877
No 107-
Forwards Estimate for
Laying the Well in Canal
Quarry at Chinch
with Proposals.

No 509

Forwarded
1st March 1877
P. W. Secretary

To
The Chief Engineer for
Public Works & Public
Buildings
Fort St George

Sent No 837 Dated
Fort St George
the 6 March 1877
To Government

No 509-
Transferred to
the Ecclesiastical De=
=partment

W. Warren Lt Colonel
Acting Joint
Secretary.

Sent to Col
27 July/77
No 509

Approved & Returned.
Lt Col P.W.D.
Secretary
Chief Engineer

Ar 3.3.77

Coast. of {1877} Works.

PUBLIC WORKS.

To The Commr Architect.

Dated

Issued

Recd. Encl.

G. O., 5 March 1877, No. 50

Nos. 104-105

St Mary's Church. Fat Range. The estimate of Rs 1620 for laying down tiles in a portion of the ——, sanctioned, and the work to be commenced after 1st April

Ex. Engr

Ar 3.3.77.