

(1) Number of pages **6**

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No. **75**

Press
Ms.

Dated **9** / **1** / **18** **77**

Not to be folded or roughly handled

Read the following:—

No. 11 W.

No. 141. *Note by the Chief Engineer for Irrigation.*

THE District Engineer, Kurnool, forwards, with his letter marginally noted, an estimate in connection with the Munna-gunta Tank, situated in the Rayelkota Taluq, Kurnool Range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow:—

ORDINARY AGRICULTURAL.

Original Works.

Forming a natural escape... .. Rs. 180

Repairs.

Raising and repairing the bund, also repairing the sluice and loose stone escape Rs. 80

Total ... Rs. 260

3. The following particulars of this Tank are recorded:—

Ayaout area...	...	Acres	82
Assessment	...	Rs.	192
Average revenue	...	"	161
Highest do.	...	"	191
Expenditure during the previous four years	...	"	345

The area of the catchment basin is 3 square miles; the maximum flood supply is calculated at 1,170 cubic feet per second, for discharging which as surplus there is a rough stone escape 48 feet in length at the eastern end of the bund, and it is proposed to form a natural escape 142 feet in length, so as to make an aggregate length of 190 feet available for the surplus discharge.

The bund is low, and it is proposed to raise it 4 feet above weir crest level.

The tank has a sluice which needs trifling repairs, it is otherwise in good order. The rough stone escape also requires slight repairs.

The estimate provides for raising and repairing the bund, also for repairing the sluice and rough stone escape, and it is recommended that sanction be given to it.

(Signed) A. DEC. SCOTT, Major, R.E.,

5th January 1877.

*Dy. Chief Engr. for Irrigation,
for Chief Engr. for Irrigation.*

To the Secretary to Government, Public Works Department.

Proceedings of the Madras Government, Public Works Department,
9th January 1877. No. 75.

No. 142.

ORDER THEREON, 9th January 1877, No. 75.

IRRIGATION, No. 20.

Account.

THE following estimate from the
Kurnool Range, forwarded by the District
Engineer, Kurnool, is sanctioned:—

MUNNAGUNTA TANK.

Irrigation.

Group or Project.	Fund.	Class.	Name of Tank, Canal, or Channel.	Particulars of Work.	Amount.
..	Ordinary Agri- cultural.	Original Works .. Repairs ..	Munnagunta Tank.	1. Natural escape .. 2. Repairing bund, sluice and escape.	Rs. 180 80

To be carried out by the Public Works Department Officer in charge, Kurnool Range.

2. This sanction has been registered as No. 257—I. of 1876-77.

(True Extract.)

Major General, R.E.,

Secretary to Government.

To the District Engineer, Kurnool.
" Collector of do.
" Chief Engineer for Irrigation.
" Examiner of Public Works Accounts.
" Revenue Department.

No 75 P.W.D.
Proceedings of the Madras Govt.
Under date the 9 Jan 77
Read the following
From the Chugur for Brief (H.E. No 11 W 75 Jan 77)

THE following Estimate from
the Kurnool Range
forwarded by the District Engineer,
Kurnool is sanctioned:—

Munnagunta Tank.

Irrigation.

Group or Project.	Fund.	Class.	Name of Tank, Canal, or Channel.	Particulars of Work.	Amount. Rs.
	Ordinary Agricultural	Original Works	Munnagunta Tank	1. Natural escape	180
		Repairs		2. Repairing bund sluice & escape	80

To be carried out by the P. W. Depart-
ment Officer in charge Kurnool Range.

Ch. Kurnool - ✓
This sanction has been registered as No. 257. I. of 1876-77.

Ch. E. for dis. with S. E.
Ch. E. for dis. with S. E.
Ch. E. for dis. with S. E.

Ch. E. for dis. with S. E.
Ch. E. for dis. with S. E.

98. Gov

~~WORK~~

B. 10

Dated
Issued

Issued

Recd.

Encl.

G. O., ⁵²*9th Ave* 1877, No. *75*

G. O., 9th March 1877, No. 75
 W. 141742.

Mumazunta Subk
Guano District.

Estimated Rs 260
for repairs to
the —, sanctioned

Paul and Mary