

(1) Number of pages

(2) Date of repair

(3) Initials of the Referent

MADRAS RECORD OFFICE.

Government of Madras.

Public Works

DEPARTMENT.

G.O. No. 76

Press
Mia.

Dated 9 / 1 1877

Not to be folded or roughly handled

11K

*Proceedings of the Madras Government, Public Works Department,
9th January 1877. No. 76.*

Read the following:—

No. 14 W.

No. 143. *Note by the Chief Engineer for Irrigation.*

THE District Engineer, Cuddapah, forwards, with his letter marginally noted, an estimate in connection with the No. 2,201, dated 23rd December 1876. Cotha Cottah Byajee Tank, situated in the Madanapully Taluq, Madanapully Range.

2. The nature of the work proposed for execution and the heads of account to which it is chargeable are as follow:—

ORDINARY AGRICULTURAL.

Original Works.

	RS.
Constructing a masonry weir	145

Repairs.

Raising and strengthening the bund and rebuilding the stone revetment	935
Total ...	1,080

3. The following particulars of this tank are recorded:—

Ayacut area	Circar 14 Inam 13 Total 27 Acres.	
Assessment	Circar 115 Inam 172 " 287 Rupees.	
Average revenue	Circar 51 Inam 100 " 151 "	
Highest do.	Circar 88 Inam 173 " 260 "	
Expenditure during the previous four years ...	Not stated.	

The area of the catchment basin is about 2 square miles; the maximum flood supply is calculated at 588 cubic feet per second, for discharging which as surplus there is an outlet 10 feet in length which is insufficient, it is therefore proposed to construct a masonry weir 60 feet in length.

This tank is situated in latitude 13° 29' 30", longitude 78° 19'; two tanks above surplus into it, both of which are in good repair. It has been up to lately a Dasabundum tank, and it has been allowed to get into bad order. The bund is weak in some places and requires raising, and the revetment will be relaid throughout—half of it with new stone.

The estimate provides for these repairs and additions. The rate intended for earthwork appears to be excessive for an embankment of such small dimensions, and it should be altered to 1 Anna per cubic yard. The charge will be reduced by Rupees 71. The item, "Mixed Revetment," is presumably meant to refer to the stone work partly formed of the old stone now laid and partly of new stone to be brought to the site of the work. There should have been two distinct entries in this case.

The estimate as reduced is recommended for sanction.

(Signed) A. DEC. SCOTT, Major, R.E.,

6th January 1877.

*Dy. Chief Engr. for Irrigation,
for Chief Engr. for Irrigation.*

To the Secretary to Government, Public Works Department.

C.D.

Recd. 17-1-77

Proceedings of the Madras Government, Public Works Department,
9th January 1877. No. 76.

No. 144. ORDER THEREON, 9th January 1877, No. 76.

IRRIGATION, No. 21.

Account.

THE following estimate from the Madanapully Range, forwarded by the District Engineer, Cuddapah, is sanctioned:—

COTHA COTTAH BYAJEE TANK.

Irrigation.

Group or Project.	Fund.	Class.	Name of Tank, Canal, or Channel.	Particulars of Work.	Amount.
..	Ordinary Agricultural ..	Original Works..	Cottha Cottah Byajee Tank ..	Weir ..	Rs. 145
		Repairs		Raising and repairing bund, &c.	864
				Total ..	1,009

To be carried out by the Public Works Department Officer in charge, Madanapully Range.

2. This sanction has been registered as No. 258—I. of 1876-77.

(True Extract.)

Major-General, R.E.,
Secretary to Government.

To the District Engineer, Cuddapah.
" Collector of do.
" Chief Engineer for Irrigation.
" Examiner of Public Works Accounts.
" Revenue Department.

Exd. S. T. Austin.

Spare Copies

E. I. Form No. 4-A.

No 76 Mr D
Pr: of the Madras Govt 3k
Under date 9 Jan 77
Read the following
From the Inspector of Bridges (H.E. No 14 of 76 Jan 77)

THE following Estimate from the Madanapully Range forwarded by the District Engineer, Cuddapah is sanctioned:—

Cottha Cottah Byajee Tank.

Irrigation.

Group or Project.	Fund.	Class.	Name of Tank, Canal, or Channel.	Particulars of Work.	Amount. Rs.
	Ordinary Agricultural	original works	Cottha Cottah Byajee Tank	Weir	145
		Repairs		Raising & repairing bund &c.	864

To be carried out by the P. W. Department Officer in charge of the Range.

Total Rupees 1009—

2. This sanction has been registered as No. 258. I. of 1876-77.

H. Cuddapah S.
Collector of do.
Ch. Engr. for Irrigation, with 7 B =
in H.A.
Revenue Dept.
Archd - 17-1-77

1-1-77

6-1-77

Govt. of 1877 Madras.

PUBLIC WORKS.

To

The H. E. Buddafab

Dated

Issued

Recd.

Encl.

G. O., 9th March 1877, No. 76

103.

Cotta Cottah Ryajie
Sanku, Cuddapah Dist.

Estimate of Rs. 1009
for repairs to the
—, mentioned

Est in Reg