

(1) Number of pages _____

(2) Date of repair _____

(3) Initials of the Referencer _____

MADRAS RECORD OFFICE.

Government of Madras.

Public Works DEPARTMENT.

G.O. No.	999	(14)	Press
			Mis
Dated	23-3-		1877.

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
23rd March 1877. No. 999.

No. 593. Read the following letter from Major P. MONTGOMERIE, R.E., District Engineer, Salem, to the Acting Joint Secretary to Government, Public Works Department, Buildings and Roads Branch, dated Yercaud, 13th March 1877, No. 156:—

I HAVE the honor to submit, for the sanction of Government, an estimate of Rupees 195 for constructing dais and improving the Tahsildar's Cutcherry at Trichengode.

One Estimate.
One Plan.

2. The estimate and plan have been approved of by the Collector.

No. 594. ORDER THEREON, 23rd March 1877, No. 999.

CIVIL WORKS, No. 53.

SANCTIONED.

2. The District Engineer will provide funds for the work from his Minor New Works grant for 1877-78.

This sanction has been registered as Provincial No. 280 of 1876-77.

(a) *Heads of Service*.—Provincial.
Fund.—Ordinary.
Class.—Original Works.
Main-head.—Civil Buildings.
Sub-head.—B, Revenue Department.
Section.—ii, Taluq Cutcheries.
Name of Work.—Constructing dais and improving the Tahsildar's Cutcherry at Trichengode.
Amount.—Rupees 195.
To be carried out by the Public Works Department.

(True Extract.)

Colonel,
Acting Joint Secy. to Govt., P.W.D.,
Buildings and Roads Branch.

To the District Engineer, Salem.
" Examiner of Public Works Accounts.
" Revenue Department.

" *Indl Deptt*

Exd. W. J. Lewis.
Spare Copies

Public Works Department

Salem District

Salem Division

Trichengode Taluk

Abstract Estimate No of 1876-77

Work Constructing Dais and improving the Savidars Catchery

Trichengode

Original Value of the Building ————— Rs 2,330 — — —

at repair ————— 76-77 — Rs 32 — — —

Number or Quantity	Description of Work	Rate				Amount Total	
		Rs	As	P	As	Rs	As
7 1/2	Cy of Breasting wall —————	Cy	2	1	13		
1 3/4	Do Brick in chunam —————		3	12	6	9	✓
1 1/4	Sq of Plastering chunam —————	Sq	2	8	3	2	✓
57	Sq of White washing —————		2		11		✓
1	Malabar truss wrought and put up including posts and 4c. complete } Teakwood ————— (16 + 1/2 + 1/4) —————	1	20		20		✓
2	Batten Windows with shutters — } Complete (3 + 1/2 + 1/2) —————	1	10		20		✓
1	Masonry plat form (4' x 9' x 2') for Dais ————— } Do —————	Each			38		✓
32	Running feet of Teakwood rails around Dais ————— } Do —————	do	3		96		✓

Total ————— 185 8

Sundries at 5 percent ————— 9 8

Total Repairs ————— 195

Detailed Estimate No. of 187 - 7

Specification

Particulars of work	Measurement				
	No	L	B	H	Content
Removing the existing wall at the proposed site of the dais	2	5 1/2	1 1/2	7 1/2	119 3/8
To gable end	1	11	1	2 1/4	38 1/2
Breaking the wall for fixing the windows	1	4	1 1/2	3	18
Total cft of Breaking wall					206 3/8
or cubic yards					1 1/2
<u>Brick in chunam</u>					
Blocking the doorway	1	4	1 1/2	3	18
For fixing the windows	2	13	1 1/2	1/4	27 1/4
Total cft of Brick in chunam					47 1/4
or cubic yards					1 3/4
<u>Plastering</u>					
All round the windows	11	13	1	-	52
To new wall	2	5	3	-	30
At both sides where walls to be removed	2	7 1/4	2	-	37
Total Sq ft of Plastering chunam					119
or Squares					1 1/4
<u>White washing</u>					
To Sasildars room	3	14 1/4	-	7 1/2	420 3/8
To Out side of the room	1	28 1/2	-	9 1/2	270 1/4
Total Sq ft of White washing					690 3/8
or Squares					7
Masonry plat form (9x9x2) for Dais					1
Running feet of wooden Railings around the plat form of do					36

The wall E. H. marked in the accompanying sketch is to be removed so as to allow space for the construction of Dais.

The Doorway " to be blocked up
and a window substituted in its place

Another window at c in the outside wall to be opened for good breeze.

A plat form for the Dais to be built of brick in chunam 9 feet square 2 feet high with one foot foundation and plastered on the surface and sides with 2 coats of chunam plaster and wooden Railings provided with door to be prepared in teakwood and fixed around the plat form of the Dais and coated with 2 coats of wood oil.

(Signed) L. Pungasunung Naidoo
Taluk Overseer.

Salem Range office.

Julm. 22^o. February 1877

Murphy
Executive Engineer

Monte meo Major RE,
23 p. 7.
District Eugene

L. D. Hussey
Collector of Saline.

F.W.D.

15th 1877

2765

2

N^o 156 District Engineer's Office,
Yercaud 13th March 1877.
Buildings and Roads.

From

The District Engineer,
Salem.

The Chief Engineer,
Buildings & Roads Branch,
P. W. D.

Sir,

Enclosures 2
1 Estimate.
1 Plan.

I have the honor to submit
for the sanction of Government
an estimate of Rs. 195 for con-
-structing dais and improving the
Tahsildar's Cutcherry at Trichengode.
2. The estimate and plan have
been approved of by the Collector.

I have the honor to be,
Sir,

Yours most obedt. Servt.

Major R. H. Major R. H.,
District Engineer, Salem.

D. S. W.

Salem District Engineer

To the District Division

Trichengode Taluk

Estimated Estimate. No.

of 1876-77.

Civil Building

Order

Received 1st February 1877

Work

Constructing dais

and improving the

Tahsildar's Cutcherry at

Trichengode.

Estimated Rs. 195

G. A. 23rd March 1877 No. 593

W.D.
1977
No. 2765

Buildings and Roads

From District Engineer,
Salem.

No. 156
Dated 13th March 1877
Recd

Enclosures 2 1/2

Tahsildar Cutcherry
at Trichengode. —

Submits an estimate of
Rs. 105 for constructing dais
& improving the —

G.O. 23rd March 77 J.B.L. 593

24.3.77

(a) Heads of Service— Provincial

Fund. Ordinary

Class. Original Work

Main-head. Civil Buildings

Sub-head. S. Revenue Department

Section. II Taluq Cutcherry

Name of Work. Constructing dais & improving the
Tahsildar's Cutcherry at Trichengode.

Amount. Rs. 105

To be carried out by the Public Works Department.

It is in the margin of G.O. No. 999 of 23/3/77—

W.D.
177
565

CLW/MS

No 999

Public Works Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 23rd March/77

Read the following:—

From the Muz Salem (H.R. No 156 of 13th March/77)

Sanctioned.

2. The District Engineer will provide funds for the work from his minor new works grant for 1877-78.

This sanction W.H. has been re-17.3.77 -filed as Provincial No 280 of 1876-77-

LD
2/3

tem
ting

Judicial Dept. - respd. 14.4.77

Muz Salem ✓
Exp. Mr. Ault ✓

Rev. Dept. ✓ respd 7-4-77

W. A. P.

27-3-77

Govt. of 1877 Madras.

PUBLIC WORKS.

To Mr. M. B. Salem

Dated

Issued

Recd.

Encl.

G. O., 23rd March 1877, No. 999

Nos. 593-594

Sahildars Catchment at
Trichingode, Salem Dt.
The estimate of Rs. 195 for
Constructing dois and
improving the —, sanctioned
funds to be provided by the
District Engineer.

For Mr. B. B.