Archives 1—10,000—6-10-76.

(1) Number of pages 16.

(2) Date of repair 4-7-86.

(3) Initials of the Referencer G.N.D

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P W D- DEPARTMENT

G.O. No. / B.P. No.	1063 W	Press. / Mis.
Dated	2-3-1878	197

Not to be folded or roughly handled

1063
1

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

2nd March 1878, No. 1,063 W.

Buildings and Roads.

Civil Works.

Read the following paper:—

No. 27. From Major H. W. WOOD, R.E., District Engineer, Vizagapatam, to the Chief Engineer, Public Works Department, Buildings and Roads Branch, dated Waltair, 20th February 1878, No. 2,579.

I HAVE the honor to forward herewith, for the sanction of Government, a plan, estimate* and specification for certain additions to the Munsif's Court at Parvatipoor.

* Amounting to Rupees 127.

2. The plan and estimate have been prepared at the request of the District Judge and were countersigned by him.

3. In the event of the estimate being sanctioned the necessary funds for the work can be provided from the allotement to be placed at my disposal for "Minor New Works," "Civil Buildings," "Provincial" in 1878-79.

No. 28. ORDER THEREON, 2nd March 1878, No. 1,063 W.

THE plan and estimate of Rupees 127 for certain additions to the Munsif's Court at Parvatipoor in the Vizagapatam District are sanctioned. The work will be carried out from the source indicated in paragraph 3 of the foregoing letter.

2. This sanction has been registered as Provincial No. 293 B of 1877-78.

(True Extract.)

Colonel, R.E.,
Secretary to Government, P.W.D.

To the District Engineer, Vizagapatam.
" Examiner of Public Works Accounts, with Estimate.
" Judicial Department.

Exd. S. T. Austin.

Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1878) Madras.

PUBLIC WORKS.

To

THE DISTRICT ENGINEER,
VIZAGAPATAM,
&c, &c, &c

Dated March 2nd.

Issued

Recd. Ansd.

G. O., 2nd March 1878, No. 1,563 W.

MARCH.

Nos. 27-28.

Munsiff's Court at Parvatipoor, Vizagapatam District.—Sanctions plan and estimate for certain additions to the—

Specification to accompany Plan and Estimate for certain additions to the Munsiff's Court at Parvatipore.

106 3/3

Amount of Estimate Rupees 127—

In order to construct a room in the Veranda

1063/2

[illegible]

ing—

All the exposed surfaces of the walls are to be plastered with 2 coats of chunam. Before laying the 1st Coat the walls to be trimmed with trowels and well sprinkled with water. The plaster to the first coat to be composed of 1 part of well slaked lime and 1½ parts of clean sharp river sand, thoroughly mixed and well beaten up with water. A day or

BUILDINGS AND
CIVIL WORK
Govt. of (1878)
PUBLIC WO

Munsiff's Court at Parvatipore
pathum District.—Sanctions Es
mate for certain additions to t

Specification to accompany Plan and Estimate for certain additions to the Munsiffs' Court at Parvatipore.

1065/3

Amount of Estimate Rupees. 127—

In order to construct a room in the Verandah it is first necessary to remove a number of stones which cover the tops of the basement wall &c and a portion of the old wall which is in continuation of the cross wall of proposed Verandah room; to be demolished, as the walls progress.

Rubble masonry— The superstructure of the proposed verandah wall is to be built with rough stone in mortar which is to consist of 2 parts of clean sharp river sand, and 1 part of well slaked lime; through bond stones to be inserted at distances of 3 feet.

Flat arch work— Flat arch work over door and window is to be built of well burnt and properly trimmed bricks in fine lime putty composed of equal parts of lime and brick dust.

Plastering— All the exposed surfaces of the walls are to be plastered with 2 coats of chunam. Before laying the 1st Coat the walls to be trimmed with trowels and well sprinkled with water. The plaster to the first coat to be composed of 1 part of well slaked lime and ½ parts of clean sharp river sand, thoroughly mixed and well beaten up with water. A day or

or two after the first coat is put on and while it is moist, the second coat is to be applied. The plaster used for the second coat to consist of 3 parts of lime and one of white clean sharp river sand. These are to be mixed as before and afterwards ground on a flat stone with a small stone roller till they are reduced to a fine paste. During the process of the work the plaster is to be occasionally sprinkled with a little pure lime mixed with water to give it a hard and even surface.

Blue washing

The walls to be blue washed, ~~[illegible]~~ two coats with wash composed for 10 squares of 1⅓ parah of Chunam mixed with water in which ½ seer of raw rice has been boiled and ⅓ parah of Charcoal.

Doors & windows

There will be one pair of teak wood batten door and two pairs of teak wood batten windows to the dimensions shown in the Plan and Estimate, and are provided with lock, key, hinges and bolts &c.

Painting with wood oil

The door and windows are to be covered with three coats of wood oil. During the process of the work a day or two must be allowed for the first two coats to dry before the third or finishing coat is laid on.

Iron work

All the iron works such as hinges of (11" × 1¼ × ¼") bolts of (7" × 1¼ × ¼") hooks (6" × ¼ × ¼") are to be plunged while red hot into tar before being fixed.

On completion of the work all rubbish to be cleared away and the premises to be left in a clean condition.

1263

District Engineer's Office Waltair 25th July 1877

Major R.E.
District Engineer
Vizagapatam

Vizagapatam District Court 9th February 1878.

[illegible]
District Judge

District Engineers Office

No 2579 Vizagapatam 20th February 1878

1662

From

The District Engineer

Vizagapatam

To

The Chief Engineer P.W.D.

Buildings & Roads Branch

Madras.

Sir,

I have the honor to forward herewith, for the sanction of Government, a plan, estimate* and Specification for certain additions to the Munsiffs' Court at Parvatipore.

* Amounting to Rs. 127—

2. The plan and estimate have been prepared at the request of the District Judge and were countersigned by him.

3. In the event of the estimate being sanctioned, the necessary funds for the work can be provided from the allotment to be placed at my disposal for "Minor New Works" "Civil Buildings" "Provincial" for 1878-79.

I have the honor to be
Sir
Your most Obdt Servant
Major RE
District Engineer, Vizagapatam

Buildings and Roads

From

The District Engineer

Vizagapatam

To

The Chief Engineer P.W.D.

Buildings and Roads Branch

Madras

No. 2579

Dated 20th February 1878

No. of Enclosures Three.

Plan, Estimate & Specification

Moonsiffs' Court

at Parvatipore.

Submits for sanction a Plan, Estimate &c for Rs. 127 for certain additions to the

Cir 25-2-78.

No. 1063 W Public Works Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 2nd March 1878

Read the following :—

From the D.Engr Vizagapatam (No. No. 2579 of 20th Feby 1878).

The plan and estimate of Rs. 127 for certain additions to the Moonsiffs Court at Parvatipore in the Vizagapatam District are sanctioned.

The work will be carried out from the source indicated in para 3 of the foregoing letter. W 27-2-78

Cir 27/2

This sanction has been registered as Proc. No 293 dt 27 of 1877/78

District Engineer Viragapatam.
Examiner P. W. Accounts.
Judicial Department.

with Estimate

W R. Dft 9-3-78

Received before Meeting 2nd Sept

4-28-2-02

No 2353

Accdt. of (1878) Madras.

PUBLIC WORKS.

To

The V. B. Vizagapatam

Dated

Issued

Read. Encl.

G. O. 2 Mar 1878. No. 1034

Nos. 27-28

Monsiff's Court at
Parvatipoor, Vizagapatam

Dr. — Sanctions filed
& Estimate for certain
additions to Pro —

Audited 20 Dec