

(1) Number of pages 12 Pages -
 (2) Date of repair 18.7.86
 (3) Initials of the Referencer cmg

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P.W.D.

DEPARTMENT

G.O. No.	1504(w)	Press.
B.P. No.		Mis.
Dated	25.3.1878	197-

1181

Not to be folded or roughly handled

1504
1

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

25th March 1878, No. 1,504 W.

Buildings and Roads.

Military Works.

Read the following paper :—

No. 344. From J. W. RUNDALL, Esq., District Engineer, Bellary, to the Chief Engineer for Buildings and Roads, dated Bellary, 11th March 1878, No. 5,492.

I HAVE the honor to forward, for the sanction of Government, an estimate of Rupees 136, accompanied by a plan and report, for improving and extending the latrine attached to the hospital at Ramandroog to adapt it for storing dry earth.

1. One Estimate.
" Report.
" Plan.

2. The estimate has been prepared on the requisition of the military authorities, and it has been approved by His Excellency the Commander-in-Chief.

3. Funds will be provided from the provision for "Minor New Works, Military," in the budget for next official year.

No. 345. ORDER THEREON, 25th March 1878, No. 1,504 W.

THE plan and estimate of Rupees 136 for improving and extending the latrine attached to the hospital at Ramandroog to adapt it for storing dry earth are sanctioned.

2. Funds will be provided from the source indicated in paragraph 3 of the foregoing letter.

3. This sanction has been registered as Imperial No. 119 B of 1877-78.

(True Extract.)

Colonel, R.E.,
Secretary to Government, P.W.D.

To the District Engineer, Bellary.
" Examiner of Public Works Accounts, with estimate.
" Military Department.

Ed. A. F. Goodall.
Spare Copies

ENGINEERING
MILITARY WORKS.
No. 1 of (1873) SERIES.
PUBLIC WORKS.

To

TO DISTRICT ENGINEER
BELLARY.

By Mr. J. J. J.

By Mr. J. J. J.

By Mr. J. J. J.

By Mr. J. J. J.

By Mr. J. J. J.

No. 341-345.

For the use of the Hospital at Bellary
and for the use of the Hospital at Bellary

Report and Specification.

Agreeable to District Engineer
No. 2410 that accompanied Dimensional order
No. 1031 dated 25th October 1877 regarding a list
of works (Military) sanctioned by the District
Engineer for Estimates. I have inspected
the Hospital latrine for preparing the
improvements &c. The latrine as can be
observed from the accompanied Plan
as an enclosure for to store dry earth
having no roof does not answer the
purpose it is intended for and moreover
it has been reported too small.

I have proposed to have the width
6 feet broad, instead of 3 feet as it is at
present, with its present length. See
Plan, the yellow to indicate new work
proposed.

proposed. This dimension will be
ample from information &c. I have
collected, that is interior dimension 6
feet by 11 feet. And to preserve the earth
dry, to carry out the dry earth system I
propose a tiled roof to cover this en-
closure. Please see plan.

The Stone to be used must be
at least 3 inches thick and of the
description procurable at Ramandooz
and that are capable to be detached
in layers.

Before the plastering be laid
on the joints must be picked out
at least half an inch deep, the joints
and surface well wetted before the
Plastering comes on. The Plastering
will

1504
will consist of the following proportion
one of lime to two of river sand thoroughly
mixed and well beaten up to the
required consistancy. And after being
allowed to set for a few days it then
should be laid on with a trowel to half
an inch thick with the surface kept rough
and before drying the second coat must
be applied consisting of three parts of lime
to one part of river sand mixed and ground
up till reduced to a fine paste and applied
in the usual way and afterwards brought
to the required finish.

The wood work to consist of
sound and seasoned teak wood
procured at Bellary.

After the work has been
Completed

Completed if the best materials all rubbish
must be shot over the brow of the hill
and in the usual way handed over to the
Military Authorities

(Signed) Leo Pereira Pereira
Forsett & Co.

Forsett & Co. Office
28th January 1878
in temporary charge of Forsett & Co.

D. P. W.

No. 5492.

1504
BELLARY,
Dist. Engineer's Office,
11th March 1878.

FROM

The District Engineer
Bellary

TO

The Chief Engineer
for Buildings and Road.

SIR,

Enclosures.

I have the honour to forward for
the sanction of Government an Estimate of
Rs 136 accompanied by a plan and report
for improving and extending the Latrine attached
to the Hospital at Ramandurg to adapt it
for stormy dry earth.

2. The Estimate has been prepared on
the requisition of the Military Authorities and
it has been approved by His Excellency the
Commander in Chief.

3. Funds will be provided from the
provision for Minor New Works Military
in the Budget for next financial year.

I have the honour to be

Yours most obedt servant
J. D. Randall
District Engineer Bellary

N. 1504 of Public Works Department

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 25th March/78

Read the following:—

From

The District Engineer
Bellary

To
The Chief Engineer
Fort St. George
Madras

Dated 11th March 1878.

No. 5492.

Hospital Latrine at
Ramanadrog. — For-
warding an Estimate
for the sanction of Govt.
for improving the & ex-
tending the —

From the District Engineer Bellary No. 5492 dated 11th March/78

The plan and estimate
of Rs. 136 for improving
and extending the latrine
attached to the Hospital
at Ramanadrog to adapt
it for storing dry earth
are sanctioned

Funds will be pro-
vided from the source
indicated in para. 3 of
the foregoing letter. Wk
18.3.78

ELT

This sanction has been
registered as Imperial No. 119 B
of 1877-78.

To
The Dist. Engr. Bellary
Examiner P. W. Accounts
Military Department
With Estimate
15/17/78

4/5/81

Dept. of (1878) 210000

PUBLIC WORKS

D. L. Bellamy

1000

1000

1000

25 Mar 1881

Nos.

*Saline attached to the
hospital at Camanche
Illinois Dist*

*Balance of \$136 for
ink & soap and expended
for — purchased*

Subd. 1000