

(1) Number of pages 30.
 (2) Date of repair _____
 (3) Initials of the Referencer 30. 9. 86.

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P.W.D. DEPARTMENT

G.O. No.	2227 w	Press.
B.P. No.		Mis.
Dated	21. 5. 1878	197 .

Not to be folded or roughly handled

B.S.Y.

2229
1

GOVERNMENT OF MADRAS
PUBLIC WORKS DEPARTMENT.

21st May 1878, No 2,229 W.

Buildings and Roads
Civil Works

Read the following paper —

No 230 From Major ROSS THOMPSON, R E, District Engineer, Presidency, to the Chief Engineer, Buildings and Roads, dated Fort St George, 18th April 1878, No 356

With reference to G O, No 879, dated 15th March 1877, I have the honor to submit, for sanction and allotment of funds, plans, specification report and estimates, amounting in all to Rupees 8,310, for the following works and to state that they have been approved of by the Inspector-General of Jails —

Two plans.
One site plan
Three abstract estimates with details
One specification report

Constructing quarters for a Jailor of Her Majesty's Penitentiary	RS 4,408
Constructing quarters for a Deputy Jailor of Her Majesty's Penitentiary	3,182
Fencing and supplying water to Her Majesty's Penitentiary	720
Total	8 310

2 A site plan is also herewith submitted

No 231 ORDER THEREON, 21st May 1878, No 2,229 W

The plans and estimates aggregating Rupees 8,310 for the following works are sanctioned —

	RS	NO
1 Constructing quarters for a Jailor of Her Majesty's Penitentiary	4,408	37
2 Constructing quarters for a Deputy Jailor	3,182	37
3 Fencing and supplying water to the above buildings	720	37

2 The Railway Department will provide the necessary funds with reference to the orders noted in the margin

G O No 72 of 12th Nov 1873 3 This sanction has been registered
" " 1,173 of 14th May 1874 as Provincial and numbered as shown
" " 879 of 15th Mar. 1877 above.

(True Extract)

(Signed) E A. FOORD, Colonel, R E,
Secretary to Govt, P.W.D.

(True Copy.)

Major. R E,
Under Secy. to Govt, P.W.D.

To the District Engineer, Presidency
" Examiner of Public Works Accounts
" Consulting Engineer for Railways
" Judicial Department
" Examiner of Railway Accounts
" Accountant-General
Ed R O Sankar
Spare Copies

PUBLIC WORKS.
 C. L. of (1878) Madras.
 PUBLIC WORKS.
 MAY.
 Nos 250-251.

F.S.

No 400 of 1877-78. 19th November 1877.

Detail Estimate for Constructing Quarters for a
 Deputy Jailor on the East side of the Madras Penitentiary Madras.
 Vide G.O. No 879 of 15 March 1877.

2227
2

tail of work

Measurements & No. of each description
 L B & Co. Contnls of work

Main Building	
Externaling	
Front, Centre & Rear walls	1 10. 4. 4. 1 2880
End, and Cross walls	1 12. 4. 1. 1 854
Do	6 8. 4. 1. 1 864
Front Steps	1 10. 3. 2. 1 41
Rear do	1 7. 3. 1. 1 10 1/2
Do	2 3. 2. 1. 1 10 1/2
Total	1678 1/2 or 1706 1/2

Concrete	
Front, Centre & Rear walls	1 10. 3. 6. 1 280
End & Cross walls	1 12. 3. 6. 1 84
Do	6 8. 3. 6. 1 84
	448 1/2

Foundation	
Front, Centre & Rear walls	1 10. 2. 9. 1 1750
End & Cross walls	1 12. 2. 9. 1 528
Do	6 8. 2. 9. 1 528
Front Steps	1 17. 9. 3. 1 40
Rear do	1 7. 3. 1. 1 15 1/2
Do	2 3. 3. 1. 1 10 1/2

Plaster	
Front Centre & Rear walls	1 10. 2. 2. 1 640
End Centre & Rear do	1 12. 2. 2. 1 192
Do	6 8. 2. 2. 1 192
	3904 1/2

Detail of work

Measurements Area of each
L B & Contents of work

Paint

Carsons green paint to doors	7	4	22 1/2	820	x
Do	2	3	18	108	x
Do Windows	6	3	18	315	x
Total				1063	or 11 1/2

Good Oil

Preserver	1	10	2	80	x
Do	2	10	2	40	x
Do	1	10	2	22 1/2	x
Total				142 1/2	or 1 1/2

For 2 Carts to Pulmagran registers 2 1/2

Cook Room and Godcurs

Excavating

Centre wall	1	14	6	4	8	195 3/4	x
End walls	2	14	6	4	8	32 1/2	x
Side walls	4	10	4	2	6	400	x
Total						972	or 36 1/2

Concrete

Centre wall	1	14	6	3	6	26 3/4	x
End walls	2	14	6	3	6	50 3/4	x
Side walls	4	10	4	3	6	70	x
Total						147 1/4	or 14 1/2

Foundation

Centre wall	1	14	6	2	6	90 3/4	x
End and Side walls		14	6	2	6	31 1/2	x
Basement to	1	83	6	1	9	14 1/2	x

Superstructure

Centre wall	1	14	6	1	3	16	290	x
End walls	2	14	6	1	3	16	562 $\frac{1}{2}$	x
Side walls	4	10	4	1	3	16	600	x
Bed for fire place	1	12	3	2	6	90	x	
							<u>1974 $\frac{1}{2}$</u>	

Detail of work

Measurements Area of each
L B & Contents of work

2229
4

Deductions

Doors	2	3	1	3	1	45	x
Windows	3	3	1	3	1	45	x
Flat Arch	5	5	1	3	1	39 1/2	x

Total Deductions 129 1/2 x

Total Brick work 1825 or 1845 Cft

Flat arch work in Chumam 40

Cornice work 1 30 9 9 50 50

Roofing 1 16 6 30 495 or 500

Plastering

Basement	1	78	6	1	3	1	98 1/2	x
End walls out side	2	14	6	1	1	1	31 1/2	x
Side walls	2	23	9	13	1	1	61 1/2	x
End walls inside	2	12	10	5			240	x
Side walls	4	10	12	5			522	x
Centre wall	2	12	16	5			384	x
Side of Steps	4	1	1	2			2	x
Total							2180 1/2	x

Deductions

Doors	2	3	1	3	1	36	x
Windows	3	3	1	3	1	36	x
Total Deductions						72	x

Total Plastering 2108 1/2 or 21 1/2 Agn

Shocking Cook Room and Godcurs 2 12 10 1 210 1 or 2 1/2 Agn

Plaster

Wall plates 3 12 6 2 3 3 3

Batten Doors Complete 2 3 1 3 3 3 3 3

Batten Windows Complete 3 3 4 3 3 3 3 3

Paint

Carsons Red Ox for Doors 2 3 12 72

Do for Windows 3 3 8 72

Total 144 or 1 1/2 Agn

For 2 Carts to Pulmagran registers 2 1/2

Detail of work

Measurements Area of each
L B D or Description
Contents of work

Latrines

Excavation

Side & Cross wall	1	11.2	2.6	11.0	
Screen wall	1	10.6	2.2	11.2	
Total		11.8	4.8	22.2	1/2 cys

Foundation

Side and Cross walls	1	11.2	2.6	11.0	
Screen wall	1	10.6	2.2	11.2	
Basement for Side and Cross	1	11.2	1.6	11.0	

Superstructure

Side & Cross walls	1	11.2	1.6	11.0	
Gable Ends	2	12.6	1.6	11.2	
Screen wall	1	10.6	1.6	11.0	
Total		11.8	4.8	22.2	

Deduction

Door	1	3.0	1.6	11.2	
Bull eyes	3	2.0	1.6	11.0	
Flat arch	1	5.0	1.6	11.0	
Door	1	5.0	1.6	11.0	

Circular Arch

Bull eyes	3	4.0	1.6	11.0	
Total		11.8	4.8	22.2	

Total Remaining Brick work

Flat Arch work					470 cfs
Circular Arch work					11

Roofs

Roofing with Palmirah Coupler					
Roof keels	12	16.0			192 or 2 cys

Plastering

Inside wall	1	36.0			81 280.8
Gables do	2	12.0			25 110.0
Out side do	1	24.0			54 102.6
Gable do	2	12.0			27 108.0
Screen wall	1	23.0			52 117.6
Total					248.9

Detail of work

Measurements Area of each
L B D or Description
Contents of work

Deduction

Door	1	3.0			6 110.0
Bull eyes	3	2.0			15 9.0
Total					27.0

Total Plaster

Flooring Asphalt

Room	1	10.8			80
------	---	------	--	--	----

Work

Bull eyes frame	2	3.0			1 11.2
do	2	2.0			1 11.2
Wall plates	2	8.0			1 11.2
Total					1 11.2

Door

Batten door	1	3.0			6 110.0
-------------	---	-----	--	--	---------

Various lead paint

Door	1	3.0			12 110.0
------	---	-----	--	--	----------

Var 2 Coats for painting rail rollers

W. C. Baddley
Lieut. R. E.
Assistant Engineer
Southern Range.

Fort St. George
30 September 1877

P.S.
15 APR 78

Major R. E.
District Engineer
Presidency

5-4-78

From

The Assistant Engineer
Bentley Range.

400 of 1877-78

Dated 22nd November 1877.

Quarters for a Deputy Jailor on
the East side of A.M. Penitentiary
submits a Detailed Estimate
for Constructing

P.S.

7 NOV 77

No 399 of 1877-78 19 November 1877.

Head of Service Provincial

Fund Preliminary

Class Original Works

Main Head Prisons Department

Sub-head Central Jail

Name of Work

Constructing Quarters for a Jailor
on the East side of A.M. Penitentiary, Madras State G.O.
No. 879 D/15th March 1877.

Amounting to Rupees 4408

To be carried out by P.W. Department

Detail of Work	Number	MEASUREMENTS IN FEET			Area or Contents.	Total quantity of each description of Work
		L	B	D		
<u>Main Building</u>						
Excavating						
Front Centre and Rear walls	4	45	1	4 1/2	245 1/2	
End and Cross walls	4	18	1	4 1/2	129 1/2	
D: D:	6	12	1	4 1/2	129 1/2	
Front Steps	1	22	3	9	19 1/2	
Rear steps in Centre	1	8	3	9	18	
Rear steps	2	8	3	9	15 3/4	
Total					610 3/4	on 22 nd 1877
<u>Concrete</u>						
Front Centre and Rear walls	4	45	3	6	810	
End and Cross walls	4	18	3	6	126	
D: D:	6	12	3	6	126	
					588	588 1/2
<u>Foundation</u>						
Front Centre and Rear walls	4	18	2	9 1/2	271 1/2	
End and Cross walls	4	18	2	9 1/2	792	
D: D:	6	12	2	9 1/2	792	
Bed for steps	1	21	3	9	17 1/4	
D: rear steps	1	7	3	9	15 3/4	
D: D:	2	8	3	9	15 3/4	
					377 1/4	

Detail of Work	Number	MEASUREMENTS IN FEET			Area or Contents	Total quantity of each description of Work
		L	B	D		
Basement..					3774 3/4	
Front Gate and rear walls	4	48	2	2	768	
End and Cross walls	4	18	2	2	288	
D: D:	6	12	2	2	288	
Steps	1	21	3	1	63	
Rear Steps	1	5	3	1	15	
D: D:	2	3	3	1	21	
Superstructure						
Main walls front and rear	2	48	16	7	2448	
End and Cross walls	4	18	16	7	1536	
Gables for Cross walls	2	18	16	2	162	
Front D:	2	17	14	9	259	
Rear Cross walls	4	12	16	2	960	
	3	1	16	2	96	
Pillars	2	3	16	2	84	
	2	1	16	2	24	
Wall over hyssumer in front						
Grasshopper	2	12	9	6	90	
					1161 3/4	
Deduction						
Doors	8	4	16	7	560	
D:	2	3	16	7	70 3/2	
Windows	6	2	16	5	157 1/2	
Flat Arches						
Front Doors	8	6	16	10	90	
D: Windows and Doors	8	6	16	9	45	
Total Deduction					720	
Total remains Brickwork					1089 3/4	
Roofing for main building	1	47	26		1274	112 3/4
D: for Grandah	2	49	18		1764	117 3/4

Detail of Work	Number	MEASUREMENTS IN FEET			Area or Contents	Total quantity of each description of Work
		L	B	D		
Plastering					105	
Main room inside around	1	72		7 1/2	1224	
D: end rooms D:	2	60		7 1/2	2250	
Gable walls for both sides	4	18		2	216	
Grandah Room inside	2	48		10 1/2	1248	
D: D:	1	49		10 1/2	807	
Main room outside	1	45		7 1/2	765	
D: Ends D:	2	21		7 1/2	714	
Grandah out side	2	10 1/2		10 1/2	351	
Rear walls out side	2	17		9	306	
	3	8		8	144	
Pillars	2	3 1/2		8	56	
	2	10		8	160	
Wall over hyssumer	2	12		5	240	
Decorative	4	48 1/2		2	388	
Side of Steps	8	3		1	24	
Total					8510	
Deductions to D:						
Doors	8	4		7 1/2	240	
D:	2	3 1/2		7 1/2	52 1/2	
Windows	6	3 1/2		5	106	
Total					398 1/2	
Total Remaining Plaster					8111 1/2	112 3/4
Staircase						
Main Room	1	18		15	324	
End D:	2	18		12	432	
Rear Grandah	2	12		12	288	
D:	1	18		12	216	
Front Grandah	1	45		12	540	
Between Pillars	6	9		1 1/2	81	
					1886 1/2	

Detail of Work	Number	MEASUREMENTS IN FEET			Area or Contents	Total quantity of each description of Work
		L	B	D		
Spacia in rear Verandah Pillars	1	14	2		28	1882
Door ways	8	1	1		8	
D ^o	2	3	1		6	10 1/2
Total Flooring						1780 1/2 or 1785 sq ft
Paving Steps	35	6	2		120	10 1/2 sq ft
Wood work						
Beams	1	25	6		150	
D ^o	2	12	6		144	
D ^o	1	16	7 1/2		120	
Wall plate for main wall and Verandah	1	122	6		732	
Pillar plates	9	1	6		54	
Total Scaffolding						27 1/2 or 27 1/2 ft
Pairs Ornamental Junction Doors with frames & complete	8	2	7		112	
D ^o	2	3	7		42	
Pairs Junction Windows	6	3	5		90	
Paint						
Carsons green paint for Doors	8	2	7		112	
D ^o	2	3	7		42	
D ^o Windows	6	3	5		90	
Total						112 1/2 or 112 3/4
Wood Oil						
Beams	1	25	2		50	
D ^o	2	12	2		48	
D ^o	1	16	2		32	
Total						130 or 130 sq ft

Detail of Work	Number	MEASUREMENTS IN FEET			Area or Contents	Total quantity of each description of Work
		L	B	D		
See 2 Seats to the Palmyrah					222	8
Couples for main building					1800	
D ^o for Verandah rafters					17 1/2	
					3575	11 3/4 sq ft
Lock room and Godown						
Excavating						
Centre wall	1	11	6	1	66	
End walls	2	11	6	1	132	
Side walls	4	10	6	1	240	
Total					438	11 3/4 sq ft
Concrete						
Centre wall	1	11	6	1	66	
End walls	2	11	6	1	132	
Side walls	4	10	6	1	240	
					438	11 3/4 sq ft
Foundation						
Centre wall	1	11	6	1	66	
End and side walls	6	11	6	1	792	
Basement to D ^o	1	50	6	1	300	
Superstructure						
Centre wall	1	11	6	1	66	
End walls	2	11	6	1	132	
Side walls	4	10	6	1	240	
Bed for fire place	1	12	3	2	72	
					197 1/2	
Deductions						
Doors	2	3	7		42	
Windows	6	3	5		90	
Plat Arch	6	5	10		300	
Total Deductions					432	

Detail of Work.	Number.	MEASUREMENTS IN FEET			Area or Contents	Total of each Description of Work
		L.	B.	D.		
Total Brick work					1825	1825 Cft
Cornice work	1	90	9	9	595	50
Keelings	1	16	30		495	115 1/2 Sq
Total Brick work in Charnam						1.0 Cft
Plastering						
Basement	1	75	10		904	
Side walls out side	2	14	11		319	
Side walls in	2	20	9		417 1/2	
Side walls inside	2	12	11		240	
Side walls outside	4	10	10		520	
Side walls	2	12	10		384	
Side of steps	1	1	1		2	
					2180 5/8	
Deduction	2	3	6		36	
Doors	3	3	4		36	
Windows					72	
					2108	1121 1/2 Sq
Total Plastering					240	112 1/2
Keelings, Keelings & Godown	2	12	11			
Roof	3	12	6		36	3 1/2 ft
Wall plate	2	3	6		36	3 1/2 ft
Bottom Doors Complete	3	3	4		36	3 1/2 ft
Windows	3	3	4		36	3 1/2 ft
Bottom windows Complete	3	3	4		36	3 1/2 ft
Paint	12				72	
Household Color for Doors	2	3			72	
for Windows	3	3			72	11 1/2 Sq
Total					144	6 1/2 Sq
Net Cost for Colonial Roofers						

Detail of Work	Number.	MEASUREMENTS IN FEET			Area or Contents	Total quantity of each description of Work.
		L.	B.	D.		
Latrine						9
Excavation						
Side and Cross walls	1	41	2	2	410	
Screen wall	1	10	2	2	42	
Total					452	11 1/2 Cft
Foundation						
Side and Cross wall	1	41	2	2	205	
Screen wall	1	10	2	2	20	
Basement for Side & Cross	1	41	1	1	30	
Superstructure						
Side and Cross wall	1	41	1	1	410	
gable Ends	2	12	1	1	62	
Screen wall	1	10	1	1	40	
					823-1 1/2	
Deduction						
Door	1	2	1	1	22	
Bulls eye	3	2	1	1	11	
Flat arch						
Door	1	5	1	1	7	
Circular arch						
Bulls eye	3	4	1	1	11	
					52-9	
Total Remaining Brickwork						790 Cft
Flat arch work						5
Circular arch work						11
Cornice						
All Round	1	56	9	9	31	3 1/2
Roof						
Roofing with Palmistah Coupler teak rafters	12	15			192	112 Sq

No 399. 400 & 401 of 1877-78. 21/19 November 1877.

22 10

Specification to accompany the Plans and Estimates for constructing Jailor's & Deputy Jailor's Quarters on the ground between St. Mary's Bridge and the Penitentiary Madras.

P.S.
7 NOV 77

Amount of Estimates

Jailor's Quarters	4408
Deputy Jailor's Quarters	3182
Fencing and	
Supplying water &c.	4250
Total Rs	8500

Plan. A reference to the site plan will show that the Quarters are to be placed facing the East, fenced in from the Road & rear to prevent the ground being used as a thoroughfare & supplied with a stand pipe connected with the Red Hills water, and that the road leading to the Penitentiary from the Bridge will be altered so as to make a more convenient curve for vehicles entering the Compound from the Bridge

to be performed. The centre line having been laid out & the breadth of the foundations marked, excavate to the full depth shown on the drawings or to such other additional depth as the officer in Charge may consider necessary. The ground having been excavated to the full depth ram well and then lay 6" of Portland Concrete consisting

Detail of Work.	Number.	MEASUREMENTS IN FEET			Area or Contents.	Total quantity of each Description of Work
		L.	B.	D.		
Plastering						
Inside wall	1	36.	8		288.	
Gable D.	2	10.	2		20.	
Out side D.	1	16.	8.5		132.	
D. Gable D.	2	12.	2.5		60.	
Screen wall	1	23.	6.5		149.	
					948.	
Deduction						
Door	1	2.	6		12.	
Butt's eye	2	2.	1.5		3.	
					24.	
					924.	974 8/9
Plaster						
Decorating Asphalt	1	10.	8.		80	80 sq ft
Room						
Trunk	2	3.	2.5	1.5	10.5	
Butt's eye frame	2	2.	2.5	1.5	6.5	
Wall plates	2	8.	6.	2	100.	
Total Trunk					177.	177 1/2 ft
Door						
Butt's door	1	2.	6		12.	15 sq ft
Carroll's lead Paint						
Door	1	2.	12		24.	
For Palmetto and keepers	12.	16.			192	200 sq.

W. A. Baddley
Lieut. R. E.
Assistant Engineer
Southern Range.
Major R. E.
District Engineer Presidency

W. A. Baddley
5, Victoria 1877
Comptroller

consisting of 2 parts of shell lime 2 parts of sand
2 parts of finely powdered coarsh & 1 part of
bricks. The jelly water & ram water thoroughly
incorporated.

Construction. Brick in Chunan carried up
in a line as detailed in the drawings. The mortar
to consist of 1 part shell lime to 2 sand, the bricks
to be well burnt and of fair shape consistent
with the size, carefully loaded & laid with thin
mortar. Each side wall to be covered with
water in the corner & care to be taken that
no dry & hot bricks are used in any part of the
work.

Placement. Bricks in Chunan 2' high as above
superstructure. Bricks in Chunan as per
foundations.

Roofing. To consist of Palmyrah Couple of
collar pieces for the centre, and Palmyrah
balks for the Gendash. Teak trusses flat
iron tiles & Chunan borders.
The whole of the materials to be of the best
quality carefully fitted & laid.

Flooring. The flooring throughout will
consist of 8" square bricks laid in Chunan
with 2 bonding course of 3" port wall bricks
underneath except the latrine which in lieu of
brick will have 4" asphalt
floor of windows. Painted Christian doors
& windows of dark wood with frames
of iron. The whole of the work to be of
good

x Parton done
& windows for
the Cathouse

Paint Works.

good sound material carefully wrought & put up
The doors & windows of main building to have
3 coats of Carson's Green, doors & windows of out houses
3 coats of Carson's lead color, the brissumers
3 coats of Wood Oil, the palmash rafters 2 coats
of Oil.

Plastering

The whole of the Brick work outside & inside
to be plastered with 2 coats of Chunan.

Fencing

Will consist of Teak rails of triangular
section with posts top & bottom frames tarred
all over with 2 coats. Care being taken that
the bottom of the posts are tarred before fixing.

Water Supply

A 2" branch will be fixed in the Red
Will pipe leading to the Penitentiary and
carried to a stand pipe of Cast Iron with
masonry cistern around it.

Drainage

A masonry drain will be constructed as
shown in the plan to carry off the surplus
water to the Coom.

Laying Road

A new road will be opened as shown in
the plan & laid with 5" of Laterite Stone
Jelly & gravel.

15 APR 1878
H. C. Baddley Lieut. R.E.

Assistant Engineer
Southern Range.

Fort at George
31st October 1878.

M. Thompson Major R.E.
District Engineer Presidency

No 356

402

22²⁹/₁₉

From

The District Engineer
Presidency

Encl: 7

2 Plans

1 Estimate

3. Abstract of
Costs & Receipts

1. Specification

To
The Chief Engineer
Roads & Buildings

Sir With reference to
L.O. No 879 of 15th March/77 I have the honor
to submit for sanction
& allotment of funds
Plans, Specification
Report and Estimates
amounting in all to Rs.
1310-0-0 for the works
as per margin and to
state that they have
been approved of by
the Inspector General of
Rail

Copy 200 for a factor of the Government
Rs 4400/-
Copy 200 for a supply of Rs. 3100/-
Supplying Rs. 720/-
Rs 8310/-

Jails.

A. L. L. plan is
also herewith submitted.

I have the honor to be

Yours most respectfully

~~W. L. L.~~ ~~W. L. L.~~

W. L. L. ~~W. L. L.~~
President

For the People
18th April 1878

77

2229
12A

G.O. 72-12-11-73.
 -1179-2-8-74.
 -879-15-3-77..

From
 The District Engineer
 Presidency

Dated 18th April 78
 Received

No 356.

Enclosure 9

Quarters for Jailor
 & for the Trucking

Submits Plans &
 Estimates amounting
 to Rs. 8310 for sanction
 & allotment of
 funds.

to 204-15-5-78
 C.E. 7-5-78 R.R. 21-5-78

131 H
 at craks

No 2229 W

Public Works Department.

2229
 13

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 21 May 78
 Read the following -

From the District Presidency (H.B. No 356 of 18th April 1878)

The plans and
 estimates aggregating Rs.
 8310 for the following works
 are sanctioned.

1. Constructing Quarters for a jailor of Her Majesty's Penitentiary. Rs: 4,408
2. Do Do for a Deputy jailor Rs: 3,182.
3. Fencing and supplying water to the above buildings. Rs: 720.

Register No 27/2
 1878
 27/3

The Railway Department will provide the necessary funds with reference to the orders noted in the margin.

W.H.
 18.5.78

G.O. No 72 of 12th Nov 1873.
 G.O. No 1173 of 4th May 1874.
 G.O. No 879 of 15th March 1877.

District Presidency,
 Examiner P.W. Accts. & Estimates
 Cms of Engg. for Railways
 Judicial Department
 Examiner Ry. Accts.
 Accountant General
 P.W. H.L.

This sanction has been registered as Provincial & numbered as shown above

14

4716

GOVT. OF (1878) INDIA.
PUBLIC WORKS

D

J. L. Presidency

Date:

From:

To:

For:

G. O. 21 May 1878. No. 22291

Res.

Victor's & Dr. Taylor's Drawings
of the Penitentiary, Madras.

The Plans & Estimates
for —, sanctioned

Int. Secy. B. M.

Cir 17-5-78 P. L. 21-5-78
15-5-78