

(1) Number of pages 26
(2) Date of repair 28.7.86
(3) Initials of the Referencer bcw.

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

Public Works DEPARTMENT

G.O. No.	2284	Press.
B.P. No.		Mis.
Dated	27.5.1878	197.

[Signature]

Not to be folded or roughly handled

2294
1

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

27th May 1878, No. 2,294 W.

Buildings and Roads.
Civil Works.

Read the following paper:—


No. 313. From Major H. W. WOOD, R.E., District Engineer, Vizagapatam, to the Chief Engineer, Public Works Department, Buildings and Roads Branch, dated Waltair, 3rd May 1878, No. 243.

WITH reference to G.O., 17th October 1877, F.R. No. 2,377, I have the honor to submit a plan (sent by a separate packet) with sections of that portion of the Vizagapatam backwater which may be required to be excavated by famine labor.

2. An estimate for the work is also herewith forwarded. Assuming that the excavation is taken to a depth of one foot only below mean low water, or about four inches and a quarter below lowest low water, the cost will be Rupees 1,08,550. If, however, the excavation be made to a depth of one and a half feet below mean low water level, or about ten inches and a quarter below lowest low water level, the cost will be Rupees 31,503 in addition, or in all Rupees 1,40,053.

3. For the shallower excavation the rate is about $5\frac{1}{2}$ cubic yards for a Rupee, while in the deeper excavation it is about $4\frac{1}{2}$ cubic yards for a Rupee. These rates may seem excessively high, but if necessary they can be reduced. The reason of the rates being so high is that the excavated soil is supposed to be carried by women and children. If long wooden troughs or shoots into which the soil could be hoisted and swept inland by a continuous stream of water raised by means of picottahs from the backwater (*vide sketch*) were adopted, the cost of excavating the portion of the backwater in question would no doubt be very considerably reduced. In event,

PLAN OF DOUBLE CRIBBLE LIFT PICOTTANS FOR FEEDING SHOOT WITH WATER



however, of such labor saving appliances being used there would be no employment for the large mass of women and children requiring relief.

4. The outer portion of the backwater is proposed to be connected with the piece of ground in which the latrines stand by a channel (*vide* plan C.S.A.) curving round the north of the rocky hill on which the large powder magazine stands and cutting through the road running from thence northwards. The channel has been provided to have a breadth of 34 feet at bottom, and if the inner piece of ground immediately on the north-west of the town of Vizagapatam should be excavated and used as a scouring basin a special culvert will require to be designed for the channel where it crosses the road that has been mentioned, while the sides and bottom may require to be pitched with stone.

5. No connecting channel has been designed to run on the south side of the magazine hill, first, because the ground at this particular point is almost certainly the same rocky ridge as that of the hill, and, second, because I would suggest the desirability of the "fishery tank" being filled up, and some open ground being thus gained near the magazine, which is at present in a rather confined position.

6. A reference to the Sections B, C, D, E, F, across the ground north-west of the town, on which the latrines stand, shows that it will be necessary to fill in the edges of this piece of land up to at least the level of highest high water. At present there are a number of huts on this low land, which is also used as a timber store. It was in this quarter that almost all the loss of life took place in the flood caused by the cyclone of October 1876. I have not calculated the cost of this filling in, but I think it would be desirable that the earth used should be clean and brought from a distance. I would beg the favor of subsidiary orders being issued on this and other points when it has been decided whether the inner piece of ground immediately north-west of the town is to be excavated or not.

No. 314. ORDER THEREON, 27th May 1878, No. 2,294 W.

HIS GRACE the Governor in Council considers the results of the examination to be valuable. But the cost is large considering the amount of improvement which will be effected; and as the work is not now required for the employment of famine labor it cannot be taken up on behalf of Government. The plan will, however, be communicated to the President of the Vizagapatam Municipality for any remarks which he may wish to offer.

(True Extract.)

(Signed)

E. A. FOORD, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the District Engineer, Vizagapatam.
" President, Vizagapatam Municipality, with plan.
" Financial Department.
" Revenue (Famine) Department.

Edw. C. Howarth.
Scriba

2294
2

★
 CHIEF AND DEPUTY
 CIVIL WORKS
 GOVT. of (1878) [unclear]
 PUBLIC WORKS.

DISTRICT ENGINEER
 VIJAYANAGAR

No. 512-611

For any further information
 please apply to the
 District Engineer
 at Vijayanagar

Estimate for excavation of the Buck
 water Swamp at Viragapatam prepared in
 accordance with O.G. of 17th October 1877 F.R.
 at 2377.

224/182

1. The following formula, have been
 used in calculating the area of the cross
 sections:-

When the base has an odd number of
 equal parts,

$$\text{Area} = \left(\frac{a}{2} + b + c + \dots + k + \frac{l}{2} \right) \delta$$

When the base has an even number of
 equal parts,

$$\text{Area} = (a + \frac{1}{2}b + c + \dots + c + \frac{1}{2}k + l) \delta$$

where, $a, b, c, \dots, k, l$, are the breadths (or
 depths) of the several parts into which the section
 is divided and δ is the common distance between
 those breadths (or depths).

Area of Cross section at 1 - 1355 Sft.

at 2	105
at 3	1180
at 4	1285
at 5	1415
at 6	1730
at 7	930
at 8	1570

Area of cross section A 127-1650 sq ft

128-1650

129-1650

130-1650

131-1650

132-1650

133-1650

134-1650

135-1650

136-1650

137-1650

138-1650

Total area of 18 sections 29316 sq ft

Area of average section 1628.6 sq ft

The centre length of the portion to be excavated is 8240 ft

Therefore the content of the excavation will be 8240×1628.6

$= 13420864$ cu ft

$= 344432$ cu yds.

or say (a) 344430 cu yds.

2. The sum of the bottom lengths of 18 cross sections is 10180 ft i.e. the average section is about 566 feet long. Therefore, it should be determined to excavate six inches deeper than is shown on the plan, the further

amount of excavation to be done, will be $566 \times 8240 \times \frac{1}{2}$

$= 2351920$ cu ft

$= 56367$ cu yds.

or say (b) 56370 cu yds.

3. The mean breadth of the cutting to connect the backwater with the ground on which the latrines now stand is 50 feet.

The area of the section A taken along the centre length of the cutting is 1370 sq ft.

Hence the volume of the cutting, will be 50×1370

$= 68500$ cu ft

$= 2537$ cu yds.

or say (c) 2540 cu yds.

4. Should it be determined to excavate the cutting six inches deeper than is shown in the plan, the further excavation will amount to this extra depth multiplied by the bottom breadth of the cutting multiplied by the length of the cutting, i.e. to $\frac{1}{2} \times 34 \times 1040$

$= 17680$ cu ft

$= 655$ cu yds.

or say (d) 660 cu yds.

5. For the excavation of the piece of ground on which the latrines stand,

Area of cross section B. 2500 sq ft

" " " " 2360

Area

the price for the quantity (a) or 344430 yds³ will be 23 1/4 pies or say 2 Annas per cubic yard and the excavation will cost Rs. 43054 nearly.

8 For the quantity (c), the average lead will be 20 yds. while the lift will be as before viz. 2 yds, the rate (increased as before by 25 per cent) will be 11 1/4 pies per Cyb. The cost therefore of excavating (c) or 2540 Cyds. will be about Rs. 149.

9. For the quantity (e) the average lead will be 1500 feet or 500 yards while the lift will be 2 yds. and the price paid for excavation of soft silt in a channel, would be 40 pies or increasing this rate by 25 per cent for excavation in mud and water as before the price would be 50 pies or 4 1/6 Annas per cubic yard. The cost of excavating the quantity (e) or 231100 Cyds. will therefore be about Rs. 60180.

10. Summing the above results we have
Cost of excavating — a — Rs. 43054
— " — " — c — 149
— " — " — e — 60180
Total Rs. 103383

Area of cross section D — 3570 sq ft
Area — " — " — E — 3570 —
— " — " — F — 3810 —

Total area of these cross sections 15610 sq ft
Area of average section 3122 —

And the total length of excavation is 2000 feet.
Therefore, the volume of excavation will be, 2000 x 3122 = 6244000 sq ft
or say (c) — 231100 Cyds.

6. Should it be determined to excavate this portion six inches deeper than is shown on the plan, the further amount of excavation to be done will be 1/2 multiplied by 2000, multiplied by the average length of the sections which is 1/2 x 2000 x 1500 = 1500000 sq ft
or say (f) — 55555 Cyds.

For the quantity of excavation (a) the average lead will be 66 feet or 22 yds. For this lead and this lift, the rate that is paid for excavating silt in a dry channel of the Viragapatam District would be 17 pies or 1 Anna 7 pies per cubic yard. Adding 25 per cent to this for work in sticky mud and water

Brought forward Rs. 103,350
 Add 5 per cent for contingencies — 5,167
 Total cost of excavating to one
 foot below Mean Low Water Level } Rs. 108,517

11. Again, for the quantity of excavation
 (b) the lead will be 190 yds. as before, while
 the lift is but six inches more. The rate
 may therefore be taken as the same, though
 an addition in this case of 25 per cent may
 be made, in consequence of the greater depth
 of water in which the excavation must be
 made. The rate will therefore be about 2½
 annas per cubic yard, and the cost of excavating
 (b) or 86,370 Cys. will be Rs. 12,595.

12. For the quantity of excavation (d)
 the rate raised 25 per cent in the same
 manner, will be 13½ pice per cubic yard.
 Therefore the cost of excavating (d) or 66,916
 will be Rs. 46 about.

13. For the quantity of excavation (f)
 the rate raised 25 per cent in a similar
 manner, will be 5 annas per cubic yard.
 The cost of excavating (f) or 55,560 Cys. will
 be Rs. 17,362.

14. Summing these three last results
 we have,

2294/6

Cost of excavating (b) — Rs. 12,595
 " " " (d) — " 46
 " " " (f) — " 17,362
 30,003

Adding 5 per cent for Contingencies 1,500
 Total for additional excavation
 to depth of one foot and a half } Rs. 31,503
 below Mean Low Water Level

District Engineer's Office
 Waltair, 3rd May 1878

Approved
 District Engineer, Tiragapatam

Estimate for excavation
of the Backwater Swamp
at Viragapalam, pre-
pared in accordance
with O.G. 17th October
1877 F.R. No. 2377.

No. 242

District Engineer Office
Madras 3rd May 1878

From

The District Engineer 2294
Viragapalam

The Chief Engineer F.M.D.
Engineering and Roads Branch
Madras

With reference to O.G. 17th October
1877 F.R. No. 2377, I have the honor to submit
a plan with sections, of that portion of the
Viragapalam Backwater, which may be required
to be excavated by Famine labor.


The estimate for the work is also
herewith forwarded. Assuming that the
excavation is taken to a depth of one foot
only below Mean Low Water, or about four
inches and a quarter below Lowest Low Water,
the cost will be Rs. 10,855. If, however,
the excavation be made to a depth of one
and a half feet below Mean Low Water
level, or about ten inches and a quarter below
Lowest Low Water level, the cost will be
Rs. 31,503, in addition, or in all, Rs. 42,358.

3

For the shallower excavation, the
rate

rate is about $5\frac{1}{2}$ Cubic yards for a rope,
 while in the deeper excavation it is about
 $4\frac{1}{2}$ Cubic yards for a rope. These rates
 may seem excessively high, but if necessary,
 they can be reduced. The reason of the
 rates being so high, is that the excavated
 soil is supposed to be carried by women
 and children. If, long wooden
 troughs or shoots, into which the soil
 could be hoisted and swept inland
 by a continuous stream of water,
 raised by means of picottas from
 the backwater, (vide sketch) were adopted,
 the cost of excavating the portion of the
 backwater in question, would no doubt be

Lines of Double
 or Triple Lift
 picottas for
 feeding, shoot
 with water.



224/8
 very considerably reduced. In event however,
 of such labor saving appliances being
 used, there would be no employment
 for the large mass of women and
 children requiring relief.

4. The outer portion of the back-
 water, is proposed to be connected with
 the piece of ground in which the Larmer
 stand, by a channel (vide plan C.D.)
 curving round the north of the rocky
 hill on which the large Powder maga-
 zine stands, and cutting through the road
 running from thence Northwards. The
 channel has been provided to have a
 breadth of 34 feet at bottom and if
 the inner piece of ground immediately
 on the N.E. of the town of Tiragapatam
 should be excavated and used as a
 scouring basin, a special culvert will
 require to be designed for the channel where
 it crosses the road that has been mentioned,
 while the sides and bottom, may require
 to be piled with stone.

5. A connecting channel has been
 designed to run on the South side of the
 Magazine

A reference to the sections
B, C, D, E, F, across the ground N. W. of
the town, on which the latines stand,
shows that it will be necessary to fill
in the edges of this piece of land up to
at least the level of Highest High Water.
At present, there are a number of Luto in
this low land, which is also used as a timber
store. It was in this quarter that almost
all the loss of life took place in the flood
caused by the cyclone of October 1876.
I have not calculated the cost of this
filling in, but I think it would be
desirable that the earth used should
be clean and brought from a distance.

I have the honor to be
Sir

14/11/1906 Major G. B.
District Engineer
Nagapattinam

G.O. No. 1193 W - 23.10.77.

Buildings & Roads

From
The District Engineer
Vizagapatam

To
The Chief Engineer P.W.D.
Buildings & Roads Branch
Madras

No. 243
Dated 3rd May 1878

By Enclosures Two
Vizagapatam Back-
water.

Submits an Estimate for
Rs. 140,053, and a plan with
sections of that portion
of the — to be excavated
by Famine Labor.

Cir. 21.5.78 Dtd 27.5.78
G.O. No. 15.5.78 P.W.D. - 77

PUBLIC WORKS DEPARTMENT.

2294/10
Letter from the District Engineer
Vizagapatam No. 243 of 3rd May 1878.

FOR ORDERS.

The estimate has
been checked and found
correct.

The rates are high
viz $5\frac{1}{3}$ cubic yards for
a Rupee in the shallow
excavation, and $4\frac{1}{2}$ in the
deeper. The leads are
however long.

If the excavation
is taken to one foot below
Mean Low Water level the
cost amounts to 1,08,550. If
the depth is extended 6 inches

more the cost will be en-
hanced by Rs 3,503, making
the total Rs 14,053. No
doubt if the troughs and
Picutahs are used the cost
will be materially reduced.

E A Ford Col. R.E.
Chief Eng: & Surg. to Genl.
P. H. W.

21st May 1878.

2274
11

FOR ORDERS.

Public Works Department.

No 2294
PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the

Read the following:-

From the *Officer-in-Charge* (H.E. No 243 of 3 May 78)
Memo. by *Chief Engineer* W.D. (H.E. dated 21-1-78)

His Grace the Governor in Council considers the results of the examination *to be valuable*. But the cost is large considering the amount of improvement which will be effected; and as the work is not now required for the employment of *famine labor* it cannot be taken up on behalf of Government. The plan will, however, be communicated to the President of the *Vengaloor Municipality* for

Cir 21-5-78. Recd 27-5-78

any remarks which he
may wish to offer.

cut
24/5

2294
13

A. L. Vignapatham
President, Vignapatham
Municipality with plan
Fin. Dept.
Res. & Eng. Dept.

Dec 13-8-98

any
may

Govt. of (1878) 
PUBLIC WORKS.

Vizagapatam

G. O. 27 May 1878. No. 2294h.

Vizagapatam Back water

Intimating that Government
are not disposed to sanction
the estimate for excavating the
— as it cannot be undertaken
as a famine work, & commu-
nicating the Plan to the Vizagapatam
Municipality.

Chittur