

(1) Number of pages 16 pages.
(2) Date of repair 5-8-86
(3) Initials of the Referencer Carv

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P W D. DEPARTMENT

G.O. No.	2671(W)	Press.
B.P. No.		Mis.
Dated	28 6 1878	197.

V B.

Not to be folded or roughly handled

2671
①

GOVERNMENT OF MADRAS
PUBLIC WORKS DEPARTMENT.

28th June 1878, No. 2,671 W.

Buildings and Roads
Military Works

Read the following paper —

No 341 From Colonel F. J. MOBERLY, R.E., District Engineer, Bangalore, to the Chief Engineer, Public Works Department, dated Bangalore, 18th June 1878, No 62

I HAVE the honor to forward herewith, for the sanction of Government, the undermentioned estimates, which have been approved of both by the Lieutenant-General Commanding the Division and His Excellency the Commander-in-Chief —

1. Providing fixed wooden cots and improving ventilation of prison room, European Infantry	Rs. 110
2. Providing the prison rooms of Native Infantry with fixed wooden cots	126
3. Providing windows, &c, to Serjeant-Major's quarters, 14th Hussars	106

No 342. ORDER THEREON, 28th June 1878, No 2,671 W.

THE estimates submitted with the foregoing letter and aggregating Rupees 352 are sanctioned

- 2 The District Engineer will provide the necessary funds from the allotment at his disposal for Minor New Works under Military
3. This sanction has been registered as Imperial and numbered as shown below —

Register No 41 B of 1878-79.

" " 42 B of "
" " 43 B of "

(True Extract.)

(Signed) E A. FOORD, Colonel, R.E.,
Secretary to Govt, P.W.D.

(True Copy)

Major, R.E.,
Under Secy to Govt, P.W.D.

To the District Engineer, Bangalore
" Examiner of Public Works Accounts.
" Military Department

Exd T D Ryan
Spare Copies

Head of Service.

Imperial.

Fund.

Ordinary.

Colo.

Original. Work.

Main Head.

Military.

Sub Head.

Military Buildings.

Section.

Native Infantry.

To be carried out by the D. P. W.

Detail Estimate No. 5 - of 1878/79.

East and West Flanking Lines.

Name of work. — Providing fixed wooden
cots to each N. I. Regiment.

A. O. M. G. No. 205 dated 11th May 1878.

Description of work.	Measure- ment			Contents Total.
	No.	L	B	D

Barrack Guard.

Removing stone floor.

Front wall 1 13 1/2 19 1/2

End walls 2 6 1/2 19 1/2

Cross wall 1 5 1/2 7 1/2

Total Sq. of removing stone flooring. 46

Excavation.

Front wall 1 13 1/2 1/4 24

End walls 2 7 1/2 1/4 26

Cross wall 1 5 1/2 1/4 10

Total bft. of excavation. 60

D. foundation stone & clay 60

Brick in chunam.

Front wall 1 13 13 1/2 18

End walls 2 7 13 1/2 19

Cross wall 1 5 1/2 1/4 10

Total bft. of brick in chunam. 47

Plastering

Front & end walls 1 29 1/4 36

Total Sq. of plastering. 36

Description of work.	No.	Measure- ment.			Contents	Total
		L	B	D		
Woodwork.						
Jaists.		5	6 1/2	4 2	1-8-10	
Total lft of Janglwood wrought					1-8-10	
Planking.					2 feet up	
Total lft of Janglwood planking		1	6 1/2	16	104	
3 Screws					2	2 1/2
Removing stone flooring.						
Excavation.						
Foundation.						
Stone in clay.						
Brick in chunam.						
Plastering.						
Woodwork.						
Jaists.						
Planking.						
3 Screws						

Head of Service
Fund
Relief
Main Head.
Sub Head.
Section

Imperial.
Ordinary.
Original Work.
Military
Military Buildings.
European Cavalry.

2671/3

To be carried out by the D. P. W.
Detail Estimate No 57 of 1878/79.
Agam Barracks.

Name of Work. Providing windows and sun shades to
Regimental Sergeant Major's Quarters.
A. P. M. J. No 210 dated 14 May 1878

Description of Work	No.	Measure- ment.			Contents	Total
		L	B	D		
Dismantling stone in chunam.	2	5	1/2	6	90	X
Total lft of dismantling.					90	
Glazed and Venetian teakwood windows						
with fettings V: complete	2	5	4	.	2	2
Sintel stones over windows	2	5	1/2	6	2	2
Stone in chunam						
Sides of frames	4	5 1/2	3/4	1/2	24 3/4	
Total lft of stone in chunam					24 3/4	
Painting with chocolate color	4	5	4	.	80	
Total lft of painting.					80	
Wood work.						
Sunshades						
Battans	2	5	2 1/2	1 1/2	3 1/2	
Triangular ports at sides	4	2	2	2	2-8	
Total lft of teakwood wrought & put up					1-0-5 1/2	

Description of Work.	Measure- ment			Contents	Total
	No.	L	B		
Zinc Shuttering					
Top					
Sides	2	6	2 1/2		25
	2	2	2		8
Total Top & Sides of zinc shuttering					33
Do 1/2 Screws					4
Nails	4			1	200
	200			300	

Head of Service _____ Imperial
 Fund. _____ 25 _____ Ordinary
 Class _____ 74 _____ Original Works.
 Main Head _____ Military.
 Sub Head _____ Military Buildings.
 Section _____ European Infantry
 To be carried out by the D. P. W.
 District Bangalore.

Detail Estimate No 15 of 1878/79.

Name of Work. — Providing wooden cots & ventilators for
 Guardroom of European Infantry Regiments.

Description of Work.	Measure- ment			Contents	Total
	No.	L	B		
Removing stone flooring.					
Front wall.	1	13	1 1/2		19 1/2
End walls	2	6 1/2	1 1/2		19 1/2
Cross wall	1	5	1 1/2		7 1/2
Total of removing stone flooring.					46 1/2

Excavation.

Front wall	1	13	1 1/2	1/4	24
End walls	2	7	1 1/2	1/4	26
Cross wall	1	5 1/2	1 1/2	1/4	10
Total of excavation					60

Foundation.

Front wall	1	13	1 1/2	1/4	24
End walls	2	7	1 1/2	1/4	26
Cross wall	1	5 1/2	1 1/2	1/4	10
Total of foundation stone in clay					60

Description of Work

Measure-
ment
L B D Contents Total.

Superstructure.

Front wall

1 13 13 1/2 1 1/2 18

End walls

2 7 13 1/2 1 1/2 19

Cross wall

1 5 1/2 1 1/2 1 1/2 10

Total lft of superstructure broad in Chennam 47

Plastering

Front & end walls

1 29 1/4 36

Total lft of plastering 36

Woodwork.

Joists

5 6 1/2 4 2 1-8-10

Planking

Total lft of Jungluwood wrought & put up 1-8-10

1 6 1/2 16 1/2 104

Total lft of Jungluwood planking 104

Screws

2 2 2

Ventilators.

Top & bottom pieces.

2 5 3/4 4 3 1-11-4

Side pieces

2 3 3/4 4 3 1-6-8

Total lft of Jungluwood wrought & put up 1-6-11

Lintel stones over ventilators

1 8 1/2 5 1

Iron bars for ventilators

12 3 3/4 4 40

Total lft of iron bars 40

Roads and Buildings.

No. 62.

DISTRICT ENGINEERS OFFICE

Bangalore 18 June 1878.

From

The District Engineer 2671

Bangalore.

To

The Chief Engineer
Public Works Dept
Madras.

SIR,

I have the honor to forward herewith, for the sanction of Government, the undermentioned estimates, which have been approved of both by the Lieutenant General Commanding the Division and His Excellency the Commander-in-Chief:-

1. Providing fixed wooden cots & improving ventilation of Prison Room, European Infantry - Rs 110. Regular No. 41 B of 1878-79.
2. Providing the Prison Rooms of Native Infantry with fixed wooden cots.
3. Providing windows for the same.

Major's Quarters, 14th Regt. Inf. R. 106/-
Register No 43 Nov 1878

I have the honor to be

Sir,

Your most Obedt Servt

A. H. B. 14th Regt. Inf. R. 106/-

District Engineer

W. H. B.
1878

Coast & Buildings.

From

The District Engineer
Bangalore.

To The Chief Engineer
Public Works Dept.
Madras.

At: B.L.

Dated 6/8/78
Recd June 1878.

Encls: 3. Estimates

Estimates — for Sanctions
of Govt — for the work
mentioned works, amounting
in aggregate Rs. 352/4/-

To acty 21-6-78

Cd 25/5/78 Rtd 25.6.78

B. R.
Chief works

Public Works Department

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 28 June 78

Read the following

21.7/

From the Dist Eng. Bangalore / H. E. No 62 d/18 June 1878.

The Estimates

submitted with the
foregoing letter and
aggregating Rs. 352/-
are sanctioned.

2. The Dist Engineer
will provide the
necessary funds from
the allotment at his
disposal for Minor
New Works under

Military.

Dist. E. Bangalore
Ex. P. W. Accts & Estimates

Mily. Dept.

27/6
11/7
20/7-78
E. D. C.

This sanction has been
registered as Imperial & numbered
as shown in the letter above
recorded

To advy 21-6-78

- Cir 25.6.78. Uda 28.6.78

1887

GOVERNMENT OF INDIA

PUBLIC WORKS

D. L. Bangalore

100

100

28 June 1887 25714

100

Minor New Works Military

Estimates aggregating
Rs. 352 per annum — at
Bangalore Sanatorium.

Submitted by