Archives I 10,006—16-8 77

(1) Number of pages 10

(2) Date of repair 2-5-89. 86

(3) Initials of the Reference Cor

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P.W.D. DEPARTMENT

G.O. No. / B.P. No.	3525-10.	Press. / Mis.
Dated	5.9.1878	197 .

257

Not to be folded or roughly handled

3526/1

Specification to accompany the Plan and Estimate for improving the Vaildan and old Deputy Collectors Cutcherries at Valladam

Amount of Estimate Rs 310

A door in the Tahsildars room at A in the plan to be removed and placed at B and the space at A to be blocked up with burnt bricks in mud and the sidewalls of the door frames at B. to be built of the same material

Both sides of the walls to be plastered with chunam plaster, composed of two parts of clean white grained sand.

A covered passage 16 ft. long and 6 ft broad to be constructed between B and C, between the Tahsildars and the old Deputy Collectors cutcherry.

The foundation of the sidewalls of the passage to be of hard stone in mud mortar 2½ ft deep and 1½ ft thick. The passage to be plastered with chunam mortar and whitewashed. The roof to consist of jungle wood rafters covered with grummums, reposing both sides on chunam arches, supported by 2 jungle wood strong posts 6 inches square and 9 ft high

Two battens of 4 inch jungle wood 4 inch

No. 171 CI

District Engrs 35 V/3 Office
Camp Erode, 19th Augt 78

From

The Aq District Engineer
Coimbatore

To

The Chief Engineer
P. W Department
Madras

Sir,

I have the honor to forward a plan and Estimate amounting to Rs 310 for improvements to the Salvg and old Deputy Collectrs Cutcherry at Palladum for sanction, which have been prepared at the request of the Collector, who has duly countersigned them.

I have the honor to be
Sir
Your most obedt Servt
A. Awdry, Captain RE
Aq Dist Engineer

Enclosures
Plan
Estimate.
Specification

No 3528 dy 5 Sch Dpt. P.W.D

Proceedings of the Madras Government

Under date the 25/26/14

Read the following.

From

The District Engineer,
Coimbatore } (D.E. No 171 Cl dy 19th August 1878)

The plan and estimate of Rs 310 for improvements to the Taluq and old Deputy Collector's Cutcherry at Pallapatti, are sanctioned for execution from funds at the disposal of the District Engineer, under Minor Head Works.

GOJ 31.10.878

This sanction has been registered in Provincial No 973 of 1878-79

To
The Distt. Engr Coimbatore
The Examiner P.W. Accts Hdqrs Estimates
Mercantile Department

Dated 16-9-78

JLC 29/8

[illegible]

[illegible]

[illegible]