

(1) Number of pages 14
 (2) Date of repair 31.10.86
 (3) Initials of the Referencer lowa

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P. M. D. DEPARTMENT

G.O. No.	<i>H279. m.</i>	Press.
B.P. No.		Mis.
Dated	<i>7.11.1878</i>	<i>197</i>

Not to be folded or roughly handled

B.S.H.

6285
1

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

7th November 1878, No. 4,279 W.

Buildings and Roads.

Civil Works.

Read the following paper :—

No. 90. From J. D. GRANT, Esq., Officiating District Engineer, Tinnevely, to the Chief Engineer, Public Works Department, dated Palamcottah, 13th September 1878, No. 95.

REFERRING to G.O., No. 2,138 W, of 13th May 1878, I have the honor to request that a sum of Rupees 300 may be allotted towards the erection of a wire fence round the Sub-Collector's bungalow at Tuticorin instead of Rupees 225 allotted for this work.

2. An estimate of Rupees 300 for this work, which is approved by the Collector, is herewith forwarded for sanction.

No. 91. ORDER THEREON, 7th November 1878, No. 4,279 W.

THE estimate of Rupees 300 for providing a wire fence to the Sub-Collector's bungalow at Tuticorin is sanctioned.

2. Rupees 225 were provided for the work in G.O., No. 2,138 W, of 13th May 1878; the difference, Rupees 75, is now appropriated from the Provincial Reserve.

3. This sanction has been registered as Provincial No. 126 B of 1878-79.

(True Extract.)

Colonel R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, Fifth Circle.
" Examiner of Public Works Accounts.
" Revenue Department.
" Judicial "

Ekd. T. D. Ryan.
Spare Copies

GOVT. OF (1878) MADRAS.
PUBLIC WORKS

THE SUPERINTENDING ENGINEER,
MADRAS.

NOVEMBER

Nov. 30-81.

Sub-Collector's Office, Dindigul.
Tinnevely District. - Estimate of Rs 300
for provision of wire fence to the
land, and funds provided.

N^o 95.

Dist. Engrs Office Tinnevely
Palamcottah 13th Sept 1878.

Roads and
Buildings.

From,

J. I. Grant Esq^{re}
Off^g District Engineer
Tinnevely

To,

Colonel C. A. Ford R. C.
Chief Engineer D. P. W.
Madras

Sir,
Sir,

Referring to G. O. N^o 2138
of 13th May 1878, I have the honor
to request that a sum of Rs 300
may be allotted towards the erec-
tion of a wire fence round the
Sub-Collector's Danga low at
Taticorum instead of Rs 225 al-
lotted for this work.

An estimate of Rs 300
for this work which is approved
by the collector is herewith for-
warded for sanction.

I have the honor to be,
Sir,
Yours most obed^t serv^t
J. I. Grant
Off^g Dist Engineer

Public Buildings.

From

Off. No. 33
The District Engineer

Tinnevely.

To

The Chief Engineer
Dist. H.
Madras.

No.

75

Dated

13 September 1878.

No. of Enclosures.

2

1/1 Plan
Plan given to *Lipman*
Sub Collector *Pungabur*
at *Tinnevely*.

Enclosures undated
for erecting a wire fence
for sanitation.

Provisions
of Estimate

The estimate provides for
constructing a gate resting on
massive pillars as per accom-
panying drawing and for fencing
the boundary between this build-
ing and *Neerampathur*
enclosed with wire fencing sup-
ported at intervals by *Walrus*
posts upright & fastened at the
interstices to the gate pillars
& end pillars. The latter (construc-
ed one at either end of the boundary)

Concrete

The foundation of the pillars
to be of concrete composed of 2
parts of broken stone and one
of mortar well mixed together
& put down in layers of 6"
in thickness & a tamped
hard.

Rough stone
in chumam

The upper portion of the foundation

Particulars of work.	Number.	Measurements in feet and inches.				Contents.
		Length.		Breadth or thickness.	Depth or height.	
		Each.	Total.			
<hr/>						
For gate.						
Concrete (below foundation)						
gate & end pillars	4	4	16	4	$\frac{3}{4}$	48
Cubic feet						48
Cubic yds.						$1\frac{3}{4}$
Rough stone in channel.						
Foundation.						
gate & end pillars	4	3	12	3	$2\frac{1}{2}$	37
Cu feet.						37
Cu yds.						3
Roughly dressed stone in channel.						
Superstructure.						
gate & end pillars	4	2	8	2	$6\frac{1}{2}$	104
Cu feet.						104
Cu yds.						4
<hr/>						
Stenciling with 60 cut stone standards fixed to rods 2						
apart with 4 rows of telegraph wires passing through						
Linear yds.						
<hr/>						

B & R
Works
No 1279 W Public Works Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 7th Nov. 1878.

Read the following:—

229
6

From the Dist Engr. Tinnevely / H.C. No 95d / 13 Sept 1878

The Estimate of
Rupees 300 for providing
a wire fence to the Sub
Collector's Bungalow
at Tatticorum as sanctioned.

Rs 225 were
provided for the work
in G. O. No 2138 W of
13th May 1878, the difference,
Rs 75, is now appropriated
from the Provincial
Reserve.

Wk
1.11.78

Supd Engr 5 Circle
Exr P. W. Accts. South 1 Circle
Rev. Dept
Indl Dept

Wk

This sanction has been
registered as Provincial No. 125 B
of 11.11.78.

Spd Engr
11.11

Dated 19. 11. 78

Handwritten text, possibly a signature or date, located in the bottom left corner of the page.

10333-

Govt. of India

PUBLIC WORKS

The S.E. Fifth Circle.

12-11

7:000 42799

Nos. 90 11

Subcollector's bungalow
at Tattorian, Tanjore, M.
Estimate of Rs. 300 for
providing a wire fence
to the ———— sanctum,
and funds provided.

Est. in Rs.