

(1) Number of pages 24 ~~24~~ ~~8~~ ~~48~~ ✓
(2) Date of repair - 13 - 86 ✓
(3) Initials of the Referencer Car

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P.W DEPARTMENT

G.O. No.	4384 W	Press.
B.P. No.		Mis.
Dated	16.11.1898	197.

Not to be folded or roughly handled

92.3

4384
1

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

16th November 1878, No. 4,384 W.

Buildings and Roads,
Civil Works.

Read the following paper:—

No. 194. From Lieutenant-Colonel R. B. KENNEDY, District Engineer, Malabar, to the Chief Engineer, Buildings and Roads, dated Calicut, 16th September 1878, No. 65.

I HAVE the honor to forward, for your sanction and entry in the budget of 1879-80, a plan and estimate, amounting to Rupees 2,060, for constructing an additional ward to the Civil Dispensary at Palghat to accommodate twelve Police patients.

2. The plan and estimate have met with the approval of the Assistant Inspector-General of Police.

3. The Vice-President has permitted to construct the additional ward in the same compound where the Palghat Civil Dispensary now stands.

No. 195. ORDER THEREON, 16th November 1878, No. 4,384 W.

THE plan and estimate of Rupees 2,060, for an additional ward to the Palghat Civil Dispensary to accommodate twelve Police patients, are sanctioned.

2. This sanction has been registered as Provincial No. 139 B of 1878-79.

(True Extract.)

(Signed) E. A. FOORD, Colonel, R.E.,
Secretary to Govt., P.W.D.

To the Superintending Engineer, Fourth Circle.
" Examiner of Public Works Accounts.
" Inspector-General of Police.
" Judicial Department.

Exd. E. C. Shunker.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of Madras
PUBLIC WORKS.

To
THE SUPERINTENDING ENGINEER,
FOURTH CIRCLE,
&c., &c., &c.

Dated November 16th.

Issued

Recd.

Encl.

G. O., 16th November 1878, No. 4,334 W.

NOVEMBER.

Nos. 194-195.

Palghat Civil Dispensary, Malabar District. Sanctions plan and estimate for an additional ward to the

Specification.

4384/3

To accompany Estimate amounting to Rs 2080
for erecting an additional ward to the Civil Dispensary
Palghat in Palghat Taluk of Palghat Division
Malabar District.

Main Building

Is to have foundation on a layer of sand
3" thick & deep 4 3/4 wide for the Main walls & 3" deep and
2 1/4 wide for the smaller walls. The depth of foundation
for retaining walls should be 3 1/4 & 3.

Basement

Is to be 4 1/2 high and all the walls
should be 9" narrower in the Basement than in the
foundation leaving an offset 1 1/2 on each side, the filling
to be put and rammed as the Basement is raised.

Superstructure

The outer walls & Pillars in superstructure
should be 8 high and the centre partition walls 19 high
the intermediate walls should be built up to the roof all
the walls to be 9" less in thickness in superstructure than
in Basement.

Archwork

Plastering

Semicircular over doors and windows.
The inside of the walls should be
plastered and outside simply whitewashed.

Whitewashing

All the walls inside & outside are to be
whitewashed.

Flowering

Roofing

Books & Min

Bricks & Tiles

o. Kestler

Wood work

Sundries

L. G. H. H.

Assistant Engineer

Mt. W. Kuning. Lieut. Col.,
Distt. Engineer, Malacca

Specification for Erecting an
Additional to the Civil Dispensary
Palghat Papers 2030

Received } Dated 25th
July 1878

From
The Assistant Engineer
Palghat Division
To
The District Engineer
Malabar

267 1/2

Estimate of the Probable cost for Erecting an Addition to the Civil Dispensary Palghat Palghat Papers 2030

Measurement	Contents	Particulars	Rate	Amount	Remarks
26 1/2	3	21	1657.00	Longitudinal Main walls	Foundations
14 1/2	3	3	130.50	Transverse Main wall	
14 1/2	2 1/4	3	195.75	End walls	
26 1/2	2 1/4	3	246.87	Bar walls	
5 1/4	3 1/4	3	155.85	End and Portion walls of back verandah	
			1004.87	Worked over	

Erecting an addition to the Civil Dispensary

Estimated proposed to the District Engineer
understanding of 29/27. Amount 1078 on 2/10
understanding of 29/27/19 10/10

4384

1884-87 Brought Forward

3	3	3	4	1	108.00	Pillars
8 1/2	2 1/4	3	3	1	172.18	Retaining walls between Pillars
5	3 1/4	3	3	1	67.50	End of Verandah
34	8	1	1	1	192.00	Steps front
3 1/2	8	1	1	1	28.00	Car
3	3	3	3	1	54.00	Pillars to covered Passage
8	3 1/4	3	4	1	216.00	Retaining walls to
2222.49					Total Foundation	

Basement

35 3/4	2 1/4	4 1/2	2	1	723.93	Longitudinal Main walls
15 1/4	2 1/4	4 1/2	1	1	154.46	End
15 1/4	1 1/2	4 1/2	2	1	205.87	End walls
35 3/4	1 1/2	4 1/2	1	1	241.23	Car wall
6 1/2	1 1/2	4 1/2	4	1	175.50	End and Partition walls of back Verandah

2 1/4	2 1/4	4 1/2	4	1	91.12	Pillars
8 1/2	1 1/2	4 1/2	3	1	132.41	Retaining walls between P. Halls
5 3/4	1 1/2	4 1/2	2	1	77.62	End of Verandah
17 1/2	8	2 1/4	1	1	315.07	Steps front
4	8	2 1/4	1	1	72.00	Car
2 1/4	2 1/4	4 1/2	2	1	45.56	Pillars to covered Passage
8 1/2	1 1/2	4 1/2	4	1	229.50	Retaining walls to - P. Halls
<u>2512.28</u>					Total Basement	

Superstructure

35	1 1/2	8	2	1	540.00	Longitudinal Main walls
26 1/2	1 1/2	5 1/2	2	1	437.25	Gables to
16	1 1/2	13 1/2	1	1	334.00	Roofs Main wall
16	1 1/2	3	1	1	72.00	Gable to
					<u>1673.25</u>	Carried over
					28.00	

16	$\frac{3}{4}$	8	2	1673.25	Brought Forward
15 $\frac{1}{2}$	$\frac{3}{4}$	8	1	192.00	End walls
11 $\frac{1}{2}$	$\frac{3}{4}$	8	1	81.00	Red wall for right corner
11 $\frac{1}{2}$	$\frac{3}{4}$	8	1	69.00	82 82 left
7 $\frac{1}{2}$	$\frac{3}{4}$	10 $\frac{3}{4}$	2	116.00	Partition wall back verandah
7 $\frac{1}{2}$	$\frac{3}{4}$	8	2	87.00	End wall of 82
1 $\frac{1}{2}$	$\frac{1}{2}$	8	4	72.00	Hallway
1 $\frac{1}{2}$	$\frac{1}{2}$	8	4	72.00	82 to covered Passage
				2363.15	Total Superstructure

Deduction

4	$\frac{1}{2}$	7	2	86.00	Front Door
3 $\frac{1}{2}$	$\frac{1}{2}$	6	2	60.00	Rear Door
3	$\frac{3}{4}$	6	2	27.00	Doors in corner Room
3	$\frac{1}{2}$	4	4	72.00	Front windows
3	$\frac{3}{4}$	4	4	36.00	Windows in End walls

3 $\frac{1}{2}$	$\frac{3}{4}$	2 $\frac{1}{2}$	2	14.43	82 in corner Room
				296.43	Total deduction
				3066.72	Total superstructure less deduction
				1680.49	Total cost of Brick masonry

Plastering

32	8	3	768	Longitudinal walls both sides rectangular Port
35	8	1	280	82 at front
25	5 $\frac{1}{2}$	3	412.50	82 both sides of gables
16	13 $\frac{1}{2}$	2	432.00	Main cross wall both sides
16	3	2	96.00	Gables for 82 82
60 $\frac{1}{2}$	8	1	548.00	Inside of End & red walls
196 $\frac{1}{2}$	$\frac{1}{2}$	1	294.75	sides, soffits & walls of opening
			3851.25	Plastered Area

95234X

2831.25	Brought Forward	
7 1/2	10 1/2	Both sides of Partition wall on rear verandah
374.00	Total Plastering	
431	Reduction for door windows & frames Plastering	
3712	Net Total of Plastering	3 . . . (1099 21 58)

Whitewashing

35 1/2	4 1/2	Front of Basement inside	
25	4 1/2	Rear of ————	Do
20	4 1/2	Basement of Passage	
35 1/2	8	Outside of End wall	
25	8	——— of Rear wall	
8	2 1/2	Ends of slope front and rear	
6	8	Pillars in front and Passage	
1847 1/2	Total with		

Total Deductions

1761.87	Net Total of Plastering	4 . . . 149 4 65
---------	-------------------------	------------------

Plastering

35	6 3/4	Front Verandah	
10 1/2	15 1/4	Centre Room	
20 1/2	6 1/2	Corner Rooms	
1 1/2	6 3/4	Back Verandah	
20 1/2	9 1/4	Covered Passage	
1002.20	Total of Plastering with Paving stones 149 m		
	a layer of concrete will be removed	12 . . . 29 129 135	

Roofing

38	25	Main Building front & rear ends	
20 1/2	9 1/2	Covered Passage	
2289.50	Total of Roofing with hip common jack Roofs		
	Roofs, well & Plate Lino & complete	18 . . . 1099 4 12 19	

Cashed Book 1979 47

From

The Assistant Engineer
Palghat Division

To

The District Engineer
Malabar

W 10108/78

Appld 13011-11-11-78

Dated 22nd

Received

July 1878

Estimate for erecting an additional
to the Civil Dispensary Palghat

Rs 2080

No 65

From

The District Engineer
Malabar

To

The Chief Engineer

Roads and Buildings
Madras

My dear Sir

I have the honor to forward
for your sanction and entry in the Budget
of 1879-80 a Plan and Estimate amounting
to Rs 2080 for constructing an additional
ward to the Civil Dispensary at Palghat
to accommodate 12 Police patients.

The Plan & Estimate have met
with the approval of the Asst. Inspector
General of Police.

The Vice President has per-
mitted to construct the additional ward
in the same compound where the Palghat
Civil Dispensary now stands.

I have the honor to be
Sir

Your most Obedt. Servant

W. B. Hare Esq.
Dist. Engineer, Malabar

Recd of Police
Civil Dept. S. 11/11

Decr 25-11-78

Road and Buildings.

The District Engineer
Malabar

Dated 18th September 1878

Enclosure 2.

Additional ward to the Palghat
Dispensary. — Forward
Plan & Estimate for construction
—, for sanction
& entry in the Budget of 1879-80

B & R
Al works 1878

N^o 4384 W Public Works Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 16th Novr 1878.

Read the following:—

From
The District Eng^r Malabar (N^o. 465 of 16th Sept^r 1878)

The plan and
estimate of Rupees 2060
for an additional ward
to the Palghat Civil
Dispensary, to accommo-
date 12 Police patients,
are sanctioned. W.L.
cut 13.11.78.

This sanction has been
registered as Provincial No. 139/B
of 1878-79.

Supp. Eng^r 4th Circle
Supt. P. W. Accts. & Estimate
Insp^r Genl. of Police
Judicial Dept^r S. W.

Dec^r 25-11-78

Ch 21
No. of (1878) Madras.
PUBLIC WORKS.

To the S.E. Fourth Circle

Dated

Issued

Recd.

Encl.

G. O. 16 Nov. 1878, No. 4384 W

Nos. 194 & 195 -

Polyhat Civil Dispensary
Moolabar Do of another
plan & estimate for an
additional ward to the

Ents in Reg.