

(1) Number of pages 18
 (2) Date of repair 5-5-86
 (3) Initials of the Referencer lomb

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

PWD DEPARTMENT

G.O. No.	582-W	Press.
B.P. No.		Mis.
Dated	4-2-1878	197

8 21

Not to be folded or roughly handled

GOVERNMENT OF MADRAS.
PUBLIC WORKS DEPARTMENT.

4th February 1878, No. 582 W.

Buildings and Roads.
Civil Works.

Read the following papers:—

No. 30. From Major J. BEATTY, R.E., Officiating Superintending Engineer, Godavery District, to the Chief Engineer for Buildings and Roads, dated Camp at Dowlaishweram, 21st December 1877, No. 3,001.

As directed in G.O., No. 174, of 27th November 1876, I have the honor to submit herewith an estimate, amounting to Rupees 33,200, together with the survey plan of site and plan of buildings proposed for the new Court House at Rajahmundry, and to request that you will be so good as to obtain the sanction of Government; and if possible an allotment of funds in the Budget of 1878-79, as the old Court House is in a very

Vide also No. 54 W of 7th August 1877, No. 949 W of 9th October 1877, and No. 1,747 W of 21st November 1877.

decayed state, and some parts cannot now be used owing to their dangerous condition.
2. The site can now be had for Rupees 260, and as it is the best and only convenient site it ought to be secured at once. The present owner is anxious to part with it, and if he disposes of it to other parties the next owner may demand a larger price. I therefore strongly recommend that permission be given to make the purchase now.

No. 30-A. From T. WEIR, Esq., Acting Registrar of the High Court of Judicature at Madras, to the Deputy Chief Engineer, Public Works Department, dated Madras, 24th January 1878, No. 162.

I HAVE the honor to return duly countersigned the plan, estimates and specification of the new Court House proposed to be erected at Rajahmundry, forwarded to me with your letter No. 376, dated 21st instant, for that purpose.

No. 31. ORDER THEREON, 4th February 1878, No. 582 W.

THE plan and estimate of Rupees 33,200 for constructing a new Court House at Rajahmundry are sanctioned.

2. It is not practicable to provide funds for the work in the outgoing Budget. But the District Engineer will secure the site, paying for it early in April next from the grant which will be at his disposal under Minor New Works, Civil Buildings, Provincial.

3. This sanction has been registered as Provincial No. 274 B of 1877-78.

(True Extract.)

Colonel, R.E.,
Secretary to Government, P.W.D.

To the District Engineer, Godavery.
" Examiner of Public Works Accounts.
" Judicial Department.

Exd. S. T. Austin.
Spare Copies

Original

BUILDINGS AND ROADS
CIVIL WORKS.

Govt. of (1878) Madras
PUBLIC WORKS.

To

THE DISTRICT ENGINEER,
GODAVERY,
Dist. Eng. Off.

Date: February 4th.

Issued.

Recd.

Encl.

G. O. 4th February 1878, No. 332 W.

FEBRUARY.

Nos. 30-31.

New Court House at Rajahmundry, Godavery District. — Sanctions with remarks to plan and estimate for constructing a —

NO. 300, Roads and Buildings.

FROM,

THE OFFG. SUPERINTENDING ENGINEER

GODAVERY DISTRICT.

TO,

THE CHIEF ENGINEER

FOR ROADS AND BUILDINGS.

CAMP DOWLAISHWERAM, 21 December 1877

Encl. 4
1 Plan
1 Site Plan
1 Estimate
1 Specification

SIR,

As directed in G. O. No. 174 of 27th November 1876, I have the honor to submit herewith an estimate amounting to Rs. 33,200, together with the survey plan of site and plan of Buildings proposed for the new Court House at Rajahmundry and to request that you will be so good as to obtain the sanction of Government; and if possible allotment of funds in the Budget of 1878/79 as the old Court house is in a very decayed state, and some parts cannot now be used owing to their dangerous condition —

2. The site can now be had for Rs. 260

and

and as it is the best and only convenient site it ought to be secured at once. The present owner is anxious to part with it, and if he disposes of it to other parties the next owner may demand a larger price; I therefore strongly recommend that permission be given to make the purchase now -

I have the honor to be

Sir

Your Most Obedt Servant
L. Scally Major R.E.
Offg. Superintending Engg. Gory

Roads and Buildings.

FROM,

THE OFFG. SUPERINTENDING ENGINEER

GODAVERY DISTRICT.

TO,

THE CHIEF ENGINEER

FOR ROADS AND BUILDINGS.

DATED 21st December 1877.
RECEIVED

No. 3001

Plan with Librarian
ENCLOSURE.

Rajahmundry —
New Court house at —

Forwarding the plans &
Estimate for sanction for
building the —

Memo 376 - 21 Jan 78

20/12/77

From

The Acting Registrar of the
High Court of Judicature
at Madras

To The Deputy Chief Engineer,
Public Works Department

Sir,

I have the honor to return
duly countersigned the Plan, Estimates
and Specification of the new Court-
House proposed to be erected at
Rajabundary forwarded to me with
your letter No 376 dated 21st Instant,
for that purpose.

I have the honor to be,

Sir,

Your most Obedient Servant,

Oden

Acting Registrar,

App. Side

High Court of
Judicature, Madras,
24 January 1878.

3 137
N^o. 582 W Public Works Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

Under date the 4th Feb 1878.

Read the following:—

Letter from the Dist. Eng^r. Godavery (H. C. N^o. 3001 dated 21st December 1877).
Letter from the Registrar of the High Court of Judicature Madras } (H. C. N^o. 162 dated 24th January 1878).

The plan and estimate of Rs. 33,200 for constructing a new Court House at Rajahmundry are sanctioned.

It is not practicable to provide funds for the work in the outgoing Budget. But the District Engineer will secure the site paying for it early in April next from the grant which will be at his disposal under Minor New Works, Civil Buildings, Provincial.

W. H. 30.1.78

This sanction has been registered as Provincial No 274 B
District Engineer, Godavery.
Examiner P. W. Accounts. 15/1/1878
Judicial Department.

R. A. B. 8-2-78

CE 376 21.1.78.
No. 1747 W 21.11.77
" 949 W 29.10.77
" 54 W 27.8.77
" 174 27.11.76

Plan with
Librarian.

800

Ar 21-1-78. 24.2.78

10. Huddleston

Specification for the New Court
House proposed to be constructed
at Rajahmundry.

To be laid under foundations
of all walls, pillars, and retaining walls
2 feet deep and as per breadth shown
in the drawing and also under steps
in the inside of Court as shown in the
plan. Proportion of sand to lime
2 to 1. One basket of the chumam being
used with 3 of broken stone; 2 baskets of the
broken stone to be first laid, then one of
chumam, & lastly one of broken stone; the
stone and chumam to be then well mixed
with mortar, then watered and rammed.
One course of concrete, which will be about
6 inches thick, over the whole of the foundation
to be done per day. It should be well
rammed for about half a day and water
occasionally thrown over it afterwards to
keep it moist.

The lime to be ^{made from} water lime stone
burnt in the kiln belonging to the
Department. The chumam throughout
the

the building to consist of 2 parts of clean sharp river sand to 1 part lime.

Of all walls, pillars, and retaining walls to be built of Rough stone in chunam 3 feet deep and as per breadth shown in the drawing.

Of all walls, pillars, and retaining walls to be built of rough stone in chunam 3 feet high and as per breadth shown in drawing.

All ^{the} walls are to be built with rough stone in chunam. The walls of the Court are to be 18 ft high up to the level of the tie rods, and of the thicknesses shown in the drawing; all the walls of the building for the Sheristadar & clerks ~~etc~~ are to be $1\frac{1}{2}$ ft thick and 15 ft ^{high} to level of tie rods.

To be laid with cubetone in chunam.

To be of rectangular cubetone slabs in parallel courses ^{3 to 5 ft} thick laid on a bed of concrete 6 inches thick and pointed with chunam.

The exterior of the walls is not to be plastered, and the face of the stone to be neatly dressed. The chunam used in pointing the dressed faces of the exterior of the building to be $1\frac{1}{2}$ parts sand to 1 part lime.

The inside of the walls to be plastered with 2 coats of chunam and whitewashed.

The main and out buildings to be roofed with flat and prantiles and chunam borders complete on teakwood reapers rafters trusses ~~etc~~ as shown in the drawing. All ^{work} the wood work in the building is to be of teak; the larger pieces may have to be made up from Pegu logs, but all the rest should be of Godavery teak.

The verandah roof to be of the sloping terrace pattern with 1 course of large flat tiles covered with $1\frac{1}{2}$ " concrete & 2 coats of plastering complete over the reapers. The slope of the verandah roofs to be inches to 1 foot.

8/562w

The rates provided for wood and iron work allow of the work being done by the workshop which will also fit it up at the site. The rates include workshop cartage.

All wood work & doors and windows are to be varnished in 3 coats.

District Eng^r's office, L. Beatty, Major A.E.
15th December 2, Offy: Superintending Eng^r
1877 3

High Court of
Madras
26 January 1878

Ap. Registrar,
Appellate Side.

In H. C. No 472/78

582W

Enclosed in a letter
No 3001 dated 21st December
from the Offy. Sup^r Eng^r
Godfrey

Crossed

Govt. of 1878; *Madras*
PUBLIC WORKS.

To *the M. B. L. Lavery*

Dated

Issued

Recd.

Encl.

G. O., 4 July 1878, No. *SB2W*

No.

Recd I have at
Long, R. B. D.
at *Remark*
to *permanence*

But not