Archives 1—10,000—6-10-76.

(1) Number of pages 32

(2) Date of repair 24-10-86.

(3) Initials of the Referencer

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

Public Works DEPARTMENT

G.O. No. ~~B.P. No.~~	1021 W	Press. ~~Mis.~~
Dated	2-4-1879	~~197~~.

Not to be folded or roughly handled

1021
1

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

2nd April 1879, No. 1,021 W.

Buildings and Roads.
Civil Works.

Read the following paper :—

No. 44. Proceedings of the Madras Government in the Public Department, dated 26th March 1879, No. 452.

Read the following letter from the Consulting Architect to Government, through Public Works Department, dated 31st January 1879, No. 532.

Read also letter from the Surgeon-General, Indian Medical Department, dated 21st March 1879, No. 140.

His Grace the Governor in Council approves the plan and estimate (Rs. 6,046) prepared by the Consulting Architect to Government for a Medical School to be erected near the Monegar Choultry, and desires that the requisite orders be issued in the Public Works Department for the provision of funds and for the execution of the work.

2. The design of the plan admits of extension which can be carried out when funds are available.

3. The site selected for the school is approved.

(True Extract.)

(Signed) C. G. MASTER,
Ag. Chief Secretary.

No. 45. Order thereon, 2nd April 1879, No. 1,021 W.

Communicated to the Consulting Architect to Government, who will include the work in the statement of demands to be submitted during the current month.

2. The sanction accorded in the above Proceedings in the Public Department has been registered as Provincial No. 1 B of 1878-79.

(True Extract.)

Major, R.E.,
Ag. Under Secy. to Govt., P.W.D.

To the Consulting Architect.
,, Examiner of Public Works Accounts.

Exd. C. Howarth.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of (1879) Madras.

PUBLIC WORKS.

To

THE CONSULTING ARCHITECT,

&c.

Dated April 2nd.

Issued

Recd.

Regd.

G. O., 2nd April 1879, No. 1,021 W.

APRIL.

Nos. 44-45

Medical School to be erected near the Monegar Choultry, Madras.—Proceedings, Public Department, approving the plan and estimate for the ——, communicated to the Consulting Architect.

1

1021/18

Public Department.

PROCEEDINGS *of the* MADRAS GOVERNMENT.

Read the following letter from the Consulting Architect to Government, through Public Works Department, dated 31st January 1879, No. 532.

Read also letter from the Surgeon General Indian Medical Department dated 21st March 1879 No. 140.

Order thereon 26th March 1879 No. 252

His Grace the Governor in Council approves the plan and *estimate prepared by the Consulting Architect to Government for a Medical School to be erected near the Monegar Choultry, and desires that the requisite orders be issued in the Public Works Department for the provision of funds and for the execution of the work.

*Rs. 6046.

2. The design of the plan admits of extension which can be carried out

when

when funds are available.

The site selected for the School is approved.

(True Extract)

G. Masters

Actg. Chief Secretary

To
The Public Works Department
(with Plan and Estimate)
(Printed copy will follow)

1021/4

×

Govt. of {187} Madras.

To

Dated } 187 , No.
Recd.

Nos.

× Retd. to the Consg. Architect on the 8-11-80. (vide L. No. 7089 of '80)

8-11-80.

Pro. of 2-4-79 No. 1021 [illegible]

621/5

Descriptive Specification of Medical School and Dissecting room - Moonegar Choultry.

The buildings will be erected on a site to be selected in communication with the Medical department.

The walls will consist of Brick in Mortar plastered internally and externally.

The doors will be of teak wood painted oak color and fitted with brass fastenings.

The steps will be of cut-stone.

The roofing will consist of School of Arts tiles supported by teak wood timber.

The materials and workmanship will be the best of quality and kind.

R Chisholm

Consg Archt to Govt.

Estimate of the cost of constructing a Medical school with dissecting Room at the Monegar Chaultry

Detailed quantities

Description of work	No	L	B	D	Contents	Total
Excavation for foundations						
Lecture Hall outer walls		106 . 0	5 . 6	5 . 0	5060 ✓	
Store room Do		35 . 0	5 . 6	5 . 0		
Medical Officers room Do		43 . 0	5 . 6	5 . 0		
Verandah walls		123 . 10	4 . 10	5 . 0	2993 ✓	
Steps		10 . 0	3 . 0	1 . 6	77 ✓	
do		7 . 0	3 . 0	1 . 6		
Cubic ft					8130 ✓	
Cubic yds						301 ✓
Earthfilling in basement						
Lecture Hall		30 . 0	20 . 0	1 . 6	900 ✓	
Stores		8 . 0	20 . 0	1 . 6	240 ✓	
Medical Officers room		15 . 0	14 . 0	1 . 6	315 ✓	
Verandah		100 . 8	7 . 2	1 . 0	721 ✓	
Cubic ft					2176 ✓	
Cubic yds						81 ✓
Concrete						
Lecture Hall outer walls		106 . 0	4 . 6	1 . 0	837 ✓	
Store room Do		36 . 0	4 . 6	1 . 0		
Medical Officers room Do		44 . 0	4 . 6	1 . 0		
Carried over					837 ✓	

	Braught forward		837 ✓
Verandah walls		125 - 10 3 - 10 1 - 0	482 ✓
Steps		10 - 0 3 - 0 1 - 0	51 ✓
do		7 - 0 3 - 0 1 - 0	
		Cubic ft.	1370 ✓
		Cubic yds	51 ✓

Brickwork in foundations & basement

footings

Lecture Hall outer walls		106 - 0 2 - 6 1 - 6	713 ✓
Store room do		38 - 0 2 - 6 1 - 6	
Medical Officers room do		46 - 0 2 - 6 1 - 6	
Verandah walls		129 - 10 1 - 10 1 - 6	357 ✓
Above footings to floor level			
Lecture Hall outer walls		106 - 0 1 - 6 4 - 6	1296 ✓
Store room Do.		39 - 0 1 - 6 4 - 6	
Medical Officers room Do.		47 - 0 1 - 6 4 - 6	
Extra thickness for plinth		60 - 0 0 - 3 4 - 6	68 ✓
Verandah walls		131 - 10 0 - 10 4 - 0	439 ✓
Steps	1	10 - 0 3 - 0 1 - 0	30 ✓
do	1	8 - 0 2 - 0 0 - 6	8 ✓
do	1	6 - 0 1 - 0 0 - 6	3 ✓
steps	1	7 - 0 3 - 0 1 - 0	21 ✓
do	1	6 - 0 2 - 0 0 - 6	6 ✓
do	1	5 - 0 1 - 0 0 - 6	3 ✓
			2944 ✓
Deduct cut stone in steps		Cub ft.	33 ✓
		Cubic ft.	2911 ✓
		Cubic yds	108

Brickwork in superstructure

Lecture Hall outer walls		106 - 0 1 - 6 16 - 8	2650 ✓
		Carried over	2650 ✓

		Braught forward		2650 ✓
Lecture Hall Gables	2	23 - 0 1 - 6 3 - 10	265 ✓	
Do. platform		20 - 4 0 - 10 1 - 6	25 ✓	
Store room back wall		23 - 0 1 - 6 7 - 0	242 ✓	
Do side walls	2	8 - 0 1 - 6 9 - 6	228 ✓	
Medical Officers room outer walls		47 - 0 1 - 6 10 - 6	740 ✓	
Do Gable	1	17 - 0 1 - 6 2 - 10	72 ✓	
				4222 ✓
Deductions				
Doors	7	4 - 0 1 - 6 8 - 0	336 ✓	
Do	3	3 - 6 1 - 6 8 - 0	126 ✓	
Windows	2	2 - 6 1 - 6 5 - 0	38 ✓	
upper lights	2	10 - 0 1 - 6 4 - 6	135 ✓	
Ventilators	7	4 - 6 1 - 6 3 - 0	142	
Do	1	10 - 0 1 - 6 1 - 0	15 ✓	
Archwork as per details			122 ✓	
				914 ✓
			Cubic ft.	3308 ✓
			Cubic yds	123 ✗

Archwork

Segmental arches over doors	7	5 - 0 1 - 6 1 - 0	✓ 122 Cft
do do	3	4 - 6 1 - 6 1 - 0	
do windows	2	3 - 6 1 - 6 1 - 0	
do upperlights	2	13 - 0 1 - 6 1 - 0	
		Cubic yds	5 ✗

Cut stonework in steps

31 - 0 1 - 3 0 - 6		
21 - 6 1 - 3 0 - 6	33 ✓	
	Cubic ft.	33 ✗

Teakwood

Lecture Hall

2 Trusses 20 ft span	Tie beam	2	23 . 00	50	8	13 ✓
	Principal rafters	4	13 . 00	40	6	9 ✓
	Struts	4	6 . 30	40	4	3 ✓
	Purlins	2	37 . 00	50	6	15 ✓
	wall purlins	2	37 . 00	40	4	8 ✓
	Ridge	1	37 . 00	2½0	8	5 ✓
	Common rafters	50	15 . 60	30	4	65 ✓
	Barge board	4	16 . 01	30	1½	10 ✓
	Do	2	7 . 60	30	3	2 ✓
	Do	4	3 . 60	30	3	

Medical Officers room

1 Truss 14 ft span	Tie beam	1	17 . 00	40	6	3 ✓
	Principal rafters	2	9 . 30	40	4	2 ✓
	Struts	2	4 . 40	30	4	1 ✓
	Purlins	2	19 . 00	40	5	5 ✓
	wall purlins	2	19 . 00	30	4	3 ✓
	Ridge	1	19 . 00	2½0	6	2 ✓
	Common rafters	24	11 . 90	2½0	3	15 ✓
	Barge board	2	12 . 01	00	1	2 ✓
Store room rafters		15	13 . 00	30	4	16 ✓
	wall plate		23 . 00	30	3	1 ✓
	Brackets double	2 × 15	5 . 00	10	3	3 ✓
	uprights	15	0 . 30	23	3	2 ✓
Verandah posts		2	0 . 40	48	9	2 ✓
	Do	14	0 . 40	46	3	10 ✓
Struts		24	2 . 30	30	4	5 ✓
Cleats		24	1 . 00	30	4	2 ✓
Breastsummers			130 . 00	40	5	18 ✓
Rafters		60	11 . 60	30	4	58 ✓
Hip rafters		6	13 . 00	40	5	11 ✓
Small rafters for entrance		14	6 . 00	30	4	7 ✓
Barge board for do		2	11 . 00	60	1	1 ✓
Barge board		1	7 . 00	30	4	1 ✓
	do	2	5 . 01	60	3	4 ✓
	do	2	3 . 60	30	4	1 ✓
Wall plate		1	95 . 00	30	3	6 ✓
Brackets double		2 × 60	5 . 00	10	3	13 ✓
uprights		60	0 . 30	23	3	8 ✓
Cleats to secure rafters to Breastsummers		60	0 . 80	31	0	10 ✓
Reepers 3" centres			12,300 . 00	1¼0	1¼	133 ✓
					Cubic ft.	475 ✓

1029/16

Doors and windows

Doors	7	4 . 0	8 . 0	224 ✓
do	3	3 . 6	8 . 0	84 ✓
Windows	2	2 . 6	5 . 0	25 ✓
Clear storey lights	2	10 . 0	4 . 6	90 ✓
			squareft.	423 ✓

Ventilators

Lecture Hall	7	4 . 6	3 . 0	95 ✓
Store room	1	10 . 0	1 . 0	10 ✓
			squareft.	105 ✓

Roofing

Lecture Hall	1	36 . 6	31 . 0	1132 ✓
Medical Officers room	1	18 . 0	23 . 6	423 ✓
Store room	1	23 . 0	12 . 6	288 ✓
Verandah		104 . 0	11 . 0	1144 ✓
			squareft.	2987 ✓
			squares	30 ✓

Flooring with square tiles.

Lecture Hall		20 . 0	30 . 0	600 ✓
Medical Officers room		14 . 0	15 . 0	210 ✓
Door pieces	7	4 . 0	1 . 6	42 ✓
Do	2½	3 . 6	1 . 6	13 ✓
Verandah		104 . 0	8 . 0	832 ✓
			squareft.	1697 ✓
			squares	17 ✓

Flooring with asphalte 3/4" thick

2 Store room		8 - 0	20 - 0	161 ✓
Door piece	½	3 - 6	1 - 6	3 ✓
			squareft	163 ✓
			squares	1 3/5

Plastering interior

Lecture Hall		100 - 0	16 - 8	1667 ✓
Medical Officers room		58 - 0	10 - 6	609 ✓
Gables	2	20 - 0	3 - 4	133 ✓
1 do	2	14 - 0	2 - 4	65 ✓
Store room		40 - 0	9 - 0	360 ✓
do	2	8 - 0	9 - 0	144 ✓
Door jambs	7	20 - 0	1 - 6	210 ✓
do	3	19 - 6	1 - 6	88 ✓
Window jambs	2	15 - 0	1 - 6	45 ✓
do	2	32 - 0	1 - 6	96 ✓
Ventilator jambs	7	10 - 6	1 - 6	110 ✓
do	1	12 - 0	1 - 6	18 ✓
				3545 ✓
Deductions				
Doors	8	4 - 0	8 - 0	256 ✓
do	3	3 - 6	8 - 0	84 ✓
Windows	2	2 - 6	5 - 0	25 ✓
Upper lights	2	10 - 0	4 - 6	90 ✓
Ventilators	7	4 - 6	3 - 0	95 ✓
do	1	10 - 0	1 - 0	10 ✓
				560 ✓
			squareft	2985
			squares	30 ✓

Plastering exterior

Basement		197 - 0	1 - 6	296 ✓
			Carried over	296

102/9

			Brought forward	296 ✓
Superstructure		112 - 0	17 - 0	1904 ✓
do	2	9 - 6	9 - 0	171 ✓
	2	17 - 0	11 - 0	374 ✓
Gables	2	23 - 0	3 - 10	176 ✓
				2921 ✓
Deductions				
Doors	6	4 - 0	8 - 0	192 ✓
do	3	3 - 6	8 - 0	84 ✓
Windows	2	2 - 6	5 - 0	25 ✓
upper lights	2	10 - 0	4 - 6	90 ✓
Ventilators	7	4 - 6	3 - 0	95 ✓
do	1	10 - 0	1 - 0	10 ✓
				496 ✓
			squarefeet	2425 ✓
			squares	24 1/4

Painting with 3 coats of wood-oil

2	23 - 0	2 - 2	100 ✓
4	13 - 0	1 - 8	87 ✓
4	6 - 3	1 - 4	33 ✓
2	37 - 0	1 - 5	105 ✓
2	37 - 0	1 - 4	99 ✓
1	37 - 0	1 - 6½	57 ✓
48	15 - 6	0 - 11	682 ✓
1	17 - 0	1 - 8	28 ✓
2	9 - 3	1 - 0	19 ✓
2	4 - 4	1 - 2	10 ✓
2	19 - 0	1 - 2	44 ✓
2	19 - 0	1 - 2	44 ✓
1	19 - 0	1 - 2½	23 ✓
24	11 - 9	0 - 8½	200 ✓
15	13 - 0	0 - 11	179 ✓
30	5 - 0	0 - 7	88 ✓
15	3 - 3	0 - 8	33 ✓
60	11 - 6	0 - 11	633 ✓
		Carried over	2464 ✓

Brought forward 2464 ✓

6	13 . 0	1 . 2	91 ✓
14	6 . 0	0 . 11	77 ✓
120	5 . 0	0 . 7	350 ✓
60	3 . 3	0 . 8	130 ✓
	12300 . 0	0 . 3$\frac{3}{4}$	3844 ✓

squareft 6956 ✓

squares 69½

Painting with 3 coats of Carsons paint

Doors
do
Windows
Clear story light
Ventilators

3 × 7	4 . 0	8 . 0	672 ✓
3 × 3	3 . 6	8 . 0	252 ✓
3 × 2	2 . 6	5 . 0	75 ✓
2 × 2	10 . 0	4 . 6	180 ✓
3 × 7	4 . 6	3 . 0	189 ✓
2 × 1	10 . 0	1 . 0	20 ✓
4	16 . 0	1 . 4½	88 ✓
2	5 . 0	0 . 9	8 ✓
	29 . 0	0 . 9	22
2	3 . 6	1 . 2	8
2	12 . 0	1 . 1	26
2	11 . 0	0 . 7	13
2	8 . 6	1 . 4	23 ✓
1	7 . 0	1 . 2	8
14	6 . 0	1 . 4	112
24	2 . 3	1 . 2	63
	116 . 0	1 . 6	174

Squareft 1933 ✓

Squares 19⅓

Wrought Iron work in trusses

1¼" diar. King rods for 20 ft trusses 2 9 . 0 18 . 0 × 4.09 = 73.62

Carried over 73.62

Brought forward 73.62 ✓

1¼" hex nuts & bolt heads for 20 ft trusses	2			× 3.21 =	6.42 ✓
1" diar. King rods for 14 ft trusses	1	6 . 0		× 2.62 =	15.72 ✓
1" hex nuts & bolt heads for do	1	–		× 1.65 =	1.65 ✓
3" × 3" × ⅛" washers	9			× 0.32 =	2.88 ✓
2" × ½" flat iron straps for 20 ft trusses	4	3 . 3	13 . 0	× 3.34 =	43.42 ✓
2¼" × ⅝" bearing plates for do	4	0 . 9	3 . 0	× 4.69 =	14.07 ✓
1½" × ⅜" flat iron straps for 14 ft do	2	2 . 6	5 . 0	× 1.87 =	9.35 ✓
1¾" × ½" bearing plates for do	2	0 . 7	1 . 2	× 2.92 =	3.40 ✓
½" hex nuts for securing straps to plat	12			× 0.13 =	1.56 ✓
2" × 2" × ⅛" washers for Do	12			× 0.14 =	1.68 ✓

lbs 173.77 ✗

Interior Cornice 158 Lin ft

Wooden Ornaments in Gables 4 in Number

— Do — over verandah posts 26 in Number

Dissecting room

Excavation for foundations

Walls	59 . 0	5 . 3	5 . 0	1549 ✓
do	6 . 0	4 . 10	5 . 0	145 ✓
steps	10 . 0	3 . 0	1 . 6	45 ✓

Cubic ft 1739

Cubic yds 65 ✗

Earthfilling

1	15 - 0	12 - 0	1 - 0	180	Cft

Cubic yds 7 ✓

Concrete

Outer walls

do

steps

59 - 0	4 - 3	1 - 0	251	✓
6 - 6	3 - 10	1 - 0	25	✓
10 - 0	3 - 0	1 - 0	30	✓

Cubft 306 ✓

Cubic yds $11\frac{1}{3}$

Brickwork in foundations & basement

walls footings

do do

above footings to floor level

do do

Plinth

steps

Deduct cut stone in steps

	59 - 0	2 - 3	1 - 6	199	✓
	7 - 6	1 - 10	1 - 6	21	✓
	59 - 0	1 - 3	4 - 0	295	✓
	7 - 9	0 - 10	4 - 0	26	✓
	56 - 1	0 - 3	4 - 0	56	✓
1	10 - 0	3 - 0	1 - 0	30	✓
1	8 - 0	2 - 0	0 - 6	8	✓
1	6 - 0	1 - 0	0 - 6	3	✓
				638	✓
				19	✓

Cubicft 619 ✓

Cubic yds 23

Brickwork in superstructure

Walls

Gables

wall

Deductions

Doors

Window

	59 - 0	1 - 3	9 - 6	701		✓
2	14 - 6	1 - 3	2 - 5	88		✓
1	8 - 0	0 - 10	5 - 6	37		✓
					826	✓
1	4 - 0	1 - 3	8 - 0	40		✓
1	6 - 0	1 - 3	6 - 0	45		✓
			Carried over	85 ✓	826	

Brought forward	85 ✓	826 ✓
Archwork as per details	15 ✓	100 ✓

Cubic ft 726 ✓

Cubyds 27 ×

Archwork

door	1	5 - 0	1 - 3	1 - 0	6	✓
window	1	7 - 6	1 - 3	1 - 0	9	✓

Cubic ft 15 ✓

Cubic yds $\frac{5}{9}$ ×

Cutstonework

steps	31 - 0	1 - 3	0 - 6	19 ×	Cubft

Teakwood.

Rafters	26	10 - 6	0 - 3	0 - 4	23	✓
Collars (double)	22	6 - 0	0 - ½	0 - 3	4	✓
Brackets (double)	44	3 - 0	0 - 1	0 - 3	3	✓
uprights	22	2 - 0	0 - 3	0 - 3	3	✓
Small purlins at ends	10	2 - 3	0 - 3	0 - 4	2	✓
Barge board	4	11 - 0	0 - 9	0 - 1	3	✓

Cubicft 38 ×

Doors and windows

Door	1	4 - 0	8 - 0	32	✓
Window	1	6 - 0	6 - 0	36	✓

68 × squareft

Roofing

20 - 0	22 - 0	440 ✓	sqreft

squares $4\frac{1}{2}$ ×

Flooring with asphalte 3/4" thick

Door piece	1	15 - 0	12 - 0	180 ✓
	1	4 - 0	1 - 3	5 ✓
			squareft	185 ✓
			squares	$1\frac{4}{5}$

Plastering interior

Gables		54 - 0	10 - 6	567 ✓
Door piece	2	14 - 6	2 - 5	70 ✓
Window	1	20 - 0	1 - 3	25 ✓
	1	25 - 0	1 - 3	31 ✓
				692
Deductions				
Door	1	4 - 0	8 - 0	32
Window	1	6 - 0	6 - 0	36
				68
			squareft	625
			squares	$6\frac{1}{4}$

Plastering exterior

Basement Walls		66 - 0	1 - 6	99 ✓
Gables wall		64 - 0	10 - 0	640 ✓
	2	14 - 6	2 - 5	70 ✓
	1	16 - 10	7 - 0	118 ✓
				927
Deduction				
Door	1	4 - 0	8 - 0	32 ✓
Window	1	6 - 0	6 - 0	36 ✓
				68
			squareft	859
			squares	$8\frac{1}{2}$

Painting with 3 coats of wood oil

	26	10 - 6	0 - 11	250 ✓
	22	6 - 0	0 - 9	99
	44	3 - 0	0 - 8	88 ✓
	22	2 - 0	1 - 0	44 ✓
	10	1 - 0	0 - 11	9 ✓
			squareft	490 ✓
			squares	5 ✗

Painting with 3 coats of Carson's paint

Door	3×	1	4 - 0	8 - 0	96 ✓
Window	3×	1	6 - 0	6 - 0	108 ✓
Barge board		4	11 - 0	0 - 10	37 ✓
				squareft	241 ✓
				squares	$2\frac{1}{2}$ ✗

Sink and trap complete	1 in Number ✓
Large table	1 in Number ✗
Small table	1 in Number ✗

1021/13

Abstract

Quantity	Item	Rate	Per	amount	Total
	School				
√ 301 Cyds	Excavation for foundations	" 1 6	Cyd	28 3 6 √	
√ 81 "	Earthfilling in basement	" 1 "	"	51 " √	
√ 51 "	Concrete	4 " "	"	204 " " √	
√ 108 "	Brickwork in foundations & basement	4 12 "	"	513 " " √	
√ 123 "	Do. in Superstructure	5 12 "	"	707 4 " √	
√ 5 "	Archwork	6 4 "	"	31 4 " √	
√ 33 Cft	Cut stonework for steps	1 8 "	Cft	49 8 " √	
√ 475 "	Teakwood	3 " "	"	1425 " " √	
√ 423 sft	Doors and windows with brass fastenings	1 4 "	sft	528 12 " √	
√ 105 "	Ventilators	1 " "	"	105 " " √	
√ 30 sqrs	Roofing	25 " "	sqrs	750 " " √	
√ 17 "	Flooring with square tiles	8 6 "	"	142 6 " √	
√ 1⅗ "	Do with asphalte ¾" thick	25 " "	"	40 " " √	
√ 30 "	Plastering interior colored	3 " "	"	90 " " √	
√ 24¼ "	Do. exterior with colored bands	3 4 "	"	78 13 " √	
√ 69½ "	Painting woodwork of roof with 3 coats of wood oil	" 14 "	"	60 13 " √	
√ 19⅓ "	Painting with 3 coats of Carsons paint	3 " "	"	58 " " √	
√ 174 lbs	Wroug Iron work in trusses	" 3 "	lb	32 10 " √	
√ 158 Lft	Interior Cornice	" 4 "	Lft	39 8 " √	
√ 4 No	Ornamental Gables	6 " "	each	24 " " √	
√ 26 "	Do. over verandah post	1 8 "	"	39 " " √	
	Contingences at 5 percent			247 13 6 √	5200 " X
	Dissecting room				
√ 65 Cyds	Excavation for foundations	" 1 6	Cyd	6 1 6 √	
√ 7 "	Earthfilling in basement	" 1 "	"	" 7 " √	
√ 11⅓ "	Concrete	4 " "	"	45 5 4 √	
	Carried over			51 13 10 √	5200 " " √

	Qty	Unit	Description	Rate	Per	Amount		Total
			Brought Over			51 13 10	✓	5200 .
✓	23	Cyds	Brickwork in foundations & basement	4 12 .	cyd	109 4 .	✓	
✓	27	"	Do. in Superstructure	5 12 .	"	155 4 .	✓	
✓	$\frac{5}{9}$	"	Archwork	6 4 .	"	3 7 6	✓	
✓	19	Cft.	Cutstone for steps	1 8 .	cft.	28 8 .	✓	
✓	38	"	Teakwood wrought & putt. up	3 " "	"	114 . .	✓	
✓	68	sft.	Doors and windows	1 4 .	sft	85 . .	✓	
✓	$4\frac{1}{2}$	sqrs	Roofing	25 . .	sqre	112 8 .	✓	
✓	$1\frac{4}{5}$	"	Flooring with asphalte $\frac{3}{4}$" thick	25 .	"	45 . .	✓	
✓	$6\frac{1}{4}$	"	Plastering interior	3 " .	"	18 12 .	✓	
✓	$8\frac{1}{2}$	"	Do. exterior	3 4 .	"	27 10 .	✓	
✓	5	"	Painting roof with 3 coats of wood oil	. 14 .	"	4 6 .	✓	
✓	$2\frac{1}{2}$	"	Painting with 3 coats of carsons paint	3 . .	"	7 8 .	✓	
✓	1	No.	Sink and trap complete	10 . .	each	10 . .	✓	
✓	1	"	Table (large)	25 . .	"	25 . .	✓	
✓	1	"	Do. (small)	7 . .	"	7 . .	✓	
			Contingencies at 5 per cent.			40 14 8		846 .
						Rupees		6046 .

Rupees Six thousand and forty six.

Consg Archts Office
Chepauk 31st Jany
1879.

Chisholm

Consg Architect to Governmt

Medical School & Dissecting
Room at the Moregar
Choultry.

Recd

D. 452
D. 452

Estimate Rupees 6046...

Pro d/ 2-4-79 No 1021 W

Appd G.O. 1021 W – 2-4-79

Consulting Architects Office
31st January 1879

L Pub: 276/79

1021/15

№ 1021 W Public Works Department.

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 2nd April 1879

Read the following :—

Pro: in the Public Dept. (H.C. No. 452 d/ 26th March 1879)

Communicated to the Consulting Architect to Government, who will include the work in the statement of demands to be submitted during the current month.

D
2.4

The sanction accorded in the above Pro: in the Public Dept. has been registered as Provincial No: 1 B of 1878-79.

2.4

102/16

To The Consulting Archit
in [illegible] of W

Despd 21-4-79

Co 2641

Govt. of {1870} Madras.

PUBLIC WORKS.

To

Dated

Issued

Recd. Encl.

G. O., 2 April 1870. No. 1021 W

Nos. 44-48

Medical School to be erected near the Moneygar Choultry, Madras. Prog Public Dept approving the plan & Estimate for the —, comm'd to the Cons Architect.

6