Archives I—10,006—16-8·77.

(1) Number of pages 22

(2) Date of repair -6-87

(3) Initials of the Referencer

TAMIL NADU ARCHIVES

GOVERNMENT OF TAMIL NADU

P. W DEPARTMENT

G.O. No. 450-W Press.
~~B.P. No.~~ ~~Mis.~~

Dated 14-2-1879 ~~197~~

Not to be folded or roughly handled

A.K

459

GOVERNMENT OF MADRAS.

PUBLIC WORKS DEPARTMENT.

14th February 1879, No. 450 W.

Buildings and Roads.
Civil Works.

Read the following paper:—

No. 116. From the Acting Superintending Engineer, Fifth Circle, to the Chief Engineer, Public Works Department, dated Trichinopoly, 25th January 1879, No. 1,327.

I HAVE the honor to forward, herewith, a revised estimate for Rupees 2,353, and comparative statement for constructing a second-class station-house of Police at Meenbessil in the Tanjore District.

2. The original estimate for Rupees 2,045 was sanctioned in G.O., No. 966, of the 20th March 1877. This estimate was prepared by Supervisor (now Overseer) Mr. Littlewood, and was passed and countersigned by Colonel Roberts, R.E., when Superintending Engineer in Tanjore in 1875. It is now stated by Sub-Engineer Mr. Fox, under whose charge the work has been executed, that the rates allowed are too low for the particular locality, and that serious errors in the original estimate have been discovered.

3. Mr. Fox states that the rates are the same as those in more favorable parts of the district, and that in an out-of-the-way place near the coast he has had to pay higher rates.

4. Considering the locality and distance from which materials had to be procured I think the rates shown in the revised estimate are in no way excessive.

5. A comparative statement is forwarded showing the items on which an increased rate is required, and I venture to recommend that the revised estimate be sanctioned.

6. It is reported that the works which were commenced in 1877 are nearly completed, and I think Mr. Fox should have reported at an earlier date than the end of November that more funds would be required for the work.

No. 117. ORDER THEREON, 14th February 1879, No. 450 W.

THE revised estimate of Rupees 2,353 submitted with the foregoing letter is sanctioned.

2. This sanction has been registered as Provincial No. 123 B of 1878-79.

(True Extract.)

Colonel, R.E.,
Ag. Secy. to Govt., P.W.D.

To the Superintending Engineer, Fifth Circle
" Examiner of Public Works Accounts.
" Inspector-General of Police.
" Judicial Department.

Exd. C. Howarth.
Spare Copies

BUILDINGS AND ROADS.
CIVIL WORKS.

Govt. of {1879} Madras.

PUBLIC WORKS.

To

THE SUPERINTENDING ENGINEER,
FIFTH CIRCLE,
&c., &c., &c.

Dated February 14th.

Issued

Recd. *Encl.*

G. O., 14th February 1879, No. 450 W.

FEBRUARY.

Nos. 116-117.

Police Station-house at Meenbessil, Tanjore District.—Sanctions revised estimate for constructing —.

No. 1327 S.d. Supy Engrs Office 5th Circle
Trichinopoly 25th January 1879
Despd 30th

From
The Supy Engineer
5th Circle

To
The Chief Engineer
P.W. Department
Madras.

Sir,

Roads & Buildings

Encls - 2 -

I have the honor to forward herewith a Revised Estimate for Rs 2,353 and Comparative Statement for Constructing a Second Class Station House of Police at Meenberul in the Tanjore District.

The Original Estimate for Rs 2045 was sanctioned in G.O. No. 966 of the 20th March 1877. This Estimate was prepared by Supervisor (now Overseer) Mr Littlewood, and was passed and countersigned by Col. Roberts R.E. when Supy Engineer in Tanjore in 1875. It is now stated by Sub Engineer Mr Fox under whose charge the work has been executed that the rates allowed are too low for the particular locality and that serious errors in the original Estimate have been discovered.

Mr. Fox states that the rates are the same as those in more favorable parts of the District and that in an out of the way place near the Coast he has had to pay higher rates.

Considering the locality and distance from which materials had to be procured I think the rates shown in the revised Estimate are in no way excessive.

A Comparative Statement is forwarded showing the items on which an increased rate is required and I venture to recommend that the revised Estimate be sanctioned.

It is reported that the

works which were commenced in 1877 are nearly completed and I think Mr. Fox should have reported at an earlier date than the end of November that more funds would be required for the work.

I have the honor to be
Sir
your Most Obdt. Servt.
J. F. Manson
for Ag. Supg. Engineer
5th Circle.

Roads & Buildings

From
The Supg Engineer
5th Circle

To
The Chief Engineer
P.W. Department
Madras

G.O 26-12-75 No 3610
" 11-10-76 " 2729
" 18-1-77 " 166
" 2-2-77 " 357.
" 20-3-77 " 966.

No 1327
Dated 25th January 77
Despd 28th

Sm 14th Feby/77 No 450 W

Enclo - 2 -

Police Station house
at Meenbesul Jaypore
District -
Forwards Revised
Estimate & Compara=
tive Statement of

Cir 11-2-79 R13/2

45/4

Tanjore ~~TINNEVELLY~~ DISTRICT.

Negapatam DIVISION No. — Pattookotah TALUQ.

Comparative Statement shewing the difference between the Original and Revised Estimates for

Constructing a Second Class Police Station and one Head & 3 Constables huts at Minhessil

45/7

Description of work.	Units of Measurement	Original. Quantities	Original. Rate.	Original. Amount.	Revised. Quantities	Revised. Rate.	Revised. Amount.	Revised. Less than Original. Quantities	Revised. Less than Original. Amount.	Revised. In excess of Original. Quantities	Revised. In excess of Original. Amount.	Remarks.
Police huts												
Brickwork in Chunam	Cft	1233 3/4	" 23	173 7 11	1233 3/4	" 29	212 " 9 ✓	"	" " "	"	38 8 10 ✓	The excess is owing to the increased rate suitable to the locality where materials and labor are difficult to be had
Mud wall	Cyd	319 7/8	4 " "	79 15 6	318	" 7 "	139 2 " ✓	1 7/8	" " "	"	59 2 6 ✓	Owing to the increased rate as above.
Mud Plastering	Sqr	87.22	" 4 "	21 12 10	87.00	" 4 "	21 12 " ✓	"	" " 10 ✓	"	" " "	"
Flooring with Brick Jelly in mud	Do	953 3/4	" 12 "	7 2 5	9.25	" 12 "	6 15 " ✓	"	" 3 5 ✓	"	" " "	"
Roofing with bamboo reepers and pan tiles with Chunam borders	Do	1483 1/2	10 " "	148 5 7	23.00	12 " "	276 " " ✓	"	" " "	8.17 ✓	127 10 5 ✓	The excess is due to the increased rate, and certain items omitted in the original estimate
Tarring	Do	1483 1/2	1 " "	14 13 4	23.00	1 " "	23 " " ✓	"	" " "	8.17 ✓	8 2 8 ✓	Due to certain items omitted in the original estimate.
Jungle wood wrought	Cft	183 17/24	2 8 "	459 4 4	138 1/2	2 8 "	346 4 "	45 5/24	113 " 4 ✓	"	" " "	The saving is owing to the decreased quantity due to wrong calculation in the original estimate.
Batten doors 3×6	Each	4	15 " "	60 " "	4	15 " "	60 " " ✓	"	" " "	"	" " "	
Do Windows 2½×3	Do	6	8 " "	48 " "	6	8 " "	48 " " ✓	"	" " "	"	" " "	
Do Do small	Do	4	5 " "	20 " "	4	5 " "	20 " " ✓	"	" " "	"	" " "	
							1153 1/7		113 4 7 ✓		233 8 5 ✓	

45/4

Tanjore ~~TINNEVELLY~~ DISTRICT.

Negapatam DIVISION No. Pattocotah TALUQ.

Comparative Statement shewing the difference between the Original and Revised Estimates for

Constructing a Second Class Police Station and One Head & 3 Constables huts at Mimisal

Description of work.	Units of Measurement	Original			Revised.			Revised.				Remarks.
								Less than Original.		In excess of Original.		
		Quantities	Rate.	Amount.	Quantities	Rate.	Amount.	Quantities	Amount.	Quantities	Amount.	
							1153 1 9		113 4 7 ✓		233 8 5 ✓	
Tile Coping wall	Rft	171 3/4	" 1 6	16 1 7	Sft 6.87	7 " "	48 1 5 ✓	"	" " "	"	31 15 10 ✓	Due to the wrong calculation in the Original estimate.
Excavating foundation and filling in the basement	Cyd	134 3/4	" 1 3	10 8 5	138	" 1 3	10 12 6 ✓	"	" " "	3 1/4	" 4 1 ✓	
Sundries				50 8 1			88 " 4 ✓				37 8 3 ✓	
Total amount of Police huts				1110 " "			1300 " " ✓		113 4 7 ✓		303 4 7 ✓	
Abstract of the foregoing												
Amount for Station house				935 ✓			1053 " " ✓		5 10 11 ✓		123 10 11 ✓	
Do Do Police huts				1110 ✓			1300 " " ✓		113 4 7 ✓		303 4 7 ✓	
									118 15 6		426 15 6	
Total				2045			2353 " " ✓				118 15 6	Deduct
Deduct amount of Original Estimate sanctioned in G. O. No. 966 of 20th March 1877.							2045 " "				308 0 0	Excess
Net amount to be sanctioned							308 " " Excess					

45/8

Supg Engineers Office 5th Circle
28th January 1879.

G. W. Manson.
For Ag Supg Engineer
5th Circle

Tanjore ~~TINNEVELLY~~ DISTRICT.

Negapatam DIVISION No. Pattocotah TALUQ.

Comparative Statement shewing the difference between the Original and Revised Estimates for

Constructing a Second Class Police Station and one Head & 3 Constables huts at Minkessil

Description of work.	Units of Measurement	Original.			Revised.			Revised.				Remarks.
								Less than Original.		In excess of Original.		
		Quantities.	Rate.	Amount.	Quantities.	Rate.	Amount.	Quantities.	Amount.	Quantities.	Amount.	

No. from the Division office.

Pro 14-2-79 No. 450 W

B & R
Civil works

Public Works Department.

No 450 W

PROCEEDINGS OF THE MADRAS GOVERNMENT.

UNDER date the 14 Feb/79

E/10

Read the following :—

From the Supg Engineer Fifth Circle } (R.E. No 1327 of 25 Jany/79)

The revised estimate of Rs 2353 submitted with the foregoing letter is sanctioned. W 11.2.79

EAF 11/2

This sanction has been registered as Provincial No: 1531B of 1878-79.

S.E. Fifth Circle
Ex: P. W. Accts Works & Estimates
Inspr Genl of Police
Jud Dept

Desp 28-2-79

17

Cn 9th

Govt. of {1879} Madras.

PUBLIC WORKS.

17-2

To

Dated

Issued

Recd. Encl.

G. O., 14 Feby 1879, No. 450W

Nos. 116-117

Police Station House at Meenkeshb, Tinn Dt, Sanctions revised Estimate for constructing